

RESOLUTION NUMBER R- 296897

ADOPTED ON JUL 30 2002

WHEREAS, on September 24, 2001, Torrey View, LLC submitted an application to the City of San Diego for a Rezone, Community Plan Amendment, General Plan Amendment and Planned Development Permit No. 1660; and

WHEREAS, the matter was set for a public hearing to be conducted by the Council of the City of San Diego; and

WHEREAS, the issue was heard by the City Council on JUL 30 2002; and

WHEREAS, the City Council considered the issues discussed in Mitigated Negative Declaration LDR No. 41-0795; NOW, THEREFORE,

BE IT RESOLVED, by the Council of the City of San Diego, that it is certified that Mitigated Negative Declaration LDR No. 41-0795, on file in the office of the City Clerk, has been completed in compliance with the California Environmental Quality Act of 1970 (California Public Resources Code section 21000 et seq.), as amended, and the State guidelines thereto (California Code of Regulations section 15000 et seq.), that the declaration reflects the independent judgment of the City of San Diego as Lead Agency and that the information contained in the report, together with any comments received during the public review process, has been reviewed and considered by this Council in connection with the approval of the Campus at Torrey View Project.

BE IT FURTHER RESOLVED, that the City Council finds that project revisions now mitigate potentially significant effects on the environment previously identified in the Initial Study


and therefore, that the Mitigated Negative Declaration, a copy of which is on file in the office of the City Clerk and incorporated by reference, is approved.

BE IT FURTHER RESOLVED, that pursuant to California Public Resources Code section 21081.6, the City Council adopts the Mitigation Monitoring and Reporting Program, or alterations to implement the changes to the project as required by this body in order to mitigate or avoid significant effects on the environment, a copy of which is attached hereto and incorporated herein by reference.

BE IT FURTHER RESOLVED, that the City Clerk is directed to file a Notice of Determination [NOD] with the Clerk of the Board of Supervisors for the County of San Diego regarding the above project.

APPROVED: CASEY GWINN, City Attorney

By



Mary Jo Lanzafame  
Deputy City Attorney

MJL:pev  
7/11/02  
Or.Dept:DSD  
R-2003-126  
Form=mndr.frm

## EXHIBIT A

### MITIGATION MONITORING AND REPORTING PROGRAM CAMPUS AT TORREY VIEW REZONE, COMMUNITY PLAN AMENDMENT, GENERAL PLAN AMENDMENT, AND PLANNED DEVELOPMENT PERMIT NO. 1660 LDR NO. 41-0795

This Mitigation Monitoring and Reporting Program is designed to ensure compliance with Public Resources Code Section 21081.6 during implementation of mitigation measures. This program identifies at a minimum: the department responsible for the monitoring, what is to be monitored, how the monitoring shall be accomplished, the monitoring and reporting schedule, and completion requirements. A record of the Mitigation Monitoring and Reporting Program will be maintained at the offices of the Land Development Review Division, 1222 First Avenue, Fifth Floor, San Diego, CA 92101. All mitigation measures contained in the Mitigated Negative Declaration (LDR No. 41-0795) shall be made conditions of the Rezone, Vesting Tentative Map, Community Plan Amendment, General Plan Amendment, and Planned Development Permit No. 1660 as may be further described below.

#### **General Measures**

1. Prior to recordation of the permit, the owner/permittee shall deposit \$3,200.00 with the Development Project Manager of the Development Services Department to cover the City's costs associated with ensuring the implementation of the Mitigation, Monitoring and Reporting Program (MMRP).
2. Prior to issuance of any grading permits, the Environmental Review Manager (ERM) of the City's Land Development Review Division (LDR) shall verify that the following statement is shown on the grading and/or construction plans as a note under the heading, *Environmental Requirements*: "The Campus at Torrey View Project is subject to a Mitigation Monitoring and Reporting Program and shall conform to the mitigation conditions as contained in MND (LDR No. 41-0795)."
3. Prior to issuance of any grading permits, the owner/permittee shall make arrangements to schedule a pre-construction meeting to ensure implementation of the MMRP. The meeting shall include the Resident Engineer, the Paleontologist, and staff from the City's Mitigation Monitoring Coordination (MMC) Section.

#### **Aesthetics**

4. Prior to issuance of the Certificate of Occupancy, all crib/retaining walls and manufactured slopes shall be softened by vegetation (vines, trees and shrubs) to the satisfaction of City Landscape Staff.
5. Prior to issuance of the first building permit, building plans shall identify that buildings are sandstone or similar earthtone/vegetation tone in color and blend in with surrounding hillsides to the satisfaction of the City ERM.

## Hydrology/Water Quality

6. Prior to issuance of any grading permits, the Environmental Review Manager of Land Development Review (ERM of LDR) and/or the City Engineer shall verify that the following measures have been incorporated into the grading and/or landscaping plans and/or project design as appropriate:

### Construction Phase (Short Term Mitigation Measures)

- A. Prior to issuance of any grading permits, development of this project shall comply with all requirements of the State Water Resources Control Board (SWRCB) Order No. 99-08-DWQ (NPDES General Permit No. CAS000002), Waste Discharge Requirements for Discharges of Storm Water Runoff Associated With Construction Activity. In accordance with said permit, a Storm Water Pollution Prevention Plan (SWPPP) and a Monitoring Program Plan shall be developed and implemented concurrently with the commencement of grading activities, and a complete and accurate Notice of Intent (NOI) shall be filed with the SWRCB.

In addition, the permittee/owner(s) and subsequent permittee/owner(s) of any portion of the property covered by this grading permit and by SWRCB Order No. 99-08-DWQ, and any subsequent amendments thereto, shall comply with special provisions as set forth in Section C.7 of SWRCB Order No. 99-08-DWQ.

- B. The SWPPP shall identify all applicable erosion control devices to be used during construction. These may include (but may not be limited to) earthen berms, gravel bags, silt fences, temporary storm drains, desilting basins, energy dissipating devices, bladed swales, geotextile mats, plastic sheeting, and hydroseeding or other vegetation and irrigation practices. The SWPPP and grading plan shall include a drainage system which provides for implementation of Best Management Practices (BMPs) on-site to reduce construction phase runoff of pollutants into Los Peñasquitos Lagoon and other waters. Such BMPs must fulfill the intent of City Clerk Document No. 00-17068, "Erosion Control Measures for North City Areas Draining Into Los Peñasquitos or San Dieguito Lagoons" and Section 62.0419 "Protecting Water Quality in Coastal Lagoons" (City of San Diego Municipal Code).
- C. Grading plans shall clearly identify the type and location of erosion control devices to preclude any potential erosion impacts within and adjacent to the project footprint as shown on the approved Exhibit A.
- D. The SWPPP shall include a site plan on which the grading footprint (development area) is identified as shown on the approved Exhibit A. All construction activities (including staging areas) shall be restricted to the development area. Specified vehicle fueling, maintenance procedures and hazardous materials storage areas shall be clearly designated to preclude the discharge of hazardous materials used during construction (e.g., fuels, lubricants and solvents). The SWPPP shall include measures to preclude

spills and provide for the containment of any hazardous materials, including proper handling and disposal techniques and the use of temporary impervious liners to prevent soil and water contamination.

- E. The owner/permittee shall hydroseed all applicable areas within 30 days of completion of grading activities with appropriate ground cover vegetation (e.g., use of native or noninvasive plants) to the satisfaction of the ERM of LDR in conformance with the requirements of the City's Landscape Standards.

Post-Construction/Operational (Long Term Mitigation Measures)

- 8. Prior to issuance of any grading permits, the ERM of LDR shall verify that the type and location of post-construction Best Management Practices (BMPs) are clearly identified on the site plan(s). All site runoff shall be routed through grass-lined swales (or equivalent structural BMPs) prior to flowing into the public drainage system. All surface runoff shall be filtered/treated for removal of sediment, constituents absorbed by sediment, and oil/grease prior to leaving the site.
- 9. Prior to issuance of any Certificates of Occupancy, the following mitigation measures shall be incorporated into project design to the satisfaction of the ERM of LDR and the City Engineer:
  - A. All project-related drainage structures shall be adequately sized to accommodate at a minimum a 50-year flood event (provisions for other storm events may be required pursuant to direction from the City Engineer).
  - B. Surface and subsurface drainage shall preclude ponding outside of designated areas and sheet flow down slopes.
  - C. Energy-dissipating structures (e.g., detention ponds, rip rap, or drop structures) shall be used at storm drain outlets, drainage crossings, and/or downstream of all drainage channels to reduce velocity and prevent erosion.
- 10. Prior to issuance of any Certificates of Occupancy, the owner/permittee shall submit a Monitoring and Maintenance Program to assure long-term maintenance of all private drainage facilities, including detention basins and all structural and non-structural BMPs. The Monitoring and Maintenance Program shall be subject to the approval of the ERM of LDR and/or the City Engineer. The Monitoring and Maintenance Program shall include a schedule for the regular maintenance of all private drainage facilities and permanent BMPs, and shall identify the entity responsible for doing the maintenance.

## **Noise**

11. Prior to issuance of building permits, all recommendations listed in the acoustical report entitled "Torrey View Corporate Center, Environmental Noise Assessment" (Dudek, August 6, 2001) shall be shown on the building plans to the satisfaction of the City ERM and the City Engineer.
12. Prior to the issuance of the Certificate of Occupancy, an acoustical study shall be submitted by the applicant, satisfactory to the City ERM and the City Engineer. This report must show that construction materials and design have resulted in exterior noise levels for usable outdoor spaces of 70 dB or less.

## **Paleontological Resources**

13. Prior to issuance of the first grading permit, the owner/permittee shall provide a letter of verification to the ERM of LDR demonstrating that a qualified paleontologist as defined in the City of San Diego Paleontological Guidelines, has been retained to implement the monitoring program. A copy of the letter shall be submitted to Mitigation Monitoring Coordination (MMC) staff of LDR at least thirty days prior to the preconstruction meeting and shall include the names of all persons involved in the paleontological monitoring of this project.
14. Prior to the issuance of any grading permits, the ERM of LDR shall verify that the requirement for paleontological monitoring has been noted on the grading plans.
15. Prior to the commencement of any construction activities, the owner/permittee shall arrange a preconstruction meeting which includes the paleontologist, construction manager or grading contractor, resident engineer (RE), and MMC staff. The qualified paleontologist shall attend any grading-related preconstruction meetings to make comments and/or suggestions concerning the paleontological monitoring program with the construction manager and/or grading contractor. At the preconstruction meeting the paleontologist shall submit to MMC a copy of the site/grading plan (reduced to 11x17 inches) that identifies areas to be monitored. The paleontologist shall also submit a construction schedule indicating when monitoring is to occur. The paleontologist shall notify MMC staff of the start and end of monitoring.
16. In the event of a significant paleontological discovery, and when requested by the paleontologist, the City RE shall divert, direct, or temporarily halt construction activities in the area of discovery to allow recovery of fossil remains. The determination of significance shall be at the discretion of the qualified paleontologist. The paleontologist with principle investigator level evaluation responsibilities shall also immediately notify MMC staff of such finding at the time of discovery. MMC staff will provide information regarding appropriate LDR staff contact for consultation.
17. The paleontologist shall be responsible for preparation of fossils to a point of curation and submittal of a letter of acceptance from a local qualified curation facility as defined by the City of San Diego Paleontological Guidelines. If the fossil

collection is not accepted by a local qualified facility for reasons other than inadequate preparation of specimens, the project paleontologist shall contact LDR to suggest an alternative disposition of the collection.

18. The paleontologist shall be responsible for the recordation of any discovered fossil sites at the San Diego Natural History Museum.
19. Prior to the release of the grading bond, two copies of the monitoring results report which describes the results, analysis, and conclusions of the above monitoring program (with appropriate graphics) shall be submitted to MMC for approval by the ERM of LDR. A copy of the monitoring report shall be forwarded to the City field engineer assigned to the project. The reports shall be submitted even if the monitoring program yields no findings.

### **Transportation/Circulation**

20. Prior to the issuance of the building permit, the applicant shall provide a traffic signal at the project's driveway and Carmel Mountain Road with an interchange between Vista Sorrento Parkway/Torrey View Court and the future I-5 /Carmel Mountain Road Interchange, satisfactory to the City Engineer.
21. Prior to the issuance of the building permit, the applicant shall construct a 250-foot, eastbound, left-turn lane plus transition at the project's driveway and Carmel Mountain Road, satisfactory to the City Engineer.
22. Prior to the issuance of the building permit, the applicant shall provide a minimum 44-foot wide pavement at the project's main entrance, satisfactory to the City Engineer.
23. Prior to issuance of the building permit, the applicant shall construct a westbound right-turn lane at the intersection of Carmel Mountain Road/I-5 Northbound on/off ramps, satisfactory to the City Engineer.
24. Prior to issuance of the building permit, the applicant shall transfer the appropriate average daily trips to support the proposed project, satisfactory to the City Engineer.