

REQUEST FOR COUNCIL ACTION CITY OF SAN DIEGO	CERTIFICATE NUMBER (FOR COMPTROLLER'S USE ONLY)
--	--

TO: CITY COUNCIL	FROM (ORIGINATING DEPARTMENT): Planning	DATE: 4/8/2015
---------------------	--	-------------------

SUBJECT: Grantville Focused Plan Amendment

PRIMARY CONTACT (NAME, PHONE): Seth Litchney, (619) 236-6892, MS 413	SECONDARY CONTACT (NAME, PHONE): Brian Schoenfisch, (619) 533-6457, MS 413
---	---

COMPLETE FOR ACCOUNTING PURPOSES

FUND					
FUNCTIONAL AREA					
COST CENTER					
GENERAL LEDGER ACCT					
WBS OR INTERNAL ORDER					
CAPITAL PROJECT No.					
AMOUNT	0.00	0.00	0.00	0.00	0.00

FUND					
FUNCTIONAL AREA					
COST CENTER					
GENERAL LEDGER ACCT					
WBS OR INTERNAL ORDER					
CAPITAL PROJECT No.					
AMOUNT	0.00	0.00	0.00	0.00	0.00

COST SUMMARY (IF APPLICABLE):

ROUTING AND APPROVALS

CONTRIBUTORS/REVIEWERS:	APPROVING AUTHORITY	APPROVAL SIGNATURE	DATE SIGNED
Liaison Office	ORIG DEPT.		
Environmental Analysis	CFO		
	DEPUTY CHIEF		
	COO		
	CITY ATTORNEY		
	COUNCIL PRESIDENTS OFFICE		

PREPARATION OF: RESOLUTIONS ORDINANCE(S) AGREEMENT(S) DEED(S)

Approval of an amendment to The Navajo Community Plan, adoption of a Rezone Ordinance to implement the Community Plan, Certification of the Program Environmental Impact Report Sch. No 2013111017, and Adoption of the Findings, a Statement of Overriding Considerations, and a Mitigation, Monitoring and Reporting Program.

STAFF RECOMMENDATIONS:
Approve Requested Actions

SPECIAL CONDITIONS (REFER TO A.R. 3.20 FOR INFORMATION ON COMPLETING THIS SECTION)

COUNCIL DISTRICT(S): 7

COMMUNITY AREA(S):	Navajo
ENVIRONMENTAL IMPACT:	The City of San Diego, as Lead Agency under CEQA has prepared and completed an Environmental Impact Report Project No. 346289/Sch. No. 2013111017, dated May 2015, and Mitigation, Monitoring and Reporting Program covering this activity.
CITY CLERK INSTRUCTIONS:	Please forward all final resolutions and ordinances to Seth Litchney, MS 413

COUNCIL ACTION
EXECUTIVE SUMMARY SHEET
CITY OF SAN DIEGO

DATE: 4/8/2015

ORIGINATING DEPARTMENT: Planning

SUBJECT: Grantville Focused Plan Amendment

COUNCIL DISTRICT(S): 7

CONTACT/PHONE NUMBER: Seth Litchney/(619) 236-6892, MS 413

DESCRIPTIVE SUMMARY OF ITEM:

The Grantville Focused Plan Amendment (FPA), developed through significant public outreach, seeks to revitalize approximately 280 acres within the Navajo Community Planning Area. Objectives of the Grantville FPA include: to promote Transit Oriented Development (TOD) within walking distance to the Grantville Trolley Station, promote revitalization of properties which are underutilized; promote a multi-modal transportation strategy including walkable and bicycle-friendly streets; provide additional market-rate and affordable housing opportunities consistent with a land use pattern that promotes infill development; and facilitate implementation of the San Diego River Park Master Plan.

STAFF RECOMMENDATION:

Approve Requested Actions

EXECUTIVE SUMMARY OF ITEM BACKGROUND:

The Grantville Focused Plan Amendment (project) would amend the Navajo Community Plan to promote Transit Oriented Development (TOD) land uses, regulations, and policies, focused within the Grantville neighborhood. The project would be consistent with and further implementation of the adopted City General Plan by capitalizing on Grantville's proximity to public transit by concentrating new housing density and commercial uses in the area around the Grantville Trolley Station, thereby supporting regional mobility goals to encourage development around Village Centers, promote the use of public transportation, and reduce vehicle trips and infrastructure costs.

The Grantville Focused Plan Amendment area consists of approximately 280 acres within the Navajo Community Planning area and is comprised mainly of commercial and industrial uses. Because of the age and declining physical condition of the industrial properties and often converted use of these industrial properties to office or storage facilities, this area was identified by the General Plan's Strategic Framework Element as prime for neighborhood revitalization with a more lively mix of land uses better suited to residents and the Navajo Community.

Mission Gorge Road, which provides a primary access route south from Friars Road to the Grantville Trolley Station, is developed with a mix of mostly older, underutilized commercial and industrial buildings containing a variety of auto-dependent commercial service uses. Many properties in the area are occupied by outdated and deteriorated buildings, lack adequate parking and landscaping, and are in need of substantial capital reinvestment to stimulate economic development and create a more attractive and pleasant environment. In 2005, a new Grantville Trolley Station opened in the Navajo Community on Alvarado Canyon Road. Over time as ridership continues to increase, it is anticipated that the trolley station will contribute to an

enhanced quality of life, a reduction in additional traffic congestion, improved local air quality, and an opportunity for residents and visitors to engage in more frequent pedestrian-oriented and transit-reliant trips.

A shift in land uses from industrial to a mix of land uses including employment, commercial, higher density residential, and civic uses would allow many of the properties containing outdated buildings to be better utilized. This would add more transit-served residential, workforce housing, and local neighborhood retail, as well as new commercial and employment opportunities to the area. Over time, underutilized areas of Grantville would shift away from industrial uses to uses that serve the needs of current and projected future market conditions. Industrial uses will continue to be designated in Navajo further to the north along Mission Gorge Road. These uses will be concentrated in a technology park, currently envisioned for future development and where the high quality design guidelines and development standards of the Mission Gorge Road Industrial CPIOZ can be accomplished.

The Grantville Focused Plan Amendment is intended to encourage transit oriented developments which will minimize the need for an over reliance on automobiles and emphasize pedestrian orientation and proximity to public transit. It includes supplemental development regulations which reinforce the concept of an interconnection between development projects and the surrounding public transit system through significant physical and functional integration of project components, site design, and the provision of pedestrian and bicycle infrastructure. As development and redevelopment occurs over time, the plan envisions an elaborate pedestrian and bicycle circulation network linking new mixed use developments to the Grantville Trolley Station.

CITY STRATEGIC PLAN GOAL(S)/OBJECTIVE(S):

Goal #2: Work in partnership with all of our communities to achieve safe and livable neighborhoods

Objective #3: Invest in infrastructure

Objective #5: Cultivate civic engagement and participation

Goal #3: Create and sustain a resilient and economically prosperous City

Objective #1: Create dynamic neighborhoods that incorporate mobility, connectivity, and sustainability

FISCAL CONSIDERATIONS:

Adoption of the public facilities financing plan will provide a portion of the funding for the required public facilities. Portions of project costs not funded by new development through impact fees will need to be identified by future City Council actions in conjunction with the adoption of annual Capital Improvement Program (CIP) budgets.

EQUAL OPPORTUNITY CONTRACTING INFORMATION (IF APPLICABLE):

Not Applicable

PREVIOUS COUNCIL and/or COMMITTEE ACTION (describe any changes made to the item from what was presented at committee):

On June 12, 2007, the City Council voted 8-0 to initiate the amendment to the Navajo Community Plan, Resolution # R-302730.

COMMUNITY PARTICIPATION AND PUBLIC OUTREACH EFFORTS:

A comprehensive community outreach process took place between 2007 and 2015. At the outset of the process in 2007, the Grantville Stakeholders Committee was established to represent the various interests in the Grantville neighborhood. The Stakeholders Committee held a total of 26 public meetings between 2007 and 2015. Additional outreach included a neighborhood walking tour, a 3-day charrette process, a visual preference survey, a public opinion survey, as well as monthly updates to the Navajo Community Planning Group.

KEY STAKEHOLDERS AND PROJECTED IMPACTS:

The Grantville Stakeholders Committee, Navajo Community Planning Group, and affected property owners, residents, business owners, public and private institutions in and adjacent to the Grantville neighborhood.

Originating Department

Deputy Chief/Chief Operating Officer



THE CITY OF SAN DIEGO
REPORT TO THE CITY COUNCIL

DATE ISSUED: May 5, 2015 **REPORT NO. 15-042**

ATTENTION: Smart Growth and Land Use Committee, Agenda of May 13, 2015

SUBJECT: Grantville Focused Plan Amendment

Issue: Should the Smart Growth and Land Use Committee recommend to the City Council approval of the Grantville Focused Plan Amendment?

Staff Recommendation: Staff recommends that the Smart Growth and Land Use Committee forward the Grantville Focused Plan Amendment to City Council with a recommendation of approval based on the information contained in this report and the evidence offered as part of the public hearing.

Requested Actions:

1. Recommend to the City Council **Approval** of a resolution amending the Navajo Community Plan and General Plan.
2. Recommend to the City Council **Approval** of a rezone ordinance to implement the Grantville Focused Plan Amendment.

Community Participation and Outreach Efforts:

On February 25, 2015, the Navajo Community Planning Group voted 14-2 to support the Focused Plan Amendment and Rezone. On February 11, 2015, the Grantville Stakeholders Committee voted 9-1 to support Focused Plan Amendment and Rezone.

City Strategic Plan Goal(s)/Objective(s):

The Grantville Focused Plan Amendment is consistent with the following City of San Diego Strategic Plan goals and objectives:

- Goal #2: Work in partnership with all of our communities to achieve safe and livable neighborhoods.
 - Objective #3: Invest in infrastructure.
 - Objective #5: Cultivate civic engagement and participation.
- Goal #3: Create and sustain a resilient and economically prosperous City.
 - Objective #1: Create dynamic neighborhoods that incorporate mobility, connectivity, and sustainability.

Fiscal Considerations: Adoption of the public facilities financing plan will provide a portion of the funding for the required public facilities. Portions of project costs not funded by new development through impact fees will need to be identified by future City

Council actions in conjunction with the adoption of annual Capital Improvement Program (CIP) budgets.

Housing Impact Statement: A total of 8,275 additional residential dwelling units would be allowed within the Grantville Focused Plan Amendment area for a maximum build out of approximately 37,734 residential dwelling units within the Navajo community planning area.

EXECUTIVE SUMMARY OF ITEM BACKGROUND

The Navajo community planning area is approximately 8,000 acres in size and is located in the easterly portion of the City of San Diego (Attachment 1). The Grantville Focused Plan Amendment (FPA) area is located within the Navajo community planning area east of Interstate 15 (I-15) and north of Interstate 8 (I-8); bounded by the Admiral Baker Golf Course to the north and the San Diego River to the west. The FPA area consists of approximately 280 acres and is comprised mainly of light industrial, commercial, and office uses.

The Navajo Community Plan was adopted by the San Diego City Council on December 7, 1982 (Attachment 2). The plan has been amended eight times, including the Grantville Amendment on April 4, 1989, which provided design guidelines and established supplemental development regulations for industrial properties in Grantville.

Much of Grantville is currently developed with a mix of mostly older, underutilized commercial and industrial buildings containing a variety of auto-dependent commercial service uses. Many properties in the area are occupied by outdated and deteriorated buildings, lack adequate parking and landscaping, and are in need of substantial capital reinvestment to stimulate economic development and create a more attractive and pleasant environment. Existing industrial zoning and supplemental development regulations have not adequately accomplished the objective of the 1989 Grantville Amendment, which was intended to “encourage industrial development and redevelopment which will capitalize on the area’s central location within the metropolitan area.”

Because of the age and declining physical condition of Grantville’s industrial properties and often converted use of these industrial properties to office or storage facilities, this area was identified by the General Plan’s Strategic Framework Element (2002) as prime for neighborhood revitalization with a more lively mix of land uses to better serve the surrounding community and the City at large.

DISCUSSION

The Grantville neighborhood of the Navajo community planning area was established as a Redevelopment Project Area in May 2005. In 2007, in order to leverage the significant regional investment in the new light rail Grantville Trolley Station and the anticipation of redevelopment tax increment funding for additional infrastructure, community stakeholders worked with City officials to initiate the preparation of a comprehensive master plan for the Grantville area. On June 12, 2007, the City Council initiated an

amendment to the Navajo Community Plan to evaluate transit oriented development around the Grantville Trolley Station; identify appropriate future land uses and intensities; address circulation, parks and open space, public facilities and urban design. With the dissolution of redevelopment in 2012, the Grantville FPA process was temporarily put on hold while the community stakeholders and City officials contemplated whether to go forward post-Redevelopment. In late 2013, it was decided to continue the Grantville FPA process in order to carry on with the efforts towards neighborhood revitalization, despite the impacts of the loss of Redevelopment.

The proposed Grantville FPA was developed through a comprehensive community outreach process which took place between 2007 and 2015. At the outset of the process in 2007, the Grantville Stakeholders Committee was established to represent the various interests in the Grantville neighborhood, including property owners, business owners and interested citizens. The City had solicited members by sending notices to every property owner and tenant in the FPA area. The stakeholders committee held a total of 26 public meetings between 2007 and 2015. Additional public outreach included a neighborhood walking tour, a 3-day charrette process, a visual preference survey, and a public opinion survey, as well as monthly updates at the Navajo community planning group meetings.

Through the extensive outreach process a number of key objectives were developed, including: to promote transit oriented development within walking distance to the Grantville Trolley Station; promote revitalization of properties which are underutilized; promote a multi-modal transportation strategy including walkable and bicycle-friendly streets; provide additional market-rate and affordable housing opportunities consistent with a land use pattern that promotes infill development; and facilitate implementation of the San Diego River Park Master Plan.

The proposed Grantville FPA consists of three key actions: 1) an amendment to the Navajo Community Plan, 2) a rezone ordinance, and 3) an amendment to the Navajo Public Facilities Financing Plan. The amendment to the Navajo Community Plan is comprised of the following components: the re-designation of land uses and intensities within the Grantville FPA area; the replacement of the existing Grantville Community Plan Implementation Overlay Zone (CPIOZ) supplemental design regulations for industrial development with supplemental design regulations for mixed-use development; a comprehensive update to the Park and Recreation Element to include an additional 72.46 acres of park land identified for future acquisition and development; and a comprehensive re-formatting of the community plan to consolidate the existing supplemental design regulations for five distinct CPIOZ areas into one element. Further, additional clean-up changes were made to the Navajo Community Plan to incorporate six previously-adopted community plan amendments into the document (Attachments 3-7).

A key component of the Grantville FPA is the CPIOZ supplemental design regulations. These regulations are intended to encourage transit oriented developments which will minimize the need for an over reliance on automobiles and emphasize pedestrian orientation and proximity to public transit. Further, in order to address conditions along Alvarado Creek, which in its current state presents a barrier to the revitalization of Grantville rather than an opportunity as a usable public amenity, the supplemental design regulations provide specific requirements to facilitate pedestrian and bicycle connectivity

and to ensure that development does not turn its back on the Creek. Additionally, to address the Creek's occasional flooding issues, the City of San Diego recently submitted a SANDAG Smart Growth Incentive Program grant application aimed at facilitating the comprehensive restoration of the creek corridor.

The Grantville FPA involves a rezone ordinance which, over time, is intended to facilitate a transition of the FPA area from predominately single-use industrial and commercial development to high intensity mixed-use commercial and residential uses which promote transit oriented development. Specifically, the rezone ordinance includes the following zones:

- RM-3-7 would allow a mix of medium high residential density (up to 44 dwelling units per acre) with limited neighborhood serving commercial uses with a pedestrian orientation.
- CC-2-5 would allow high intensity community serving commercial uses and prohibit residential development. The application of this zone is limited to the freeway edge of the community.
- CC-3-6 would allow a mix of medium high density residential (up to 44 dwelling units per acre) with community commercial with a pedestrian orientation.
- CC-3-8 would allow a mix of high density residential (up to 73 dwelling units per acre) with community commercial with a pedestrian orientation.
- CC-3-9 would allow a mix of high density residential (up to 109 dwelling units per acre) with community commercial with a pedestrian orientation.
- OF-1-1 would increase the open space-floodplain zone along the San Diego River by approximately 2 acres.

The application of the above zones, together with the amended Grantville CPIOZ supplemental design regulations, will serve as the implementation tools to achieve the goals of the proposed Grantville FPA. It is anticipated that the transition from Grantville's current land uses to mixed use transit oriented development would occur through incremental implementation as individual properties are redeveloped. Existing uses that are no longer permitted based on updated land use designations and zoning become previously conforming uses. A previously conforming use can continue as it currently exists, be maintained, and be bought and sold. Chapter 12, Article 7, Division 1 of the Municipal Code provides additional information on previously conforming uses.

CONCLUSION

The proposed Grantville Focused Plan Amendment would amend the Navajo Community Plan to promote transit oriented development land uses, regulations, and policies, focused within the Grantville neighborhood. The CPIOZ includes supplemental development regulations to reinforce the concept of an interconnection between development projects and the surrounding public transit system through significant physical and functional integration of project components, site design, and the provision of pedestrian and bicycle infrastructure. The accompanying rezone ordinance is intended to facilitate a shift in land uses from industrial to a mix of employment, commercial, higher density residential and civic uses. This would add more transit-served residential, workforce housing, and local neighborhood retail, as well as new commercial and employment opportunities to the

area. Further this would facilitate implementation of the General Plan City of Villages Strategy by capitalizing on Grantville's proximity to public transit, concentrating new housing density and commercial uses in the area around the Grantville Trolley Station, thereby supporting regional mobility goals to encourage development around village centers, promote the use of public transportation, and reduce vehicle trips and infrastructure costs.



Brian Schoenfisch
Principal Planner

Attachments:


1. Navajo/Grantville Location Map
2. Existing Navajo Community Plan Land Use Map
3. Proposed Navajo Community Plan Land Use Map
4. Existing Grantville Land Use Map
5. Proposed Grantville Land Use Map
6. Proposed Rezone Map (areas to be rezoned)
7. DRAFT Navajo Community Plan

Attachment 1 – Navajo/Grantville Location Map




SOURCE: 2014, SanGIS, 2014; City of San Diego, 2014

Attachment 2 – Existing Navajo Community Plan Land Use Map



Navajo Community Land Use

Attachment 3 – Proposed Navajo Community Plan Land Use Map



LAND USE		
Single Family	Sand & Gravel	Residential - Medium High (30-43 DU/AC)
3-4 DU/NRA Very Low	Park	Community Commercial
5-9 DU/NRA Low	Mission Trails Regional Park	Community Commercial-Residential (30-43 DU/AC)
Multi-Family	Open Space	Community Village (44-73 DU/AC)
10-14 DU/NRA Low Medium	E Elementary School	Urban Village (44-108 DU/AC)
15-28 DU/NRA Medium	J Junior High School	Business Park - Residential (44-73 DU/AC)
30-43 DU/NRA Medium High (NRA-Net Residential Area)	S Senior High School	Open Space
Mixed Use	Fire Station	Proposed LRT Route
Commercial	Library	
Office	H Hospital	
Industrial	G Golf Course	
	Future Study Area	
	Lake Murray	


Navajo Community Land Use

Attachment 4 – Existing Grantville Land Use Map



SOURCE: 2014, SanGIS, 2014; City of San Diego, 2014


Attachment 5 – Proposed Grantville Land Use Map



Attachment 6 – Proposed Rezone Map



CITY OF SAN DIEGO • DEVELOPMENT SERVICES
PROPOSED REZONING



Grantvill Rezone		CASE NO.
ORDINANCE NO. _____	REQUEST VARIOUS	
EFF. DATE ORD. _____	PLANNING COMM. RECOMMENDATION	DEVELOPMENT SERVICES MANAGER
ZONING SUBJ. TO _____	CITY COUNCIL ACTION	B- 4308
BEFORE DATE _____		APN: VARIOUS
EFF. DATE ZONING _____		(227-1737) 2-12-15 Ldj
MAP NAME AND NO. _____		

NAVAJO COMMUNITY PLAN

ADOPTION DRAFT May 2015

Prepared by the

NAVAJO COMMUNITY PLANNERS

and

THE CITY OF SAN DIEGO

CITY OF SAN DIEGO PLANNING DEPARTMENT



Printed on recycled paper.

This information, or this document (or portions thereof), will be made available in alternative formats upon request.

NAVAJO COMMUNITY PLAN AMENDMENTS

The following amendments have been incorporated into this February 2008 posting of this plan:

Amendment	Date Adopted by City Council	Resolution Number
Navajo Community Plan adopted	December 7, 1982	R-257606
Grantville Amendment- updates existing conditions, provides design guidelines, and establishes supplemental development regulations	April 4, 1989	R-273164
The Circulation and Public Transportation Element was added	August 5, 2002	R-296956
Centerpoint at Grantville	May 15, 2007	R-302636
Archstone at Mission Gorge	November 18, 2008	R-304443
Pasatiempo	February 6, 2012	R-307260
Shawnee – Riverbend	October 2, 2012	R-307718
Village at Zion	February 26, 2013	R-308010
San Diego River Park Subdistrict	May 20, 2013	R-308199
Grantville Focused Plan Amendment	-	-



MAYOR

Pete Wilson

COUNCIL

Bill Mitchell
Bill Cleator
Susan Golding
Leon William
Ed Struiksma
Mike Gotch
Dick Murphy
Lucy Killea

CITY ATTORNEY

John W. Witt

CITY MANAGER

Ray T. Blair, Jr.

PLANNING COMMISSION

John G. Davies, Chairman
Dorothy Leonard, Vice Chairman
Ron Roberts
Marie Widman
Fil Chavez
Yvonne Larsen
Paula Oquita

PLANNING DEPARTMENT

Jack Van Cleave, Director
Mike Stepner, Assistant Director
James L. Overstreet
Steve Tallian
Mary Holt
Byron Frohn
Tony Pluth
Lisa Goehring

NAVAJO COMMUNITY PLANNERS, INC.

James A. McIntyre, President
Donald M. Robinson, 1st Vice President
Judy McCarty, 2nd Vice President
Hal Boaz
James H. Cusack
Dave Futch
Donald C. Heffner
Bill Myers
Peder Norby

Bob Osmer
Herbert Phillips
Mary Plichta
Phyllis Porter
Lou Quintali
Karen Sue Sweeting
John Todd
Jerry Wetter
Henry Wilson

In addition to the Navajo Community Planners, the following City Department staff has made a significant contribution to development of the Navajo Community Plan.

PARK & RECREATION

Mason Milliken

TRANSPORTATION PLANNING

Allen Holden

We also wish to thank J. V. Ward, San Diego Unified School District.

ILLUSTRATION CREDITS

Unless otherwise noted, illustrations are by the City of San Diego Planning Department.

Pages 22, 35, 119

Community Design Manual Fremont General Plan Program, Williams Cook and Mocine, City and Regional Planning San Francisco, California, 1967

Pages 35, 88

Dale Nagle Architect, La Jolla California

Page 88

The Visual Environment of Los Angeles Department of City Planning, Los Angeles, California, April 1971

Page 107

Toward a Better Tomorrow, a Transportation Report for Southern California by the Automobile Club of Southern California, Highway Engineering Department, 1971

Page 120

Lysander, New Community Final Planning Report submitted to the New York Urban Development Corporation by David A. Crane and Associates, January, 1971



THE CITY OF
SAN DIEGO

CITY ADMINISTRATION BUILDING • 202 C STREET • SAN DIEGO, CALIF 92101

July 29, 1982

The Honorable Mayor and City Council
The City Planning Commission
City of San Diego, California

Herein transmitted is the revision to the Navajo Community Plan. This revision represents a comprehensive, long-range policy guide for the physical development of this community and is intended to replace the community plan adopted by the City Council on November 7, 1973.

In June of 1971, the Navajo Community Planners came into existence with the endorsement of the City Council and City Planning Commission. The Committee's purpose is to represent the Navajo area, composed of the communities of Allied Gardens, Grantville, Del Cerro and San Carlos, and to work with the City Manager's office and City Planning Department in a cooperative effort to develop and maintain a plan reflecting the goals and the aspirations of the citizens of the community.

The Committee has met regularly with City staff, numerous agencies and individuals directly concerned with the future of the area, and with the citizens at large in well attended public meetings, the result of which is a revised document expressing a cross-section of community and City opinions. Involvement and expertise have been combined to produce a series of working solutions, all based on the assumption that Navajo will continue to grow as a healthy, predominantly single-family, yet varied area in which to live and to work.

The Plan is a vitally needed step in realizing the development potential of Navajo for present and future residents of the community, as well as for the people of the City at large. It is recommended that the Planning Commission and the City Council adopt the Plan as revised to serve as a comprehensive policy framework for the long-range development of the Navajo community area.

Respectfully submitted,

Jack Van Cleave
Planning Director

NAVAJO COMMUNITY PLANNERS, INC.

P.O. BOX 20304, SAN DIEGO, CALIFORNIA 92120

Dear Community Resident:

The goal of the Navajo Community Planners is a Plan which provides for the health, safety and welfare of the existing and future residents and maintains the area as a desirable neighborhood in which to live.

The Plan is a cross section of community options and desires blended with professional knowledge and sound planning policy. Throughout many months the volunteer members of the Community Planning Board met with the City Planning Department Staff in workshops with representatives of various City, School and State Departments. Many ideas and concepts were considered and refined to meet the needs of the community, some were rejected. The Plan presented is a comprehensive, long-range policy guide for the Navajo Community. It discusses residential, commercial, industrial, open space, circulation, environmental and community facilities in terms of existing conditions, states projected needs, objectives and proposals for each.

We hope you will take advantage of the detailed information to better understand the suggestions for the future of the community. For the Plan to serve as a useful document statements were made as precise as possible. Often it became necessary to use special phrasing and planning vocabulary. A section of definitions and concepts has been included to more clearly establish the concepts as worded in the text. Tables, charts, etc. were included where necessary for explanation and reference. The end result does give the Plan a technical textbook appearance, but it does make material available where and when it is needed.

The Navajo Community Plan is simply a first step in the never-ending desire of the citizens to participate in the destiny of their community. We are grateful for your interest in the community and hope you will actively support and participate in the community planning process.

Respectfully,

NAVAJO COMMUNITY PLANNERS

Table of Contents

INTRODUCTION

Preface..... 1

Physiography..... 3

Background..... 5

Existing Land Use and Zoning 7

Population characteristics 10

Residential..... 11

Commerical..... 17

Industrial 22

Community Plan Implementation Overlay Zone (CPIOZ)..... 24

Shawnee CPIOZ..... 26

Grantville CPIOZ..... 31

Mission Gorge Road Industrial CPIOZ 48

Mission Gorge Road Residential CPIOZ..... 55

San Diego River Park Subdistrict CPIOZ..... 58

Open Space Retention and utilization..... 69

Parks & Recreation Facilities..... 76

Public Schools..... 93

Other Community Facilities..... 99

Circulation..... 104

Public Transportation..... 106

Bicycles..... 109

Streets..... 113

Community Environment..... 121

Implementation	126
Conclusion	136
Standards and Definitions	137

TABLES

TABLE 1: Density Ranges	12
TABLE 2: Site and Trade Population Standards For Commercial Centers.....	18
TABLE 3: Grantville CPIOZ Street Tree Plan.....	45
TABLE 4: Mission Gorge Road Industrial CPIOZ Street Tree Plan.....	52
TABLE 5: River Influence Area Setback, Height and Massing.....	64
TABLE 6: Summary Of Existing And Future Population-Based Parks And Recreation Facilities	84
TABLE 7: Summary Of Population-Based Parks, Recreation Facilities And Park Equivalencies For Full Community Development	85
TABLE 8: Optimum School Enrollment And Usable Site Area Standards (San Diego Unified School District).....	94
TABLE 9: Existing Educational Facilities	95

INTRODUCTION

PREFACE

The Navajo area of San Diego is approximately 8,000 acres in size and is located in the easterly portion of the City of San Diego. It includes the community areas of Allied Gardens, Del Cerro, Grantville and San Carlos. It is bounded on the north by Mission Gorge, on the east by the cities of El Cajon and La Mesa, on the south by Highway 8 and on the west by the San Diego River channel.

Navajo is conveniently located within the metropolitan area. Employment and shopping are readily accessible within the community and in nearby areas. Grantville, a subregional employment area, is located within the westerly portion of the community. The Kearny Mesa industrial area, another major employment center, is somewhat farther away, but still convenient to the residents of Navajo. These areas, plus downtown employment centers, are quite accessible by major streets and freeways. In addition to the many industrial facilities within and close to the study area, regional and community shopping centers are located within Navajo and in nearby Kearny Mesa, Mission Valley, La Mesa, El Cajon and downtown San Diego.

The overriding objectives for the long-range development of Navajo are to retain the residential character of the area, provide adequate community services such as police and fire protection, rubbish collection, etc., establish guidelines for the utilization of canyons and hillsides, and enhance the environment of the area as a pleasant, livable, walkable community. To assist in accomplishing these objectives, this community plan provides guidelines for public and private development to the year 2000. The Plan represents a policy framework that will enable the community and the City to work jointly on more specific studies and action programs. The Plan is only an initial step.

The need for a flexible document is acknowledged. Nothing can be rigid in view of changing life styles, needs, and technology. However, the recommendations as expressed in this Plan, together with the planning principles, should not be allowed to be eroded by individual interpretations but should be kept intact and followed unless amended by due process.

The Plan discusses the community environment and major land uses: residential, commercial, open space, industrial, community facilities, and circulation. Elements are presented in terms of existing conditions, development potential or projected needs, objectives and proposals. A Plan map presents a composite of all major land use proposals. Finally, the Plan concludes with an implementation section which sets forth major projects, public and private, needed to carry out the Plan.

Periodic updating of the Plan will be necessary as conditions in the community change. Once adopted by Council, any amendments, additions or deletions from the document will require that the Planning Commission and the City Council follow the same procedure of holding public hearings as was followed in adopting the Plan originally. Future decisions affecting the environment of the area will be based on the general objectives above as well as the specific recommendations that follow.




FIGURE 1: LOCATOR

PHYSIOGRAPHY


The community is characterized by a wide variety of natural features typical of many other San Diego areas, including flat mesas, steep canyons, and rolling hills. The most prominent feature in the area is Cowles Mountain. Elevations within the community range from a low of around 100 feet above sea level at the westerly edge of Mission Gorge to 1,591 feet at the peak of Cowles Mountain, the highest point in the City.

Within the slopes of Cowles Mountain, there are approximately 4,250 acres of undeveloped land. Approximately 2,230 acres of this land are in steep slopes of 35 percent or greater; 1,070 acres have slopes of 15-35 percent; and the remaining 950 acres are relatively level with slopes of less than 15 percent. Natural vegetation in the community consists mostly of chaparral, sage, and other cover typical of semiarid regions, with some oak and sycamore trees in the canyons. The soil composition is basically alluvium, slope wash and sedimentary rocks. The high quality hard blue rock located in Mission Gorge is processed into sand and gravel by commercial enterprises.

Three sedimentary formations exist in areas of the community that, when combined, form an unstable soil condition. This unstable condition can be responsible for groundwater seepage and landslides. Measures should be taken when development is proposed in these areas that would reduce the geological hazard impacts to a level of insignificance. One such measure is the application of the Geologic Hazard Overlay category. The overlay identifies areas that, where such soil conditions exist, the developer is to provide an as-built geologic report prior to issuance of building permits by the City, and is required to provide homeowner warranties against landslides for a period of ten years following the first sale of any developed property (Council Resolution No. R-254954 adopted August 31, 1981).

There are several unique features in the area. Mission Gorge on the north is the site of the early Mission Dam and is a state historical landmark. Centered in the southeastern part of the community is Lake Murray, a City-owned reservoir which also serves as a recreation facility. The lake, proposed for continued aquatic recreational use, contains 140 surface acres of water surrounded by approximately 416 acres of City-owned land. A public golf course is located within this area.

Natural runoff from the community drains into the San Diego River to the north and west and Alvarado Canyon to the south. The natural groundwater of the San Diego River is being used by the sand and gravel processors. The river is subject to flooding that, of course, should be considered when allocating land use for the floodplain. Rainfall in the area is slightly less than ten inches a year, which is consistent with the overall San Diego average



GRANTVILLE FROM KENSINGTON 1927
 Historical collection, Title Insurance and Trust Company, San Diego, Ca.

FIGURE 2: TOPOGRAPHY

BACKGROUND

The study area is closely tied to early California history. Navajo has always been a prime location in the San Diego area--near water, in the vicinity of good land for cultivation and at the crossroads of five major trails: the Mission Trail (now known as Friars Road), Murphy Canyon Road, Yard Road, Alvarado Trail and Mission Gorge Road. California's first mission was located on the Rancheria Nipaguay, adjacent to the area, probably because of the choice location.

Formal dedication of the Presidio of San Diego de Alcalá by Father Junipero Serra occurred on July 16, 1769. The City of Saint Didacus began to produce changes on the landscape. The good Fathers needed a guaranteed supply of water; thus, the first irrigation project in California was begun. From 1812 to 1816, Indian laborers constructed what is known as the Old Mission Dam in Mission Gorge with a six-mile transmission ditch to the Mission.

In 1835, the Missions were secularized by the Mexican Government. At that time, Mission Ranch of San Diego de Alcalá encompassed 58,875.38 acres. It was the second largest Rancho in San Diego County, extending eastward from the San Diego Pueblo boundary to El Cajon Rancho, and northward from Rancho de la Nacion to what is now Miramar Naval Air Station.

Before secularization, the area (El Cajon Rancho) was included in the lands of the San Diego Mission and was one of the Mission's most valuable grazing areas. As defined by an early land commission, this rancho extended northeasterly from La Mesa to a point north of the San Diego River above El Monte Park and over the area now occupied by El Cajon, Bostonia, Santee, Lakeside and Flinn Springs.

In 1887, plans for a town site were laid out by the Junipero Land and Water Company. Plans for a Soldier's Home to be located at Grant Circle were included. The official name registered with the post office was Orchard, but the area became known as Grantville in honor of President U. S. Grant.

In 1948, the so-called Waring Tract, comprising approximately 460 acres, was annexed to the City of San Diego. Following this, the Southern Title and Trust Company Tract was annexed in 1951. This second annexation covered 1,152 acres and was subsequently developed as Allied Gardens. Waring Tract No.2 was annexed in 1954. This annexation was one of the largest in the City of San Diego and consisted of almost 5,000 acres.

The San Carlos and Del Cerro communities have been developed within this area. Since the Waring Tract No.2 annexation there have been numerous smaller annexations on the northern periphery lying generally along Mission Gorge. The last annexation was in 1982, with most annexations occurring between 1953 and 1954.



NAVAJO - 1958



On January 28, 1971, concerned residents of Allied Gardens, Del Cerro and San Carlos met to organize a community plan committee. As a result of that meeting, the Mission-Navajo-Del Cerro-San Carlos Community Plan Committee (now Navajo Community Planners) was formed, consisting of members representing the numerous community groups that already existed in the area.

In June of 1971, the City Council endorsed the Navajo Community Planners. This Committee was asked to represent the Navajo area and to work with the City Manager's office and Planning Department in the development of a community plan consistent with community goals and objectives.

The role of the Committee was to review and analyze background information, formulate community objectives, and to conduct a program to keep the community informed of its progress. City staff provided the necessary technical studies. Liaison was maintained with area residents and other groups both inside and outside the community.


EXISTING LAND USE AND ZONING

Of the total zoned land in the Navajo area, 4,018 acres, is zoned for single-family homes; 389 acres, is zoned for multiple family use; 315 acres, is zoned for commercial use; and 56 acres, is zoned for industrial use. The remaining 3,018 acres, located predominantly in the southern and eastern sections of the area, including Cowles Mountain, is zoned for agriculture and the San Diego River floodway.



Public and semi-public uses and single-family homes are the predominant land uses within the community. Public and semi-public uses occupy 39.5 percent of the area or 3,099 acres. Single-family homes occupy approximately 37.5 percent or 2,924 acres while multifamily, commercial, and industrial uses comprise only nine percent of the area or 700 acres. Approximately 14 percent of the developed area is in streets and the remaining area is vacant.¹

¹ The land uses and zoning shown in this section are dated from the built condition in 1982 when the Community Plan was written. See the current land use and general plan for additional information.



ZONING

-  RESIDENTIAL
-  COMMERCIAL
-  INDUSTRIAL
-  AGRICULTURAL
-  FLOOD CHANNEL
-  See Grantville CPIOZ-Type A Zoning

*See figure 10 for additional information




FIGURE 3: ZONING

CITY OF SAN DIEGO • PLANNING DEPARTMENT




FIGURE 4: LAND USE

POPULATION CHARACTERISTICS

The Navajo community is one of San Diego's established communities. The 1980 census counted 50,005 people in this community. This population count represents an increase of 32,640 people, or 187 percent, since the 1960 census.

Approximately 82 percent of the dwelling units within Navajo are owner occupied. The occupancy rate is 95.01 percent. The development of tract homes is subsiding, while condominium and Planned Residential Development activity in the area is increasing.

The 1975 census shows a decline from 1970 in the number of children in the 0-5 age group within the area. If the trend continues, the demand for additional elementary grade classrooms may not be as acute as previous projections have indicated. As the community grows toward total development, one might expect the age composition to change in the direction of smaller average family size and an increase in the adult population, a trend which seems to be established in older developed areas.²

² NOTE: All statistics compiled by City of San Diego Planning Department.

PLAN ELEMENTS

RESIDENTIAL

EXISTING CONDITIONS

Navajo is a family-oriented community of attractive single-family homes. In 1968, approximately 95 percent of the population resided in single-family homes. These homes accounted for 92 percent of all dwelling units in the Navajo area.



In 1970, five percent of the population resided in multifamily units, which comprised 28 percent of all dwelling units in the Navajo area. In 1970, almost 75 percent of all dwelling units were owner-occupied, compared to 50 percent in the City as a whole. Vacancy rates were approximately four percent as compared to 5.6 percent for the entire City.

In 1988, single-family homes accounted for 77 percent of all dwelling units in the Navajo area. Multifamily homes accounted for 21 percent of the dwelling units. Vacancy rates were approximately 3.4 percent, while the citywide rate was 4.4 percent. According to 1980 census data, almost 79 percent of all dwelling units are owner-occupied, compared to 50 percent in the City as a whole.

Densities in the single-family residential areas of the community vary from one to six dwelling units per acre. In the multifamily areas, densities vary from 16 dwelling units per acre in the vicinity of Navajo Road and Jackson Drive to 109 dwelling units per acre in Grantville.

At the time the Community Plan was prepared, two mobile home parks were located in the community in the vicinity of Mission Gorge Road: one is located near the intersection of Old Cliffs Road and Mission Gorge Road and the other located at the eastern end of Old Cliffs Road. The Mobile Home Park Overlay Zone was applied to both of these areas. The overlay zone provides protection for the residents of the mobile home parks against development of the sites for other uses and ensures the availability of varied housing types to create a more balanced community. In 2008, an amendment to this Community Plan resulted in removing the Mobile Home Park Overlay Zone from the site located near the intersection of Old Cliffs Road and Mission Gorge Road.

OBJECTIVES

In the course of its deliberations, the Navajo Community Planners adopted objectives for each of the major Plan elements. The principal or overriding residential objective to guide the long-range development of Navajo is to: **MAINTAIN AND ENHANCE THE QUALITY OF EXISTING RESIDENCES AND ENCOURAGE THE DEVELOPMENT OF A VARIETY OF NEW HOUSING TYPES WITH DWELLING UNIT DENSITIES PRIMARILY IN THE LOW TO LOW-MEDIUM DENSITY RANGE AS SHOWN.**

TABLE 1:DENSITY RANGES

Very low density	0-4 dwelling units per acre
Low density	5-9 dwelling units per acre
Low-medium density	10-14 dwelling units per acre
Medium density	15-29 dwelling units per acre
Medium-high density	30-43 dwelling units per acre
High density	44-73 dwelling units per acre
Very high density	44-109 dwelling units per acre

To achieve this principal objective, the following additional objectives were also adopted:

- Promote a healthy environment by careful planning and sensitive development of well-defined, balanced and distinct communities which encompass a variety of residential density patterns and housing types.
- Prevent and/or limit development in proposed open space areas which serve to enhance community identity--steep slopes and canyons, floodplains, and areas with unique views and vistas.
- Foster techniques of land development that will encourage imagination and variety in building site layouts, housing types, and costs, and that will capitalize on the unique topographic assets of the community. All housing developments within the study area should relate to existing topography in order to minimize grading and preserve the natural terrain of the area. The use of retaining walls, terraces, split level or cantilevered houses should be considered in steep terrain.
- Assurance that any individual or family may be free to choose accommodations within their economic capacity from a range of housing varying in type, quality and location.
- Continuation of community support for those programs at all governmental levels that would effectively increase the economic ability of the disadvantaged to obtain adequate housing.
- Promotion of site selection for federally assisted housing programs which would ensure dispersal throughout the community of various ethnic and minority groups.

- Encourage enhancement of the existing residential development through the use of environment and conservation programs such as cleanup, painting and landscaping programs.
- Encourage the design of residential areas so as to prevent the encroachment of incompatible uses and minimize conflict (e.g., traffic noise) with more intensive non-residential uses.
- Within each new development and where possible in developed areas, plazas, squares, and other similar open space areas should be created. Emphasis should be placed on developing interconnected bikeways and walkways separated from auto traffic as part of the internal circulation system within the study area.
- Parking and storage areas should be screened from the street and other public areas.

PROPOSALS

General

The Navajo Community Planners strongly support City Council Policy 600-19, Fostering of Balanced Community Development, which states: *It shall be the policy of the City Council to effect the development of economically and racially balanced communities in newly developing peripheral areas of the City and in all City sponsored or approved redevelopment projects, and to do what is reasonably and practically possible in all parts of the City.*

- Housing types and densities should be varied in residential development to create interest and provide a mix of people with various economic and social characteristics.
- Dwelling units should relate to topography and intensity of activity. Where it will provide for more effective land utilization and high quality living environments, residential development proposals within the community should be carried out under the Planned Residential Development or Planned Infill Residential Development concept.
- Dwelling units should front on local streets.
- Multifamily residential development along major roadways, such as Mission Gorge Road, should be adequately mitigated for roadway noise impacts associated with high traffic volumes. If perimeter noise walls are necessary to mitigate noise impacts, they should not be located in the required setback. Noise walls should be well designed with landscaping provided on both sides of the wall.
- Adequate off-street parking and storage must be provided and screened from living areas and public areas. Street trees and drought tolerant landscaping should be used in level terrain to add interest to hide parking and to separate functions. Non-contiguous sidewalks must be provided even around off street parking and storage areas.
- Development of the area north of Highwood Drive and the terminus of Lake Murray Boulevard should not exceed 168 dwelling units as per Council Resolution No. 257606, December 7, 1982.
- Residential development should conform to the guidelines provided in the Mission Trails Design District when applicable. The Mission Trails Design District applies to those portions of the Navajo, Tierrasanta, and East Elliott communities consisting of, and including, all the

commercial and multifamily residential zones; the steep hillsides guidelines and Chapter 14, Article 3, Division 1, Environmentally Sensitive Lands (previously Hillside Review Overlay Zone), as well as those non-HR and undeveloped areas contiguous to HR areas; and the two areas of land in Mission Gorge contiguous to the Mission Trails Regional Park at the east and west sides of the park. The Design District provides that no structure shall exceed four stories and in no case shall a structure exceed fifty (50) feet in height.

- Mobile home and manufactured housing has limited benefit in high land cost urban environment like San Diego. The ability to house more people and provide more affordable units of development multifamily housing. Mobile home parks are not encouraged.

Dwelling Unit Density

Based upon the proposed land use, which assumes that the canyons and sloped areas will remain open, it is projected that by 1990 the number of dwelling units will increase approximately 32 percent above the 1970 level--an increase of some 4,950 units. Approximately one-half of the new housing units will be in the medium density range of 15-29 dwelling units per acre. By 1990, medium density housing will comprise approximately 25 percent of all residential units, compared to eight percent in 1970.

As Navajo continues to evolve, it is proposed that a wide range of residential densities be permitted to develop in the community. These ranges would include very high to very low density dwelling units per acre of land. See Table 1. These densities will allow single-family houses, duplexes, townhouses, condominiums and apartments which will appeal to a wide segment of the population and provide for a diverse balanced population in the community.

Site Design

The topography of this area is important to preserve and enhance while allowing for new homes. The site design of any new projects and development should be sensitive to the street and views to and from existing homes.

- Fit house to land rather than land to house. Choose the appropriate house plan to fit the basic slope type of the site-up, down, or across slope. Correct selection will minimize grading and preserve the maximum groundcover and trees. Use retaining walls, terraces, split level or platform houses to minimize grading. This would eliminate the need for flat building pads involving extensive earth cuts.
- If earth moving is necessary, re-contour rather than cut and fill. If a new form must be given to the land, the final form should have a strong, smoothly flowing character typical of the existing hills. The basic character of the original site should provide the theme with adjustments to make the slopes gentle. Particular attention should be paid to the transition areas where the existing terrain stops and earthwork begins. Additional shaping in some areas may be necessary due to the unique subsoil and groundwater conditions present.

- Outstanding natural physical features such as the highest crest of a hill, natural rock outcroppings, major tree belts, etc., should be preserved at all costs.
- If hillsides are developed, they should be designed to complement the existing terrain. Hillside developments are usually laid out in a rigid geometrical lot pattern, and thus fences contrast sharply with the natural terrain. A more logical pattern would be for front and rear lots lines to follow the horizontal contours. Under this arrangement, the patchwork appearance of most hillside developments would be largely eliminated. Contour fencing could take the form of trellises with vines and other plant materials growing over the side, while still providing a barrier between dwelling units.
- Create privacy for each house and protect its outdoor spaces from view and noise. Develop alternate methods of handling setbacks to increase usable open space such as to minimize narrow, useless side yards, as well as to create an interesting streetscape.
- Cluster developments should be encouraged to minimize tampering with the natural topography.
- Roads should follow natural courses wherever possible to minimize cutting and grading.
- Imaginative and innovative building techniques should be encouraged to create buildings suited to natural hillside surroundings.



The photo shows a contiguous sidewalk. This design is strongly discouraged.

Detailed and effective arrangements must be formulated for the preservation, maintenance and control of open space and recreational lands resulting from Planned Residential Developments.

- Create harmonious form relationships among houses rather than endless strings of houses. Groups of houses should appear to be related to one another rather than jumbled together without pattern. Strive for consistency within groups of buildings through the use of recurring shapes and materials. All the houses in one eye span should be designed to tie together and relate to one another, yet should not be repetitive and monotonous.
- Apartment developments should be arranged in such a way as to harmonize with adjacent single-family developments. They should be designed to present less apparent bulk and to minimize the clash of scale and activity between apartments and houses.
- Variety in apartment design should be facilitated by introducing optional rear and side setbacks and a front yard requirement based on floor area rather than an absolute dimension. Variable front yard spaces can give an interesting character to the street in apartment districts. When used, side yard setbacks should be increased from present regulations to better provide for daylight and visual privacy. To assure adequate outdoor space for residents, a minimum percentage of the floor space could be in the form of balconies and landscaped roof terraces.

Residential Street Design

- Streets should be designed and developed to be pleasant places to walk as well as drive. The arrangement of houses should create a pleasant streetscape. Alignment, paving, landscaping and tree planting should all be designed to enhance the visual effect.
- Protect residential areas from the noise, pollution and physical danger of excessive traffic. The speed and volume of traffic on residential streets should be limited. Techniques for doing this include making streets discontinuous to divert traffic from a straight path, narrowing streets and intersections, creating the appearance of narrowness through landscaping and other improvements. Where possible, walkways should pass through the interior of blocks. Such changes in streets should be designed so that they will not limit the access of vehicles for police and fire protection and other emergency purposes in the protected areas. The total effect of these changes in residential streets should be to emphasize their residential qualities and encourage pedestrian usage. When major streets and other streets having heavy traffic must go through residential areas, steps should be taken to screen dwellings from the noise, fumes and other adverse effects of traffic.
- Provide buffering for residential properties when heavy traffic cannot be avoided. Heavy landscaping at the side of streets and in center islands may provide an effective barrier, as can walls, differences in elevation and the setting back of dwellings from the roadways.
- Dwellings along streets with heavy traffic should, where possible, have the main orientation of their living space and access away from the traffic. In some cases further measures such as soundproofing may be required. Businesses that attract or produce heavy traffic, such as service stations, should be screened from nearby residential areas. Screening should be provided, as well, for all open parking lots within or adjacent to residential areas. All of the aforementioned considerations should apply to recreation areas as well as to dwellings.
- Underground all utilities. This should be done not only in new subdivisions but also programmed in stages in older parts of the community. With overhead wires out of the way, it is possible to allow street trees to grow; and thereby, establish a more desirable environment.
- Design all curves, intersections and cul-de-sacs and their relationship to houses for the best visual effect. Every opportunity should be taken to make street alignment and other street features contribute positively to good urban design. For example, use should be made of long radius curves connected by short curves in aligning streets rather than long tangents connected by short sharp curves. The former gives a much more sweeping, elegant feeling at eye level while the latter is sharply defined as one enters and leaves the curve.
- Provide the maximum street tree planting. One principal characteristic of memorable streets throughout the world is their tree planting. The finest examples have mature specimens that arch across the street creating a green canopy. From an urban design standpoint, a various tree planting program is the most important single thing that the City can do. Trees should be spaced close enough together to create an effect of enclosure and to provide protection of trees from hot drying winds and sun scald.



The photo shows non-contiguous sidewalk that is encouraged because it separates pedestrians from the vehicle

COMMERICAL

EXISTING CONDITIONS

As of 1988, approximately 123 acres of the 155 acres of commercially zoned land are being used for commercial purposes, representing almost two percent of the land in the Navajo community. An additional 90 acres of industrially zoned land are being used for commercial purposes in the Grantville area.

Existing development is typified by businesses, stores and offices which provide goods and services for local consumption. Most commercial development is clustered into shopping centers and is characterized by its community rather than regional nature. Four neighborhood centers provide for the daily shopping needs of the residents. Typical establishments include food markets, service stations, barber shops, beauty parlors, drug, hardware and liquor stores. Sites vary from less than an acre to almost ten acres.

Three community centers provide convenience goods--personal, professional, financial and automotive services--and a limited variety of shopping goods. Establishments include variety stores, apparel and shoe stores, banks, professional offices plus those establishments normally found in neighborhood centers. These centers are located on major streets and are easily accessible from most points in their respective trade areas.



The largest community center, which includes the Navajo and Ralphs shopping centers, is located at the intersection of Navajo Road and Lake Murray Boulevard (See top right). The total complex of over 50 business establishments and professional offices covers 35 acres.



The other two community centers are located at Waring Road and Orcutt Street and Navajo Road and Jackson Drive. The center at Waring Road and Orcutt Street has over 30 business establishments and professional offices on 12 acres of land (See middle right).



The Navajo Road and Jackson Drive center is 45 acres and has numerous commercial and professional uses in addition to multifamily residential use (See bottom right).

Major concentrations of professional offices are located in the three community shopping centers. Other professional offices are scattered throughout the area usually in conjunction with commercial centers.

Visitor-oriented commercial uses are located at Interstate 8 (I-8) and Waring Road. The potential for visitor-oriented facilities in Navajo is very limited. There are no movie theaters, bowling alleys or other similar forms of commercial recreation in the community. The centers serve only commercial functions, rarely being used for community purposes such as art shows and other cultural events.

Grossmont Center, a regional shopping center readily accessible to area residents, emphasizes such shopping goods as apparel, major household appliances and furnishings. It is located just outside the study area in the city of La Mesa. Also easily accessible are Mission Valley establishments and Parkway Plaza in El Cajon, as well as many other adjacent areas. Time distance, even to downtown areas, is only about 20 minutes.

Mission Gorge Road, a major entry point into the community, contains strip commercial development with a mix of land uses. The visual clutter created by numerous curb cuts, unscreened parking areas, excessive signs and billboards, and above ground utilities, as well as the condition of much of the development along Mission Gorge Road does not project a positive impression of the community. In addition, neighborhood centers along Mission Gorge Road have developed without regard to other development, resulting in a lack of coordinated design.

The commercial centers are constructed for the convenience of the automobile and not the shopper, which is accentuated by the lack of other forms of transportation within the community. The commercial buildings, if built by a chain, often follow some standard facade treatment that may not relate to the character of the particular site in which it is placed. Promotional and store signs are generally geared to a through traffic, high pressure merchandising situation rather than a neighborhood situation. Almost without exception landscaping of the sites is at a minimum and frequently not maintained. In particular, parking lots consist of an expanse of unrelieved asphalt and are often laid out so that shoppers are forced to thread their way between parked cars.

Table 2 contains site and trade population standards for neighborhood, community, and regional shopping centers according to the Progress Guide and General Plan for San Diego.

TABLE 2: SITE AND TRADE POPULATION STANDARDS FOR COMMERCIAL CENTERS

Criteria	Neighborhood	Community	Regional
Population in Trade Area	2,000-10,000	10,000-25,000	100,000 or more
Acres/1000 Population	1.0	.8	.7
Site Area	1-10 acres	8-20 acres	50 acres or more

The development potential for commercial facilities that serve Navajo residents is based on these standards as applied to the projected 1990 population of 65,000 to 70,000. Accordingly, the area could support six or seven neighborhood centers with a combined area of approximately 55 acres and two or three community centers with a combined area of approximately 60 acres.

Commercial facilities in adjacent communities, particularly La Mesa and El Cajon, however, serve Navajo and reduce the need for commercial land within the planning area.

OBJECTIVES

The principal or overriding objective for long-range commercial development in Navajo is not only to ENCOURAGE NEIGHBORHOOD AND COMMUNITY SHOPPING FACILITIES WHICH ARE ADEQUATE TO PROVIDE A WIDE VARIETY OF GOODS AND SERVICES TO NAVAJO, BUT ALSO BLEND INTO AND ENHANCE THE COMMUNITY ENVIRONMENT.

To achieve this principal objective, the following additional objectives were also adopted:

- Develop commercial areas as centers for community activities. Such centers should include community facilities, such as cultural, recreational, entertainment and residential facilities, as well as retail establishments and professional offices.
- Develop commercial areas that have desirably distinctive qualities in their design, appearance and operation.
- Provide neighborhood convenience centers that are complementary to adjacent residential areas and strategically located throughout the residential areas of the community, preferably near public facilities. These shops should be accessible to pedestrians and bicyclists and be in scale and character with the neighborhoods they serve. In addition, existing centers should be encouraged to add safe facilities for pedestrians and bicyclists.
- Prevent the overdevelopment of any one type of commercial use (for example, service stations).
- Prohibit the expansion of strip commercial development on Mission Gorge Road north of Zion Ave.
- Restrict retail development to areas designated for commercial and mixed use; limit commercial office and service uses in the industrially designated areas to those that are accessory to industrial uses.
- Improve the appearance of the existing strip commercial development on Mission Gorge Road between I-8 and Zion Avenue by reducing signs, improving landscaping and architectural design, providing consistent building setbacks and providing adequate off-street parking.
- Limit the development of drive-thru restaurants to sites that can accommodate the stacking of vehicles, as well as accommodate driveways in a manner that will not conflict with the smooth operation of intersections.
- Reduce the number of curb cuts serving individual commercial uses on Mission Gorge Road to minimize traffic conflicts and provide a continuous sidewalk and landscape strip.

PROPOSALS

General

- In addition to retail stores necessary to accommodate the needs of the community, commercial centers should also provide for professional and business offices, entertainment and cultural activities, public and semipublic facilities, and residential uses. The existing centers, due to their location, size, and the character of adjacent development, could easily be improved to meet these criteria.
- All the centers should be accessible by pedestrians, bicycles and adequate public transportation as well as by car.
- The shopping center at Lake Murray Boulevard and Navajo Road, the community shopping center at Waring Road and Orcutt Avenue, and the center at Navajo Road and Jackson Drive are to be retained as community commercial centers. These establishments should fulfill the need for convenience goods and personal, professional, financial and recreational services through the year 2000.
- Neighborhood commercial centers should be retained at the intersections of Golfcrest Drive and Mission Gorge Road, Conestoga Road at Mission Gorge Road, and Zion Avenue at Mission Gorge Road. The centers should be an integral part of the residential development and retrofitted to attract pedestrian and bicycle users in addition to the automobile.
- Professional offices are to be retained at existing locations. The expansion of professional offices is recommended at all community shopping centers.
- Visitor-oriented facilities (hotels, motels, and associated uses) should be limited to those existing at the intersections of I-8 and Waring Road, and Mission Gorge Road and Alvarado Canyon Road. No additional visitor-oriented facilities should be developed.
- The number and location of service stations should continue to be regulated. No more than one station should be located at an intersection and the overall number of stations should be based on service to the community. Existing facilities appear to be sufficient to serve community needs through the year 2000.
- The removal of off-premise signs and the consolidation of multiple on-premise signs should be pursued during project reviews in an effort to reduce sign clutter and enhance the visual appearance of Mission Gorge Road.
- Any rezones or tentative maps for new commercial center development and redevelopment should require processing in accordance with the planned commercial development regulations to ensure comprehensive review of the center and its compatibility with adjacent development.




FIGURE 5: COMMERCIAL PROPOSALS

CITY OF SAN DIEGO • PLANNING DEPARTMENT

INDUSTRIAL

EXISTING CONDITIONS

Sand and gravel extraction was once the predominant industrial use in Grantville, accounting for most of the industrially zoned land along the San Diego River as well as most of the agriculturally zoned land. The manufacturing of cement block, brick, and associated secondary sand and gravel uses were also prevalent near the river. Most of the sand and gravel activities have now been discontinued and are being replaced with multi-tenant buildings.

A 250-acre site is still being used for sand and gravel processing on the north side of Mission Gorge Road, generally between Princess View Drive and Margerum Avenue. This quarry has been in operation since 1927 and is currently operating under a Conditional Use Permit (CUP) that expires in 2033. The CUP regulates the mining, processing, storage and sale of natural resource material. A master reclamation plan for the 250 acres covered within the CUP, as well as 170 acres from which sand deposits have previously been mined, establishes goals and general guidelines for the reclamation of the project area upon completion of mining activity. Final reclamation is to be accomplished in phases with the approval of precise reclamation plans.

PROPOSALS

Based on the existing conditions and objectives identified above, the following general proposals were established to encourage industrial development that is compatible with the residential character of the Navajo community.

- A Planned Industrial Development (PID) or master PID should be required for any property rezoned to an industrial zone to ensure quality site design, and compatibility with the San Diego River environment and surrounding residential areas where appropriate. A master PID establishes design guidelines and standards to be used in the review of subsequent detailed site-specific projects. The PID document shall include a conceptual site plan showing the general location of proposed uses; a list of permitted uses; a preliminary grading plan; and master circulation, landscaping and sign plans. After approval of the master PID, projects will be reviewed and approved ministerially by the Planning Department if they are found to be consistent with the approved master PID. The design guidelines identified in this Industrial Element shall be consulted in the design and review of the master PID.
- Future development of the remaining sand and gravel operation and the previously mined 170 acres should be accomplished under a master Planned Industrial Development (PID) permit process. This property is bounded on the south by a major element of the regional transportation network (Mission Gorge Road) and on the north by the San Diego River, a regionally significant natural resource. A master PID will provide an opportunity for comprehensive review of the relationship between proposed development and the ultimate reclamation plan for the San Diego River, coordination of open space and pathways with Mission Trails Regional Park, traffic impacts to Mission Gorge Road and the proposed State Highway 52 interchanges.

- The area south of Mission Gorge Road generally between Old Cliffs Road and Princess View Drive is designated for development as an industrial park complex. This property is highly visible from Mission Gorge Road, as well as from the residential areas above the river basin in Allied Gardens and Tierrasanta. Future development under the M-1B Zone is recommended; however, a planned industrial development permit should be required to ensure coordinated, quality design and compatibility with the residential uses adjacent to this site.
- In order to implement the San Diego River Park Master Plan, the San Diego River Park Subdistrict Community Plan Implementation Overlay Zone (CPIOZ-Type B) is applied to all properties within two subareas of the river, the River Corridor Area and the River Influence Area. See the San Diego River Park Subdistrict Section of this plan.

COMMUNITY PLAN IMPLEMENTATION OVERLAY ZONE (CPIOZ)




FIGURE 6: COMMUNITY PLAN IMPLEMENTATION OVERLAY ZONE (CPIOZ) AREAS

The Navajo Community Plan contains 5 distinct Community Plan Implementation Overlay Zone (CPIOZ) areas, as shown on the map above. This chapter includes the supplemental development regulations for each of these 5 CPIOZ areas.

In the areas designated as CPIOZ-Type A, development that is consistent with the Community Plan, the base zone regulations, and the supplemental development regulations identified in each CPIOZ section can be processed ministerially in accordance with the procedures of the Community Plan Implementation Overlay Zone (Municipal Code Chapter 13, Article 2, Division 14). Any development that does not comply with the Community Plan, the base zone regulations, or any of the supplemental development regulations identified in the CPIOZ section shall be required to obtain a discretionary permit.

In the areas designated as CPIOZ-Type B, a discretionary permit is required. Applications for a CPIOZ-Type B discretionary permit shall meet the regulations of the underlying zone and the purpose and intent of the supplemental development regulations identified in each CPIOZ section.

Projects that require a discretionary review process should address the design and compatibility of the project in relation to surrounding development as well as the purpose and intent of the applicable CPIOZ section and supplemental development regulations of the applicable section. Projects may propose design solutions that vary, but the design of the project shall be equal or higher in quality to the design concepts identified for these CPIOZ areas.

SHAWNEE CPIOZ




FIGURE 7: COMMUNITY PLAN IMPLEMENTATION CPIOZ-TYPE A (SHAWNEE)

OVERVIEW

Shawnee/CG7600 Master Plan consists of approximately 23 acres and is intended to be developed pursuant to these Supplemental Regulations, which allow a greater variety and intensity of uses than base zoning and provides greater flexibility from creative design. This is envisioned to provide elements of smart growth that reduces automobile dependency, increased pedestrian activity, restoration of open space and public access to the San Diego River, and the creation of a high-quality neighborhood.

SUPPLEMENTAL DEVELOPMENT REGULATIONS

The primary land use of the site is reserved for multi-family residential. The buildings that front Mission Gorge Road and Old Cliffs Road are multi-family residential uses with ground floor commercial. Roadway connections to adjacent properties are an important element that will provide convenient vehicular and pedestrian circulation. Documentation from a California Registered Traffic Engineer stating that the proposed project's traffic volumes are based on the City's trip generation rates and are less than the thresholds established in the City of San Diego's Traffic Impact Study Manual must be confirmed and accepted by the City Engineer.

River Road will connect the site to the adjacent proposed River Park at Mission Gorge project. River Road will run almost the entire length of the site and connect to Old Cliffs Road where primary access to the site will lead to Mission Gorge Road. On the west side of River Road the principle open space area will be developed and integrated with the San Diego River Park Master Plan trail corridor.

Adjacent property owners to the north and south are proposing compatible land uses with Shawnee in scale, intensity of development, uses, landscape and circulation elements. Integration of the street network and pedestrian paths are a central theme of the master plan that will encourage pedestrian activity, provide public access to the San Diego River and more closely link the community.

The existing commercial industrial land uses along "C" Street with Old Cliffs Road and "E" Street with Mission Gorge Road present a challenge for residential uses. All repair work for automobiles at the auto body shop is internalized within the concrete walls of the building which eliminates much of the problems associated with industrial uses such as noise and odor. The proposed intervening streets and private drive will provide a physical separation and buffer from potential noise coming from within the building. A fence and landscape shall be placed around the perimeter of the auto body property's western and northern boundary and the western and southern boundaries of the auto dismantling yard at the northeast corner of the site to provide sufficient visual screening. Street trees shall be planted to provide additional layers of screening for residential units. The land use plan for Shawnee/CG7600 is shown in Map 3. The following land use designations apply to the Shawnee/CG7600 site:

Multifamily Residential

- Development in this designation would primarily consist of residential uses providing a mix of dwelling unit sizes and may also include special-purpose occupancy such as seniors, students, or workforce housing.

Mixed Multifamily Residential/Retail/Commercial

- Development in this designation would primarily consist of residential uses providing a mix of dwelling sizes and may also include special-purpose occupancy such as for seniors, students, or workforce housing and shall also include residential, office, retail and other commercial uses per the list of permitted uses below, which shall be located on the ground floor. These commercial uses are to be located along the Mission Gorge Road and Old Cliffs Road frontage.

- Open Space (Park): The open space west of River Road shall be reserved for open space and provide population-based parks for the site. Additional open space for passive and active recreation will be linked throughout the site that will serve as an open space network.
- The proposed development shall comply with the following provisions of the CPIOZ and the RM-3-9, RM-4-10 and OP-2-1 zones.




FIGURE 8: SHAWNEE LAND USE

DEVELOPMENT CONCEPT

Shawnee/CG7600 shall allow the development of a mix of retail, office and residential uses along the Mission Gorge Road and Old Cliffs Road frontage in compliance with the list of permitted uses below. Privately owned community open space for public use shall also be included within the site and shall be maintained to permit public access.

Permitted Uses

Permitted uses within Shawnee/CG7600 shall be those permitted in the applicable base zone in the Municipal Code as well as residential and commercial uses as follows:

- Multiple Dwelling Units

- Separately Regulated Residential Uses
 - Home Occupations (L – Permitted subject to compliance with Section 141.0308 of the Municipal Code)
 - Housing for Senior Citizens (C – Permitted by Conditional Use Permit and subject to compliance with Section 141.0310 of the Municipal Code)
 - Shopkeeper Units
 - Live/Work Quarters
- Sale of
 - Food, Beverages and Groceries
 - Consumer Goods, Furniture, Appliance Equipment (limited to 2,500 square feet for each premises)
 - Sundries, Pharmaceuticals, and Convenience Sales
 - Wearing Apparel and Accessories
- Commercial Services
 - Building Services (limited to 2,500 square feet for each premises)
 - Business Support (Hiring Halls are not permitted)
 - Eating and Drinking Establishments (the sale of alcoholic beverages is not permitted as a primary use)
 - Financial Institutions
 - Personal Services
 - Pet Grooming and Pet Supplies (Pet Sales or Boarding Kennels are not permitted)
- Separately Regulated Commercial Service Uses
 - Child Care Centers (L - Permitted subject to compliance with Section 141.0606 of the Municipal Code)
 - Instructional Studios
 - Outpatient Medical Clinics (N – Permitted with a Neighborhood Use Permit subject to compliance with Section 141.0615(b) of the Municipal Code)
 - Private Clubs, Lodges and Fraternal Organizations
 - Sidewalk Cafes
- Offices
 - Business and Professional
 - Government
 - Medical, Dental and Health Practitioners
- Signs
 - Allowable Signs

The Shawnee/CG7600 Master Plan will regulate the development of the Shawnee/CG7600 site. Consult the Shawnee/CG7600 Master Plan for development regulations. Approval of the PDP, SDP, VTM and Rezone for the site will be concurrent with approval of the Shawnee/CG7600 Master Plan.

GRANTVILLE CPIOZ




FIGURE 9: COMMUNITY PLAN IMPLEMENTATION CPIOZ-A (GRANTVILLE)

OVERVIEW

This Grantville CPIOZ sets the framework for new infill development and provides design standards to ensure high-quality development that supports walkability, strengthens connectivity, and enhances community identity. Grantville CPIOZ shall be implemented by Chapter 13 Art 02 Div 14, Community Plan Implementation Overlay Zone. The supplemental development regulations do not apply to the following projects:

- Interior improvements to an existing building
- Interior modifications, repair, exterior repairs, or maintenance that does not expand the floor area of the existing building.

PURPOSE AND INTENT

In 2005, the Grantville Trolley Station opened in the Navajo Community on Alvarado Canyon Road. As ridership continues to increase, it is anticipated that the trolley station will contribute to an enhanced quality of life, a reduction in additional traffic congestion, improved local air quality, and an opportunity for residents and visitors to engage in more frequent pedestrian-oriented and transit-reliant trips.

Grantville, as described in the figure above, is developed with a mix of mostly older, underutilized commercial and industrial buildings containing a variety of auto-dependent commercial service uses. Many properties in the area have outdated and deteriorated buildings, lack adequate parking and landscaping, and are in need of substantial capital reinvestment to stimulate economic development and create a more attractive and pleasant environment. Existing industrial zoning in Grantville has not adequately accomplished the objective of the previous CPIOZ, which was intended to encourage industrial development and redevelopment that will capitalize on the area's central location within the metropolitan area.

Because of the age and declining physical condition of the existing properties coupled with the frequent conversion of industrial properties to office or storage uses, this area was identified by the General Plan as prime for neighborhood revitalization with a more lively mix of land uses better suited to residents and the Navajo Community.

A shift in land uses from industrial to a mix of land uses including employment, commercial, higher density residential, and civic uses would allow many of the properties to be better utilized. Grantville is envisioned to include more transit-supported residential, workforce housing, and local neighborhood retail, as well as new commercial and employment opportunities. The new development would also provide additional community benefits to the area including pedestrian and bicycle infrastructure, improvements to Alvarado Creek, and access to the San Diego River. Over time, underutilized areas of Grantville would shift away from primarily industrial use to a mix of uses that serve the needs of the current and projected population.

The Grantville CPIOZ is intended to encourage transit-oriented developments, which will minimize the need for an overreliance on automobiles and emphasize pedestrian orientation and proximity to public transit. It includes supplemental development regulations that reinforce the concept of an interconnection between development projects and the surrounding public transit system. The CPIOZ will encourage the physical and functional integration of project components, site design, and the provision of pedestrian and bicycle infrastructure. It capitalizes on Grantville's proximity to public transit by concentrating new housing density and commercial uses around public amenities. As development and redevelopment occurs over time, an elaborate pedestrian and bicycle circulation network that links new development to the Grantville Trolley Station will be achieved through the guidance provided in the Grantville CPIOZ.

The following urban design framework identified below is intended to become the basis for more finite design through detailed landscape, enhanced streetscape character, and refined building architecture. In order to create visually appealing streetscapes, it is envisioned that new residential, commercial, and mixed-use developments shall design street frontages that increase pedestrian access and retail activity through high quality street-facing building exteriors. The

purpose of the framework is to foster creative approaches to design and facilitate the transition to transit-supportive land uses in the project area.

- UD-1. Enhance pedestrian and bicycle connectivity by including sidewalks and bike facilities.
- UD-2. Create appealing streetscapes through urban design, including defining the human scale through ground floor architectural scale, and incorporating street furnishings and lighting.
- UD-3. Build attractive buildings, projects, and facades along public and private streets that create visual interest. Existing Billboards should be removed with all new development.
- UD-4. Locate active uses on the ground floor of buildings in order to enliven the pedestrian experience and engage the streetscape or public realm.
- UD-5. Diminish the overall mass of buildings and create variation as viewed by pedestrians on the sidewalk.
- UD-6. Create an active, attractive, and pedestrian-focused, retail environment in Grantville.
- UD-7. Design projects that incorporate connections to the Grantville Trolley Station and bus routes.
- UD-8. Revitalize Grantville through transit-oriented developments that provide interconnectivity through transit.
- UD-9. Design larger scale development projects with private streets and private drives that include parking, sidewalks, planting areas in order to allow multiple routes to destinations, create a smaller block size, and increase connectivity.
- UD-10. Provide the opportunity for a pedestrian/bicycle bridge over Alvarado Creek, which will allow any development projects adjacent to Alvarado the creek a critical linkage to the Grantville Trolley Station.

SUPPLEMENTAL DEVELOPMENT REGULATIONS



For Grantville CPIOZ-Type A, development that is consistent with the base zone regulations and the following supplemental development regulations will be processed ministerially in accordance with the procedures of the Community Plan Implementation Overlay Zone (Municipal Code Chapter 13, Article 2, Division 14.) The supplemental development regulations do not apply to the following projects:

- Interior improvements to an existing building
- Interior modifications, repair, exterior repairs, or maintenance that does not expand the floor area of the existing building.

Any proposal that does not comply with the supplemental development regulations shall require a discretionary permit. Projects that require a discretionary review process shall meet the purpose and intent of the supplemental development regulations and should address the design and compatibility of the project in relation to surrounding development.

- SDR 1. In order to establish the trip generation rate for a proposed project, proposed development shall meet one of the following criteria or apply for a discretionary permit:
- a. Proposed project is greater than or equal to 20 dwelling units per acre and is 165 dwelling units or less; OR
 - b. Proposed project is mixed-use, greater than or equal to 20 dwelling units per acre, does not exceed 100 dwelling units, and 10,000 s.f. of commercial use; OR
 - c. Submit documentation from a California Registered Traffic Engineer, confirmed and accepted by the City Engineer, stating one of the following:
 - i. The proposed project's traffic volumes are based on the City's trip generation rates and the proposed project generates less than 1,000 ADT's; OR

- ii. If project generates more than 1,000 ADT's, documentation must demonstrate the project has no significant impacts onto the transportation system.

SDR 2. Based on the City of San Diego interim screening criteria for GHG emission analysis, all new projects will have greenhouse gas emissions (GHG emissions) less than 900 metric tons of CO₂e measure. For projects exceeding 900 metric tons of CO₂e, the greenhouse gas analysis must show how the project will reduce its GHG emissions by 20.5% compared to the business as usual scenario. The reduction measures should include, but are not limited to, onsite recycling, water use reductions, and transportation features such as increased transit accessibility, improved pedestrian networks, and improved bikeability.

- a. Prior to adoption of the City of San Diego Climate Action Plan: Projects shall submit a GHG emissions analysis accepted by the City of San Diego showing GHG emissions less than 900 metric tons of CO₂e measure; OR a GHG emissions reduction of 20.5%; OR
- b. Upon the adoption of the City of San Diego Climate Action Plan: Projects shall submit a completed Climate Action Plan consistency review checklist.

SDR 3. Any habitable space located within a CNEL of greater than 60 dBA shall require an acoustical study consistent with Table NE-4 (Acoustical Study Guidelines – General Plan). The proposed building, wall, and roof-ceiling assemblies shall be designed to limit intruding noise to the allowable interior noise level with all exterior doors and windows in the closed position. Documentation of the noise attenuation measures shall include building assemblies section including, but not limited to, a wall and roof-ceiling assemblies section. Design of noise attenuation measures shall include the following:

- a. For residential, institutional, and visitor accommodation uses: The allowable interior noise level is 45 dBA. Wall and roof-ceiling assemblies making up the building envelope shall attenuate noise to meet applicable building code requirements.
- b. For retail and office uses: The allowable interior noise level is 50 dBA. Wall and roof-ceiling assemblies making up the building envelope shall attenuate noise to meet applicable building code requirements.
- c. For mixed-use buildings, residential, institutional, and visitor accommodation spaces must attenuate to (a) and non-residential spaces shall attenuate to (b).

Multi-Modal Connectivity

- SDR 4. All improvements identified below shall be required for all new development except as identified in §142.0611 (Exemptions from Requirement to Provide Public Improvements Incidental to a Building Permit). The Pedestrian Design section of the City of San Diego Street Design Manual should be integrated into the site planning and design of new developments. The separate zones of the pedestrian sidewalk zones are defined in the City of San Diego Street Design Manual.
- SDR 5. All new development shall provide a minimum of one vehicular access way through the project site. The layout of a private street or private drive should be in a grid pattern or modified grid pattern, emphasizing interconnected streets and the ability to reach local destinations through multiple routes. It is desirable to have streets with block faces of 400 feet in length or less. Private streets or private drives shall be coordinated and connected to the public street system. Fencing, walls, or gates that limit access are prohibited. Where possible, streets shall frame vistas of the mixed-use core, Grantville Trolley Station, San Diego River, and Alvarado Creek.
- SDR 6. All new development shall provide a minimum of one pedestrian and bicycle access-way through the project site. Pedestrian and bicycle access-ways shall be coordinated and connected to public streets. Fencing, walls, and gates that limit access are prohibited. Sidewalks shall be separated from the street by landscaped parkways and shall be provided as follows:
- Provide a minimum 5-foot landscaped parkway and minimum 5-foot non-contiguous sidewalk on at least one side of any private drive.
 - Provide a minimum 5-foot landscaped parkway and minimum 10-foot non-contiguous sidewalk along any public or private street. See Figure 11.




FIGURE 11: LANDSCAPE PARKWAY AND SIDEWALK REQUIREMENT

- SDR 7. For all new projects, provide way-finding signage. The signage shall identify the pedestrian and bicycle routes to and from the Grantville Trolley Station and San Diego River. Signage shall be submitted for review. The placement of signs and other public facilities shall be done in a manner so as to provide a clear unobstructed pedestrian path and continuous parkway design. Submit the following signage for review:
- a. Provide one vertical way-finding signage per 100 feet of street facing building façade. Examples of vertical way-finding signage include permanent banners, traditional sign posts, or plaques. Incorporate vertical way-finding signage into the building elevation as a plaque or install vertical way-finding signage in the pedestrian zone; OR
 - b. Provide one horizontal way-finding signage per 100 feet of street facing building façade. Examples of horizontal way-finding include specialized paving patterns or inset arrows. Incorporate the horizontal way-finding signage into the hardscape treatments along public street, private street, and private drive.
- SDR 8. Pedestrian paths and sidewalks shall be continuous, clear of obstructions, easily identifiable, and visually distinguishable from surrounding concrete or hardscape areas. Pedestrian paths and sidewalks should be separated from parking area by wheel stops, curbs, landscaping, or other physical barriers.
- SDR 9. Provide street trees in all landscaped parkways to establish a shaded pedestrian environment and give character to the street. Provide street trees shall conform to the following conditions:
- a. The number of trees required for each public street, private street and private drive frontage shall be calculated at the average rate of one 24 inch box canopy tree for every 30 feet of frontage. Tree spacing may be varied to accommodate site conditions or design considerations; however, the total number of trees calculated for all frontages shall be provided in landscaped parkways as street trees. Street tree placement can include the use of double row of trees.
 - b. Each street tree shall receive a minimum of 10 cubic feet of below surface volume.
 - c. Street trees in tree grates are allowed; however, if trees in tree grates are selected, landscaped parkway must incorporate a permeable hardscape that allows water infiltration.

Street Furnishings

- SDR 10. Above-ground utility placement within the sidewalk and/or pedestrian path is prohibited. Above-ground utilities shall be either: located in landscaped parkways; OR located adjacent to building, screened from view, and accessible from the sidewalk or pedestrian path.
- SDR 11. A minimum of 25% of all required bike racks must be provided along the project's street frontage.

Ground Floor Design

- SDR 12. All commercial and mixed-use buildings shall be oriented so that primary and functional pedestrian entrances for each ground-floor commercial, office, or retail tenant space and shopkeeper units are individually accessible from an abutting public street by a pedestrian path.
- a. The primary and functional pedestrian entrance requirement identified above shall also apply to any tenant spaces on private streets.
- SDR 13. Shopkeeper units may be used to meet the ground floor commercial requirements. A minimum depth of 30 feet shall be provided.
- SDR 14. All commercial and mixed-use buildings shall provide a minimum floor-to-ceiling height of 15 feet.
- a. For shopkeeper units, the first 15 feet shall meet the minimum floor-to-ceiling height requirement.
- SDR 15. For all commercial and mixed-use buildings: Create activation of the ground floor and pedestrian zone by providing the following ground floor transparency along the street wall areas of public and private street frontages:
- a. A minimum of 50% of street wall area between 18 inches and 12 feet above the sidewalk shall be transparent with clear glass visible into a commercial or residential use; AND
 - b. Windows or other transparent materials that provide visibility into a parking garage, non-public commercial area, and similar areas shall not be used to meet the minimum transparency requirement; AND
 - c. Transparency requirement shall be applied to the building frontage of shopkeeper units.
- SDR 16. Each residential unit shall be oriented so that functional pedestrian entrances are accessible from abutting public streets, private streets, and private drives by a pedestrian path.

Building Articulation

- SDR 17. Buildings shall be setback from the property line no further than the minimum dimension needed to provide a 5-foot landscaped parkway and 10-foot sidewalk for 100% of public street and private street frontage.
- SDR 18. Building facades shall be varied and articulated to provide visual interest to pedestrians. This can be accomplished by incorporating the following: changes in wall texture and color, changes in material and color, and special architectural elements such as:
- a. Green walls (permanent vertical landscape features integrally designed into the building), vertical fins, horizontal shading devices, solar panels, metal detailing

on building facade. Special architectural elements may encroach into the pedestrian paths by no more than 2 feet.

SDR 19. All building elevations fronting a public street or private street shall be composed of offsetting planes that provide relief in the building facade by inseting or projecting surfaces (planes) of the building. The minimum number of offsetting planes and the minimum horizontal separation between planes is based on the length of the new building facade, as shown below:

Offsetting Plane Requirements	
Length of New Building Façade	Number of Offsetting Planes Required
25 feet or less	2 with a minimum separation of 3 inches
More than 25 feet but less than or equal to 50 feet	4 planes consisting of : <ul style="list-style-type: none"> • 2 with a minimum separation of 3 inches, and • 2 with a minimum separation of 8 inches
More than 50 feet but less than or equal to 100 feet	6 planes consisting of: <ul style="list-style-type: none"> • 2 with a minimum separation of 3 inches, and • 2 with a minimum separation of 8 inches, and • 2 with a minimum separation of 3 feet
More than 100 feet	6 planes consisting of: <ul style="list-style-type: none"> • 2 with a minimum separation of 3 inches, and • 2 with a minimum separation of 8 inches, and • 2 with a minimum separation of 3 feet, and plus <ul style="list-style-type: none"> • 1 additional plane for each 50 feet of building facade length over 100 feet (maximum of 3 additional planes required with a minimum separation of 5 feet).

SDR 20. Provide projections and recesses on upper floors by incorporating balconies with rail details, bay windows, or inset balconies on a minimum of 50% of building elevations along public streets, private streets, and private drives.

SDR 21. Buildings at controlled intersections shall include one of the following gateway features:

- a. distinct architecture that includes material change and enlarged window fenestration; OR
- b. rounded corner with exaggerated roof element.



SDR 22. Create visual breaks in the roof.

Incorporate staggered roof lines or shaded roof decks. Up to 20% of the length of the building facade may exceed any identified height limit per the base zone in order to provide roof decks, green roofs, facade variations, accents, tower elements, and other similar elements. Usable roof space shall not be included in the floor area calculation of the structure.

- a. Any flat roof shall be designed as an architectural/landscape amenity to enhance the views of the proposed structure from adjacent structures. Such enhancement may include roof gardens, architectural features, special paving, patterns, and other comparable treatments. Roof amenity spaces can be counted towards common area requirements.
- b. Roof surfaces shall be simplified and appurtenances shall be grouped and screened.
- c. A continuous roofline may be provided if the location of the proposed development optimizes orientation and the roof incorporates angle and orientation to maximize the capture of solar energy. If a continuous roofline is provided, design of the roof shall seamlessly integrate solar panels into the building design and should diminish roof mass.

SDR 23. Exposed roof top parking is not permitted. Top level of parking shall incorporate solar energy features.

Public/Private Open Space

SDR 24. A paseo can be used to provide a pedestrian connection through development. Figure 12 illustrates the relationship between Plazas and Paseos. A paseo can contribute to the common area requirement.




FIGURE 12: PASEO ILLUSTRATION

SDR 25. Mixed-use and commercial developments that exceed 3 stories at controlled intersections shall incorporate a publicly accessible plaza with the following conditions:

- a. Plaza as allowed by line of sight study per transportation engineering section. Submit site plan for review.

SDR 26. Per SDR 5, an increased setback area beyond the minimum required for parkway and sidewalk shall be allowed only if the following conditions are met:

- a. the width of the increased setback shall not exceed 30% of the width of the project's total public street or private street frontage, AND
- b. the setback area is designed as a pedestrian amenity such as plaza with public seating; AND
- c. building(s) surround the plaza.



Parking

SDR 27. Parking ratios shall be calculated based on the reduced parking ratios identified in [Chapter 14, Article 2, Division 5](#) for all new development.

- a. All mixed-use and commercial developments that exceed 3 stories shall provide the following:
 - i. A minimum of 2 alternative fuel charging stations.
 - ii. A minimum of 1 car share parking space.

SDR 28. A minimum of one garage entrance or parking facility shall be accessed from the alley when available. If alley access is not available, garage entries shall be recessed from sidewalk and parking shall be screened.

SDR 29. Locate all parking underground or to the rear or side of the building. Parking shall be provided at-grade only if wrapped with building on public street, private street, and private drive frontages. Underground or structured parking shall not be counted as part of the building floor area ratio.

SDR 30. Dead ends, parking courts, and cul-de-sacs are prohibited.

SDR 31. Enclosure that surrounds a mixed-use or residential development and gated private drives are prohibited. Fencing can be used to delineate property boundaries, but shall not be used to create residential enclaves. Chain-link fencing is prohibited.

SDR 32. Drive-through features are prohibited in all new development.

Screening

SDR 33. All heavy work or storage areas shall be contained within an enclosed building area. Outdoor storage is prohibited unless completely screened. Storage areas shall not be placed facing a public right-of-way.

SDR 34. Screen all visible building equipment, utilities, trash enclosures and service/maintenance areas with a wall that uses consistent materials and colors with the building façade. Landscaping shall also be incorporated.

Specific Design Areas

SDR 35. On Mission Gorge Road, south of Friars Road, the following conditions shall be met:

- a. For a single development that includes lot consolidation: one curb cut shall be permitted for each 150 feet of street frontage. One additional curb cut may be permitted for each 150 feet of street frontage on Mission Gorge Road.
- b. For individually developed lots without lot consolidation, one curb cut per lot shall be permitted.

SDR 36. For projects located along Alvarado Canyon Road, the following streetscape treatments shall be provided:

- a. A 12-foot landscaped parkway shall be established from the edge of curb. Two rows of trees must be planted in the landscaped parkway and 10 cubic feet of below surface volume shall be provided per tree.
- b. A 10-foot sidewalk shall be established between the landscaped parkway and building edge.
- c. Balconies are prohibited unless set back a minimum of 20 feet from the property line.

Alvarado Creek

For properties south of Mission Gorge Place, north of Alvarado Canyon Road and east of Mission Gorge Road, and west of Mission Gorge Place, the following design regulations shall apply:

SDR 37. Development along Alvarado Creek shall provide a 10-foot wide multi-use pedestrian and bicycle trail directly adjacent to the Alvarado Creek.

SDR 38. Developments shall orient buildings, common areas, and dwelling units toward the Alvarado Creek trail as identified in SDR 44.

SDR 39. Provide direct access to the Alvarado Creek trail as identified in SDR 44 from common areas and ground floor units.

SDR 40. Surface parking is prohibited within 50 feet of the Alvarado Creek floodway. Parking shall not be visible from the Alvarado Creek trail as identified in SDR 44.

Landscaping

For street trees in the landscaped parkway of any sidewalk or pedestrian path, trees shall be chosen from the following species to be consistent with the predominant species in the area.

- Double-rows of street trees should be provided along development frontages wherever feasible.
- Root barriers shall be installed to protect water and sewer lines or other facilities.
- Tree grates shall be installed along Mission Gorge Road and Fairmount Avenue.
- Each street tree shall receive 10 cubic feet of below surface volume for water retention and growth capacity.

TABLE 3: GRANTVILLE CPIOZ STREET TREE PLAN

	BOTANICAL NAME	COMMON NAME
For 4 to 7 foot parkways and larger or in 5' by 5' cutouts.		
Mission Gorge Road	<i>Jacaranda mimosifolia</i> <i>Brachychiton acerifolius</i>	Jacaranda Flame tree
Twain Avenue	<i>Brachychiton acerifolius</i> <i>Jacaranda mimosifolia</i>	Flame tree Jacaranda
Fairmount Avenue	<i>Brachychiton acerifolius</i> <i>Jacaranda mimosifolia</i>	Flame tree Jacaranda
Vandever Avenue	<i>Brachychiton acerifolius</i> <i>Jacaranda mimosifolia</i>	Flame tree Jacaranda
	BOTANICAL NAME	COMMON NAME
For 7 to 10-foot parkways or larger and minimum 40 square foot cutouts		
Mission Gorge Road	<i>Koelreuteria paniculata</i>	Golden Rain
Twain Avenue	<i>Pinus canariensis</i> <i>Koelreuteria paniculata</i>	Canary Island Pine Golden Rain
Fairmount Avenue	<i>Koelreuteria paniculata</i>	Golden Rain
Vandever Avenue	<i>Koelreuteria paniculata</i>	Golden Rain

DEFINITIONS

Active commercial uses mean commercial uses that are accessible to the general public, generate walk-in clientele, and contribute to a high level of pedestrian activity. Active commercial uses include retail shops, restaurants, bars, theaters and the performing arts, commercial recreation and entertainment, personal and convenience services, hotel lobbies, banks, travel agencies, airline ticket agencies, child care services, libraries, museums, and galleries.

Alternative Interim Uses means uses permitted under the base land use regulations of this Division but which are not identified as active commercial uses within the Neighborhood Mixed-Use Center Land Use District, or the Main Street and Commercial Street Overlay Districts.

Blank wall means any street wall area that is not transparent, including solid doors and mechanical area wall(s).

Employment uses mean non-residential uses that provide employment opportunities and include those uses specifically designated in Table 156-0308A.

Eco-roof means an open space area on top of a building roof that is landscaped and maintained according to the requirements of Section 156.0309(e)(4).

Mixed-use development means development that includes two or more land uses.

Pedestrian entrance means a functional entrance or door that is accessible to the general public from an enclosed occupied space. Entrances to mechanical equipment or storage areas, emergency exits, or decorative nonfunctional doors and entrances are not considered pedestrian entrances.

Performance Path means a way to demonstrate that a development has exceeded the California Green Building Standards Code (CALGreen) by achieving a targeted level of performance in an existing voluntary green building rating system.

Plaza means an outdoor area designed to be used as a public space. A plaza can include one or a combination of paving, play areas, seating areas, water features, useable lawn areas, shrub beds, and plants in containers.

Paseos are pedestrian ways that connect a plaza with other spaces or uses and are considered a part of the plaza for purposes of overall calculation of landscape area and point requirements for each plaza.

Private drive means a nonpublic thoroughfare. Private drives connect public rights-of-way to multiple locations within a development.

Private open space means an area connected or immediately adjacent to a dwelling unit. Private open space may include a balcony, porch, at-grade or above-grade patio or roof deck used exclusively by the occupants of the dwelling unit and their guests.

Public open space means an area owned by the City of San Diego intended for use by the general public, or an area on private property for which a public park, open space, or similar easement or covenant has been recorded in favor of the City of San Diego for use by the general public.

Screen or screening means partial or full enclosure of a space or area by solid materials that are compatible with the materials and architectural design of the development in order to block views of the area from nearby development or public rights-of-way.

Setback is the horizontal distance between the property line and the nearest front, side, or rear building wall.

Shopkeeper OR live/work unit means a dwelling unit with both living quarters and commercial space that meets all occupancy separation requirements of the Building Code, where the commercial use is located on the ground floor and operated by the resident of the dwelling unit. Live/work or shopkeeper unit requires a minimum of 2 parking spaces per unit.

Stepback means the distance measured from a property line to the building walls of the upper floors of a building above a specified height.

Street wall means the building façade along a property line adjacent to any public street. The street wall may include arcades, colonnades, recessed entrances, private open space, or urban open space.

Structured parking means all parking facilities that serve a primary use or are open to the general public.

Transportation demand management (TDM) means a series of measures that encourage use of alternative forms of transportation to alleviate traffic demand on area roadways.

Urban open space means any usable space accessible to the general public which is 1,000 square feet or greater in size and includes plazas or parks.

MISSION GORGE ROAD INDUSTRIAL CPIOZ




FIGURE 13: COMMUNITY PLAN IMPLEMENTATION CPIOZ-TYPE A (MISSION GORGE ROAD INDUSTRIAL)

OVERVIEW

In the areas designated as CPIOZ Type A, development that is consistent with the Community Plan, the base zone regulations, and the supplemental development regulations identified in each CPIOZ section can be processed ministerially in accordance with the procedures of the Community Plan Implementation Overlay Zone (Municipal Code Chapter 13, Article 2, Division 14).

Any development that does not comply with the Community Plan, the base zone regulations, or any of the supplemental development regulations identified in the CPIOZ section shall be required to obtain a discretionary permit.

In the areas designated as CPIOZ-Type B, a discretionary permit is required. Applications for a CPIOZ-Type B discretionary permit shall meet the regulations of the underlying zone and the purpose and intent of the supplemental development regulations identified in each CPIOZ section.

Projects that require a discretionary review process should address the design and compatibility of the project in relation to surrounding development as well as the purpose and intent of the applicable CPIOZ section and supplemental development regulations of the applicable section. Projects may propose design solutions that vary, but the design of the project shall be equal or higher in quality to the design concepts identified for these CPIOZ areas.

SUPPLEMENTAL DEVELOPMENT REGULATIONS

Documentation from a California Registered Traffic Engineer stating that the proposed project's traffic volumes are based on the City's trip generation rates and are less than the thresholds established in the City of San Diego's Traffic Impact Study Manual must be confirmed and accepted by the City Engineer.

Floor Area Ratio (FAR)

New development processed under ministerial (CPIOZ-Type A) review shall not exceed a floor area ratio of 1.0. Development proposals that exceed a floor area ratio of 1.0 shall apply for a discretionary permit. The discretionary review process should address:

- The design and fit of the project in relation to surrounding development, including conformance with the design guidelines of this Industrial Element.
- The ability of Mission Gorge Road and adjacent streets in Grantville to accommodate additional travel demand.
- The opportunity for instituting travel demand management strategies such as participation in a transportation management association.

Offsetting Planes and Facade Variations

- Any building facade which faces a public street have a minimum of three offset building planes or three distinct building facade variations, or a combination of offset building planes and facade variations which meets the intent of this requirement.
- An offset building plane is distinguished by an average horizontal or vertical difference of two feet measured perpendicular to the adjacent plane. Each offset plane shall constitute at least 20 percent, but not more than 50 percent of each building facade.
- A building facade variation is distinguished by a distinct change in materials, textures, colors, or any combination thereof. Each variation shall constitute at least 20 percent, but not more than 50 percent of each building facade.

Building Reflectivity

- No more than 30 percent of any single elevation of a building's exterior may be constructed of a material with a light reflectivity factor greater than 25 percent.

Equipment Enclosure

- All mechanical equipment and appurtenances shall be screened on all sides so that they appear to be an integral part of the overall architectural design of the building. The screening may include grillwork, louvers, or latticework.
- Wind generated turbines shall not be screened but shall be painted to match the rooftop color.
- No merchandise, material or equipment shall be stored or displayed on the roof of any building.

Outdoor Storage and Display

- Outdoor storage areas shall be located in interior side or rear yards only.
- Outdoor storage areas shall be screened with a solid six-foot fence or wall or an enclosed structure. All such fences, walls or structures shall be of a similar material and color as the main building. No material or equipment shall exceed the height of the fence, wall or structure.
- Outdoor display of the following merchandise sold on the premises shall not be subject to the storage requirements above but shall meet the landscaping requirements for vehicular use areas of the Citywide Landscape Ordinance:

Automobiles (usable)
Trailers
Artwork and pottery

Boats (usable)
Equipment and tools
Flowers and plants

Refuse Collection Areas

- Refuse collection areas shall be located in interior side or rear yards only.
- Refuse collection areas shall be screened with a solid six-foot fence or wall or an enclosed structure. All such fences, walls or structures shall be of a similar material and color as the main building. Deposited refuse shall not be visible from outside the refuse screening.

Loading Areas

- Loading and service areas shall be located in interior side or rear yards only.

Parking Requirements

The below parking requirements shall replace the parking area requirement of the M-1B and M-1A zones (Municipal Code Sections 101.0435.2E and 101.0436B). If the citywide industrial parking requirements are revised, the new standards will replace those identified below.

- Off-street parking shall be provided by use as follows:

Spaces/Square Feet of Gross Floor Area

For wholesale, distribution and manufacturing uses	1/1500
For business and professional offices	1/300
For medical and dental facilities	1/250
For commercial uses that take access from Mission Gorge Road	1/250
For all other commercial uses	1/300

Curb Cuts and Driveways

- On Mission Gorge Road, south of Friars Road, one curb cut shall be permitted for each lot with frontage on Mission Gorge Road. One additional curb cut may be permitted for each 150 feet of frontage on Mission Gorge Road. No driveway shall exceed a width of 25 feet measured at the property line.
- On Mission Gorge Road, north of Friars Road, curb cuts shall be in conformance with the Street Design Manual standards for primary arterials.

Signs

Signs shall be in conformance with the Citywide Sign Regulations (Municipal Code Section 101.1100) with the following exceptions:

- Ground signs other than monument signs shall not be permitted in the industrial zones except on lots that have frontage on Mission Gorge Road or the southerly 500 feet of Fairmount Avenue (i.e., 500 feet south of the intersection of Mission Gorge Road and Fairmount Avenue). Monument signs shall not exceed a height of six feet.
- On Mission Gorge Road, ground signs shall not exceed the height of the building or the citywide height limit of 30 feet, whichever is less, unless they meet the definition of freeway oriented signs in Municipal Code Section 101.1101.56.
- A landscaped area shall be provided at the base of all ground signs. The size of the landscaped area shall be equal to or greater than the area of the sign face.

Landscaping

Landscaping shall be provided as required by the Citywide Landscape Ordinance. For the streets identified below, trees in the public right-of-way shall be chosen from the following species to be consistent with the predominant species in the area.

TABLE 4: MISSION GORGE ROAD INDUSTRIAL CPIOZ STREET TREE PLAN

Street	Botanical Name	Common Name
Friars Road	<i>Platanus acerifolia</i>	London Plane
	<i>Liquidambar styraciflua</i>	Sweetgum
	<i>Platanus racemosa</i>	California Sycamore
Mission Gorge Road, northeast of Friars Road	<i>Platanus acerifolia</i>	London Plane
	<i>Liquidambar styraciflua</i>	Sweetgum
San Diego River	<i>Platanus racemosa</i>	California Sycamore
	<i>Populus fremontii</i>	Cottonwood
	<i>Salix hindsiana</i>	Black Willow
	<i>Sambucus</i>	Elderberry
Mission Gorge Road, south of Friars Road	<i>Liquidambar styraciflua</i>	Sweetgum
	<i>Jacaranda mimosifolia</i>	Jacaranda
	<i>Koelreuteria paniculata</i>	Goldenrain Tree
Riverdale Street	<i>Liquidambar styraciflua</i>	Sweetgum
	<i>Jacaranda mimosifolia</i>	Jacaranda
	<i>Cupaniopsis anacardioides</i>	Carrotwood
Twain Avenue	<i>Pinus canariensis</i>	Canary Island Pine
	<i>Koelreuteria paniculata</i>	Goldenrain Tree
Alvarado Canyon Road	<i>Koelreuteria paniculata</i>	Goldenrain Tree
	<i>Liquidambar styraciflua</i>	Sweetgum
Fairmount Avenue	<i>Liquidambar styraciflua</i>	Sweetgum
	<i>Jacaranda mimosifolia</i>	Jacaranda
	<i>Koelreuteria paniculata</i>	Goldenrain Tree
Vandever Avenue	<i>Liquidambar styraciflua</i>	Sweetgum
	<i>Jacaranda mimosifolia</i>	Jacaranda
	<i>Koelreuteria paniculata</i>	Goldenrain Tree

Design Guidelines

The following design guidelines will be used in the review of discretionary projects:

- Architecture, building color and texture should be coordinated within larger industrial developments. In smaller developments similar or complementary architectural elements should be used to provide continuity between existing and new developments.
- Building design should include variations in wall texture, color or material, variations in upper floor setbacks and the use of varied roof forms. All buildings should incorporate some form of shadow relief where pop-outs, offsetting planes, overhangs, and recesses are used to add visual interest. Large, unbroken expanses of wall should be avoided.
- Exterior building walls should be constructed of durable, permanent materials such as textured concrete, stone, brick, stucco, wood or glass. Reflective glass should not be used, particularly along heavily traveled roadways because of problems with reflected heat and glare.
- Industrial developments should consist of several smaller buildings rather than large building masses to prevent the appearance of a wall of development along the street, particularly along Mission Gorge Road.
- Building height should be restricted where industrially zoned property abuts residential property to reduce impacts to the residential areas.
- All outdoor storage, refuse collection, and loading areas should be located in interior side or rear yards. Where industrial development abuts residentially zoned property, special consideration shall be given to locating these facilities in areas least disruptive to adjacent residential uses.
- Because building roofs are visible from surrounding residential properties, they should be carefully designed. Roof-mounted equipment should be avoided. If roof-mounted equipment is provided, all equipment and appurtenances shall be designed so that they appear to be an integral part of the overall architectural design of the building.
- Multi-building industrial development should provide a coordinated sign program. Pole signs should not be permitted in the industrial zones except on Mission Gorge Road, south of Twain Avenue, where development is more commercial in nature. Monument and wall signs should be used instead of pole signs in the industrial areas.
- Fences should be constructed of wood, masonry, wrought iron, or a wood-masonry combination. Fencing should use pilasters, offsets or some other form of visual relief to break up the linear nature of the fence.
- Curb cuts should be minimized by the use of common, joint use driveways and/or consolidation of lots.

The following additional guidelines are provided for new industrial development on both sides of Mission Gorge Road, from just south of Old Cliffs Road to Margerum Avenue:

- A 25-foot landscaped setback should be provided along Mission Gorge Road. Landscaped parkways should be provided between the sidewalk and the curb on Mission Gorge Road and

on any interior circulation system. A landscaped median should be provided in Mission Gorge Road. Paving patterns and landscaping should be consistent with the existing medians to the south on Mission Gorge Road. Maintenance should be assured through formation of an assessment district or a similar mechanism.

- Access and circulation design should provide continuous pedestrian and bicycle access along public streets and to uses within the development. Bicycle parking facilities should be conveniently located near the entrances of buildings, without blocking pedestrian traffic. No parking areas or driveways should be located between the structures and Mission Gorge Road.

MISSION GORGE ROAD RESIDENTIAL CPIOZ




FIGURE 14: COMMUNITY PLAN IMPLEMENTATION CPIOZ-B (MISSION GORGE ROAD RESIDENTIAL)

OVERVIEW

In order to ensure quality design along Mission Gorge Road, Community Plan Implementation Overlay Zone (CPIOZ) –Type B is applied to the residential properties generally located between Old Cliffs Road and Zion Avenue and abutting Mission Gorge Road. A discretionary permit is required. Applications for a CPIOZ-Type B discretionary permit shall meet the regulations of the underlying zone and the purpose and intent of the supplemental development regulations identified below.

All projects should address the design and compatibility of the project in relation to surrounding development as well as the purpose and intent of the supplemental development regulations of

this CPIOZ section. Projects may propose design solutions that vary, but the design of the project shall be equal or higher in quality to the design concepts identified for this CPIOZ areas.

SUPPLEMENTAL DEVELOPMENT REGULATIONS

Architectural Design

- New development shall be compatible in design with the existing neighborhood. The bulk and scale of new buildings should be similar to the surrounding buildings. Where adjacent development is single-family, large building masses shall be avoided. Several smaller buildings should be used to maintain the pattern of development.

Building Height

- New development shall be limited to 30 feet in height where adjacent development is single-family.

Roof Treatment

- Roof forms shall be predominantly sloped. Rooftop ventilation or other mechanical equipment shall be screened from adjacent residential areas and from the public right-of-way.

Setbacks, Landscaping and Noise Walls

- An extensively landscaped street yard shall be provided for any new residential development along Mission Gorge Road except for new residential or commercial development where commercial retail, office use or shopkeeper units are located on the ground floor. If noise walls are proposed, the walls should be well-designed, incorporating articulation, pilasters and other design features to achieve an attractive design. Noise walls shall not be permitted in the setback. In addition, landscaping should be used to soften the appearance of perimeter walls and residential structures from Mission Gorge Road and from adjacent uses.

Traffic and Access

- New development should be designed to minimize further traffic impacts on Mission Gorge Road.

Parking

- Parking areas shall be well-screened from Mission Gorge Road using a combination of landscaped berms, tall trees and shrubs. Parking areas shall be located in areas least disruptive to adjacent single-family uses. Tree plantings shall be incorporated throughout the parking area.

Streetscape Improvements

- New development shall be required to provide non-contiguous sidewalks.
- All utilities shall be undergrounded on-site

A median shall be constructed along the Mission Gorge Road frontage. The feasibility of landscaping the median in Mission Gorge Road should be studied as new development occurs. Landscaping and paving in the median should continue the pattern established in the existing median on Mission Gorge Road.

SAN DIEGO RIVER PARK SUBDISTRICT CPIOZ




FIGURE 15: COMMUNITY PLAN IMPEMENTATION CPIOZ-B (SAN DIEGO RIVER PARK)

OVERVIEW

In order to ensure quality design along the San Diego River, Community Plan Implementation Overlay Zone (CPIOZ) –Type B is applied the area identified in Figure 15. A discretionary permit is required. Applications for a CPIOZ-Type B discretionary permit shall meet the regulations of the underlying zone, purpose and intent of the supplemental development regulations identified below, and San Diego River Park Master Plan.

All projects should address the design and compatibility of the project in relation to surrounding development as well as the purpose and intent of the supplemental development regulations of this CPIOZ section. Projects may propose design solutions that vary, but the design of the project shall be equal or higher in quality to the design concepts identified for this CPIOZ areas.

Within the area designated as CPIOZ-Type B, no building, improvement, or portion thereof shall be erected, constructed, converted, altered, enlarged, or established until a discretionary permit is obtained.

SUPPLEMENTAL DEVELOPMENT REGULATIONS

Boundaries

The San Diego River Park Subdistrict includes the River Corridor Area and the River Influence Area. The River Corridor Area comprised of the current 100-year floodway (floodway) as mapped by Federal Emergency Management Agency (FEMA) and the 35-foot wide Path Corridor on each side of the floodway. Figure 1 illustrates how the River Influence Area is the 200-foot wide area extending outward from the River Corridor Area on each side of the river.




FIGURE 16: SECTION / PLAN VIEW OF RIVER CORRIDOR & INFLUENCE AREA

RIVER CORRIDOR AREA

Permitted Uses and Development

Development within the floodway shall be in accordance with Land Development Code Section 143.0145 (Development Regulations for Special Flood Hazard Areas).

- Within the 35-foot wide Path Corridor only the following development shall be allowed: the San Diego River Pathway, trails, and passive recreational uses, as determined by the City Manager, including picnic areas, scenic or interpretive overlooks, fitness stations, seating and educational exhibit areas.
- Within locations that are not mapped as Multi-Habitat Planning Area (MHPA), as identified by the City of San Diego MSCP Subarea Plan, or determined to be wetland buffers in accordance with Land Development Code Section 143.0141, the following development shall be allowed; children's play areas, multi-purpose courts, turf fields and development determined by the City Manager to be for active recreation use.
- Portions of the 35-foot wide Path Corridor that are mapped as MHPA, as identified by the City of San Diego MSCP Subarea Plan, or determined to be wetland buffers in accordance with Land Development Code Section 143.0142 shall be developed in accordance with the MSCP Land Use Considerations and the Environmentally Sensitive Lands Regulations in Chapter 14, Article 3, Division 1 of the Land Development Code.

Grading

- Grading within the floodway shall be conducted in accordance with MSCP Land Use Considerations and the Environmentally Sensitive Lands Regulations in Chapter 14, Article 3, Division 1 of the Land Development Code.
- Grading within the 35-foot wide Path Corridor shall, to the satisfaction of the City Manager;
a) Avoid long continuous engineered slopes with hard edges; b) provide gradual transitions at the top and bottom of the slopes; c) and stabilize and revegetate slopes with native plants consistent with the surrounding habitat type.

San Diego River Pathway

Development on a lot located wholly or partially in the River Corridor Area shall include a San Diego River Pathway and shall meander to the satisfaction of the City Manager.

Where portions of the Path Corridor are mapped as MHPA, as identified by the City of San Diego MSCP Subarea Plan, or determined to be wetland buffers in accordance with Land Development Code Section 143.0141, the San Diego River Pathway shall be located outside the MHPA and the wetland buffer, immediately adjacent to the Path Corridor. See Figure 2, Path Corridor Realignment for MHPA and Wetland Buffer.

The San Diego River Pathway shall be dedicated with an easement that allows public access and shall be completed in the first phase of any phased development.

The San Diego River Pathway shall include the following features:

- A minimum 10-foot wide pathway of concrete or similar material, in a color that blends with the surrounding native soil.
- A minimum two-foot wide area of decomposed granite or similar material along each side of the San Diego River Pathway in a color similar to the San Diego River Pathway.
- A minimum 10-foot wide landscape area between the floodway and the San Diego River Pathway.
- A minimum 12-foot vertical clearance above finished grade of the San Diego River Pathway.

Trails

Pedestrian-only trails may be located within the River Corridor Area in accordance with the following:

- Trail alignments shall mimic natural conditions and minimize grading and disturbance to vegetation.
- Trails shall be designed to provide continuous loops to the San Diego River Pathway, with no trail alignment resulting in a dead end.
- Trails located in areas mapped MHPA, as identified by the City of San Diego MSCP Subarea Plan, or determined to be wetland buffers in accordance with Land Development Code Section 143.0141 are subject to the MSCP Land Use Considerations and the Environmentally Sensitive Lands Regulations in Chapter 14, Article 3, Division 1 of the Land Development Code.
- Trails shall include the following features: i) A maximum eight-foot width; ii) An eight-foot vertical clearance above finish grade of the trail; and iii) Surface material shall be decomposed granite or similar material in a color that blends with the surrounding native soil.

Picnic Areas and Overlooks

- Development on a lot located wholly or partially in the River Corridor shall include at least one picnic area or overlook along the San Diego River Pathway unless either exists less than one-half mile away. Picnic areas and overlooks shall include a combination of site furniture, such as picnic tables, trash and recycling receptacles, bicycle racks, shade structures, benches, interpretive signs and drinking fountains, to the satisfaction of the City Manager.




FIGURE 17: PATH CORRIDOR REALIGNMENT FOR MHPA AND WETLAND BUFFER

Lighting

- Shall be provided along the San Diego River Pathway as necessary to provide for security and personal safety. Light poles shall not exceed 12 feet in height. All lighting shall be shielded and directed away from the floodway, the edge of the San Diego River Pathway fronting the river and the MHPA.

Site Furniture

- Shall be designed in accordance with the San Diego River Park Master Plan Design Guidelines and include the San Diego River Park Logo. Shall be provided along the San Diego River Pathway at picnic areas, overlooks and other locations that complement the San Diego River Pathway. Lots that do not have picnic areas or overlooks shall include along the San Diego River Pathway a minimum of one piece of site furniture for every 200 linear feet of the San Diego River Pathway.

Signs

- Shall be designed in accordance with the San Diego River Park Master Plan Design Guidelines and include the San Diego River Park Logo. Overlooks shall include, at a minimum, one interpretive sign. Information Kiosks (as described in the San Diego River Park Master Plan Design Guidelines) shall be provided at any location where the San Diego River Pathway intersects a public street.

Fences

- Located between the San Diego River Pathway and the River shall be provided only as required to protect sensitive habitat or historic resources, and shall allow for wildlife movement. Fences shall be in accordance with the following:
- Located a minimum of five feet from the San Diego River Pathway or trails and shall follow the natural grade.
- Consist of horizontal rails of either wood peeler log or steel posts and cables, c) maximum height of 42 inches, and shall be at least 75 percent open.
- For purposed of this subsection, chain link fencing shall not qualify as a 75 percent open fence.

Plant Materials

- The River Corridor Area shall include a mixture of native plants and trees consistent with the surrounding habitat type.
- Non-native grasses and lawn areas shall not be permitted in any areas mapped MHPA, as identified by the City of San Diego MSCP Subarea Plan, or determined to be wetland buffers in accordance with the Land Development Code Section 143.0141.

Visual Openings

- Views within the River Corridor Area shall be maintained at the pedestrian level along the San Diego River Pathway by using tall canopy trees, rather than short bushy trees. Plant materials shall be selected and located in order to provide views to the river along at least 50 percent of the river side of the San Diego River Pathway of each lot.

Plant Material Adjacent to the San Diego River Pathway

On the river side of the San Diego River Pathway and within 10 feet of the non-river side of the San Diego River Pathway:

- Trees shall have a canopy clearance of eight feet above the finish grade of the San Diego River Pathway
- All other plant materials shall not exceed a mature and natural growth habit of 30 inches in height above the finish grade of the San Diego River Pathway.

Buildings Height and Massing

- Maximum building height and massing on lots adjacent to the River Corridor Area shall be determined by the distance the building is set back from the River Corridor, and shall be in compliance with Table 2A or the base zone, whichever is more restrictive*. See Figure 3, River Influence Area Maximum Building Height and Setback.

* Except for properties located along Fairmount Avenue within the Grantville neighborhood, where the maximum building height allowed shall be 70 feet.

TABLE 5: RIVER INFLUENCE AREA SETBACK, HEIGHT AND MASSING

Minimum Distance the Building is Set Back from the River Corridor Area ⁽¹⁾	Maximum Building Height Allowed	Massing
10 feet ⁽²⁾	35 feet	No more than 50 percent of a building's wall may be located at the setback measured from the River Corridor Area.
20 feet	45 feet	Not regulated by this Division
30 feet	70 feet	At or above 70 feet in height above finished grade, a building's wall shall be at least 30 percent narrower than the width of the building wall on the ground floor.
70 feet	The maximum building height allowed is equal to the number of feet the building is set back from the River Corridor Area.	
115 feet	The maximum building height allowed is established by the base zone.	Not regulated by this Division

⁽¹⁾ Where river and street setbacks overlap, the requirements of the River Influence Area shall apply.

⁽²⁾ Buildings shall be set back a minimum of 10 feet from the River Corridor Area. Architectural features such as eaves, cornices, eyebrows, trellises, bay window balconies, entry roofs and arbors, and fireplaces may extend a maximum of 4 feet into the 10-foot setback.




FIGURE 18: RIVER INFLUENCE AREA MAXIMUM BUILDING HEIGHT AND SETBACK

Setbacks not identified in Table 2A

- Refer to the Base Zone.

Off Setting Planes

- Offsetting planes requirements of the Base Zone and the Navajo Community Plan CPIOZ shall apply.

Building Façade and Entrance

- Development that abuts the River Corridor Area shall, provide a river-fronting façade and entrance that are of substantially equivalent design and quality of materials as the primary building façade and entrance to the satisfaction of the City Manager.

Building Transparency

- Building facades that front the River Corridor Area or building facades that front a street that abuts and runs parallel to the River Corridor Area shall provide building transparency in accordance with the following:
- The amount of transparency, measured as the visible light transmittance (VLT) shall be at least 0.65 VTL.
- Commercial and Mixed Use Zones, a minimum of 50 percent of the total façade shall be transparent and a minimum of 70 percent of the ground floor (between finish grade and the full height of the first floor) shall be transparent,
- Industrial Zones a minimum of 25 percent of the total façade shall be transparent.

Building Reflectivity

- Building facades that front the River Corridor Area shall not include materials with a visible light reflectivity (VLR) factor greater than 10 percent.

Exterior Equipment Enclosures, Outdoor Storage, Loading Areas and Refuse Collection Areas

Shall be in accordance with the following:

- Located a minimum of 100 feet from the River Corridor Area.
- Shall be screened with landscape and an opaque wall at least 6 feet in height or, if the item to be screened exceeds 6 feet in height, a wall 1-foot taller than the item, to a maximum wall height of 10 feet shall be provided. Screening shall be of the same design and materials as the primary building façade.
- Loading areas shall also comply with the requirements of Land Development Code Section 1514.0403(d) Off Street Freight Loading Spaces Required.

Off-Street Surface Parking

- Off-street surface parking areas located adjacent to the River Corridor Area shall be set back and screened for the full height and length of the parking area, with one or more of the following:
- Shall be screened with residential, commercial, industrial, or mixed use development, in accordance with the base zone; or
- Screened with landscape materials, in which case the following shall apply: i) Parking areas shall be setback a minimum of 20 feet from the River Corridor Area; ii) Parking areas adjacent to the River Corridor Area shall not exceed 30 percent of the length of the lot frontage along the River Corridor Area or a maximum of 120 feet of the lot frontage along the River Corridor Area, whichever is less; iii) Parking areas shall be screened with shrubs capable of achieving a minimum height of 30 inches along 80 percent of the length of the parking area along the River Corridor Area frontage within a 2 year period, except that screening shall not be required at pedestrian access points; and iv) Screening for parking

areas shall include one 24-inch box evergreen tree for every 30-foot of frontage along the River Corridor Area. The trees shall be spaced apart or in naturalized groupings.

Parking Structures

Parking Structures located adjacent to the River Corridor Area shall be set back and screened for the full height and length of the parking area, with one or more of the following:

- Shall be screened with residential, commercial, industrial, or mixed use development, in accordance with the base zone; or
- Shall be screened with landscape materials in accordance with Section (8)(b) and in which case the following provisions shall apply; i) Parking structures shall be setback a minimum of 30 feet from the River Corridor Area; and ii) Parking structures adjacent to the River Corridor Area shall not exceed 50 percent of the length of the lot frontage along the River Corridor Area.

Streets that Abut and Run Parallel to the River Corridor Area

- Shall be the minimum width allowed by the Street Design Manual of the Land Development Manual. Development shall be designed to minimize the number of curb cuts, to the satisfaction of the City Manager. On-street parking shall be provided in clusters of parking bays along the river side of the street.

Building Access to the River Corridor Area

Development on lots that abut the River Corridor Area shall provide building access paths connecting the primary structure with the San Diego River Pathway in accordance with the following:

- One building access path for every 300 linear feet of river frontage.
- The building access path shall be to the primary building entrance or to a secondary entrance that, to the satisfaction of the City Manager, is of substantially equivalent design and quality of materials as the primary entrance.

Public Access Pathway Across a Development Site

Development on lots that abut the River Corridor Area shall provide public access pathways connecting the public street and the San Diego River Pathway in accordance with the following:

- At least one public access pathway shall be provided for every 1,000 linear feet of frontage along the River Corridor Area.
- The public access pathway shall be designed to the same quality as the primary on site pathways, to the satisfaction of the City Manager.
- A public access pathway sign shall be provided at the public street and at the intersection of the San Diego River Pathway to identify the entry to the public access pathway and shall be placed in a clearly visible location.
- An easement for public use shall be required for public access pathways.

Public Access Pathways from Streets that Abut and Run Parallel to the River Corridor Area

Public access pathways shall connect the street to the San Diego River Pathway at every street intersection and, at a minimum, provide a connection every 1,000 linear feet of street frontage along the River Corridor Area.

Lighting

All lighting within 100 feet of the River Corridor Area shall be shielded and directed away from the River Corridor Area.

Fences

Within the 10-foot building setback area, only the following fences are permitted:

- A solid fence not to exceed three feet in height.
- A fence that is at least 75 percent open and does not exceed 6 feet in height; or
- A combination of a 3-foot tall solid fence topped with a 3-foot tall fence that is at least 75 percent open.
- d) For purposes of this Section, chain link fencing shall not qualify as a 75 percent open fence.

Signs

- Within 100 feet of the River Corridor Area, wall signs fronting the river shall not exceed a height of 15 feet above finish grade.
- Ground signs between a building and the River Corridor Area shall be monument signs not to exceed five feet in height and shall be located within a landscaped area at least equivalent to the area of the sign face.
- Signs fronting the River Corridor Area shall be face lighted or internally lighted.

Plant Material

- Plant materials within 15 feet of the River Corridor Area shall be non-invasive low water use species.

OPEN SPACE RETENTION AND UTILIZATION


INTRODUCTION

In its broadest sense, the term "open space" refers to all land that is not used for buildings or structures. It may be either urban or non-urban. Open spaces affect the character of development and vice versa. Among other things, open space offers aesthetic variety and relief, shapes the environment, stabilizes other land uses, reduces noise and conserves natural resources.

The reasons for retention of open space are many. The more important of these were spelled out by the late President Kennedy in a special message to Congress: "Open space must be reserved to provide parks and recreation, conserve water and other natural resources, prevent buildings in undesirable locations, prevent erosion and floods and avoid the wasteful extension of public services and control the rate and character of community development."¹³

Urbanization is frequently unattractive and ugly. However, it need not be so; if man desires, he can remedy the physical blight and decay within aesthetically offensive areas by strategically introducing openness and greenery, thus providing sorely needed leavening for both visitor and resident.

Open space can serve a most important function by inhibiting that amorphous type of development commonly referred to as "urban sprawl," an affliction visited upon so many large urban areas. Open space also serves to limit concentrations of people and improvements under aircraft flight patterns or on floodplains. It should be used to minimize development in areas subject to geological hazards such as earth slippage and landslides.



³ President John F. Kennedy, "Our Nation's Housing," an address to the first session of the 87th Congress, March 9, 1961.

Open space has economic value and indirect benefits that are not generally recognized. For example some lands within highly urbanized areas may be more expensive to develop from the public standpoint than they are worth. As has been pointed out in a recent study, the "direct public benefits of a regional open space system would include:

- Income from leases on open space lands for agricultural, recreational, or other compatible uses.
- User benefits (in terms of dollar values) accruing to the public.
- The non-recoverable value of the public's investment in open space land."²⁴

Indirect benefits deriving from the impact of the open space program on urban development patterns would include a series of non-measurable social, economic, and environmental benefits. In addition, a savings in utility costs might also be realized.

Open space may prove directly profitable in other cases as well. A number of examples have been reported where urban open space, especially in the form of city parks, has enhanced the value of surrounding properties to the point where the tax received from those properties exceeds any tax yield that might have been realized had the area of open space been built upon. A good example in the City of San Diego is the area surrounding Balboa Park.

This Plan is an attempt at fulfilling our obligation of leaving a meaningful legacy to future generations. For the long-range good of the entire community, generous expansions of natural open space must be preserved.

In summary, the case for open space in aggregate is impressive. While specific quantitative standards, like those utilized in determining needs for neighborhood and community park facilities, have not been developed for open space systems, the City of San Diego and the Navajo community have recognized this need.

A unique feature in the Navajo Community Plan is the open space element designed to preserve the river, scenic canyon and hillside areas, and to link elements of the community. The proposed open space areas will become green belts and will provide areas for pedestrian, bicycle or equestrian uses. The open space system conceived for the Navajo community envisions that the canyon and hillside areas could be used for both active and passive recreational uses. The majority of open space, however, will probably remain in its natural state, with pathways and picnic areas.

The study area contains many outstanding examples of open space as defined above. There are over 700 acres of scenic canyons, including Mission Gorge, which are dominant topographical features of the Navajo community. These canyons contain a natural reserve of trees and wildlife-resources that are quickly vanishing from the San Diego scene.

⁴ **AN OPEN SPACE SYSTEM** for the San Diego Region, San Diego Comprehensive Planning Organization, Open Space Study: Report No. 1, Livingston & Blayney, Royston, Hanamoto, Beck and Beck, April 1972.

The San Diego River, another significant feature of the community, traverses Mission Trails Regional Park through Mission Gorge and is responsible for creating much of the existing topography. That portion of the river located in the northeast section of the community has been significantly altered as a result of an ongoing sand and gravel extraction operation. Much of the area in and around the river has already been mined and is currently being used for industrial and contractor storage and operation uses.



A mix of retail, industrial and industrial office park uses have been developed along that portion of the river that forms the western boundary of the Navajo planning area. The existing development has not taken advantage of the aesthetic qualities of the river environment, nor the passive recreation value of the river and wetlands abutting these sites, but has instead turned its back on the river. It is critical that future development proposals along the river be required to incorporate sensitive site design in addition to providing measures for protecting riparian habitat.

OBJECTIVES

Because there is pressure for intense use of land located within the urban complex, the following principal or overriding open space objective was adopted:

DESIGNATE AND PRESERVE OPEN SPACE BEFORE DEVELOPMENT TAKES PLACE.

In this way, it is possible for the best land available for recreation and open space to be preserved to provide a framework for subsequent development. The assignment of a high priority to recreational open space development requires immediate action if preservation is to take place.

The Navajo community recognizes that there is a need to provide adequate and accessible open space for the needs of the population and that without positive action the community may lose this valuable open space through the development of the river area, canyons and hillsides.

Therefore, the following additional objectives were adopted:


- Preserve, improve and reconstruct the wetlands and riparian habitat areas in and along both sides of the San Diego River.
- Enhance and maintain the aesthetic and recreational qualities of the San Diego River corridor as part of the open space system.
- Conserve the present amenity of Navajo, Rancho Mission, Mission Gorge and other canyons for the enjoyment of this generation and as a legacy for succeeding generations.
- Establish and preserve a total open space system in perpetuity and guard against its commercialization. Preserve the natural environment including wildlife, vegetation, and terrain.


- Permit only those uses within the system that are compatible with the open space concept.
- Ensure that any public improvements such as roads, drainage channels and utility services and any private lessee developments be compatible with the objectives of the open space system.
- Ensure that development of properties adjoining the open space system is in a manner compatible with the natural environment and in conformance with the Mission Trails Design District Ordinance and Design Manual and the San Diego River Park Master Plan.

PROPOSALS

The overall system entails a network of open space belts connecting larger open space areas. These areas for the most part are located in the canyons, along the San Diego River, and on Cowles Mountain as shown on the following map.


- The open space areas, including over 700 acres divided among Navajo Canyon (179 acres), Rancho Mission Canyon (258 acres), and Mission Gorge (300 acres), should be preserved in a substantially open character. Mission Gorge (the San Diego River System) should be given high priority for acquisition as a part of the City's open space system.
- Open space should initially be maintained in its natural condition. Studies, however, should be undertaken to determine uses compatible with the open space concept. Such uses, designed with consideration for topography, vegetation and access, may include archery ranges, hiking, biking trails, picnic facilities, wildlife preserves, and non-vehicular camping facilities.
- Any public improvements such as roads, drainage channels and utility services as well as any private lessee developments should be compatible with the objectives of the open space system. No through roads will be permitted except for the extension of Navajo Road, designed to parkway standards, through Navajo Canyon and the extension of Jackson Drive.
- Safe, convenient access should be established and maintained to all open space areas.





OPEN SPACE PROPOSALS

 OPEN SPACE ACQUISITION PRIORITY
MISSION GORGE



CITY OF SAN DIEGO • PLANNING DEPARTMENT

FIGURE 19: OPEN SPACE PROPOSALS

- In the event that those open space areas illustrated on page 77 are not acquired they should be permitted to develop according to the following guidelines:
- Low residential densities not to exceed one dwelling unit per acre in those areas falling within the Hillside Review (HR) Zone, except as noted below.
- In all cases improvements should implement the intent of the HR Zone, which is to “ensure that development results in minimum disturbance of natural terrain.”
- The implication of this requirement is that densities for a given ownership will be transferred and clustered on the flattest and most developable land.
- Development in open space areas, including those in the HR Zone, should be guided by the following additional criteria:
 - Slopes of 0-12 percent should be permitted to develop up to two dwelling units per acre.
 - Slopes of 13-24 percent should be permitted to develop up to two dwelling units per acre.
 - Slopes of 25 percent and greater should be permitted to develop no more than one dwelling unit per acre.

An exception to the above guidelines is:

- That portion of the Navajo Canyon westerly of Waring Road, which should be limited to residential use of one dwelling unit per acre due to its location, restricted access and projected traffic conditions. A Planned Commercial Development for this area would be considered to allow for uses compatible with the open space concept, such as plant nurseries, etc.
- Residential development within the canyons should be designed to preserve natural amenities such as topography, trees and streams in an open space linkage system. Further studies would have to be undertaken to minimize problems such as drainage, unattractive hillside cuts, access, and inadequate public facilities resulting from increased population.
- If the canyons adjacent to existing or future school sites are not obtained for open space, a neighborhood park with a minimum of five acres should be reserved next to each school.

Development along the San Diego River should be regulated to minimize the disturbance to wetland habitat areas. The San Diego River Park Subdistrict of this Plan contains objectives and proposals for development of the river located within the Navajo community. These objectives and proposals have been incorporated into the River Park Subdistrict Community Plan Implementation Overlay Zone (CPIOZ B). All development proposals for property within the River Park Subdistrict CPIOZ will be required to comply with the CPIOZ B Supplemental Development Regulations contained within this Community Plan.

In addition to the CPIOZ for the San Diego River Subdistrict, future development along the river shall meet the requirements of the Multiple Species Conservation Program (MSCP) Subarea Plan and the requirements of the Environmentally Sensitive Lands Regulations. The MSCP has been prepared pursuant to the general outline developed by the United States Fish and Wildlife Service and the California Department of Fish and Game (herein referred to as the “Wildlife

Agencies”) to meet the requirements of the California Natural Communities Conservation Planning Act of 1992.

The MSCP is a comprehensive habitat conservation planning program that addresses multiple species habitat needs and the preservation of native vegetation communities in the San Diego region and was adopted by City Council in 1997. This Subarea Plan forms the basis for the Implementing Agreement which is the contract between the City and the Wildlife Agencies that ensures implementation of the plan and thereby allows the City to issue take permits at the local level. The MSCP’s core, hardline biological preserve system has been mapped by the City in cooperation with the Wildlife Agencies, property owners, developers, and environmental groups and is referred to as the Multi-Habitat Planning Area (MHPA).

The MHPA delineates core biological resource areas and corridors targeted for conservation. Within the MHPA limited development may occur and all development must meet the MSCP Section 1.4, Land Use Considerations and the Framework Management Plan guidelines. The MSCP is implemented by the City through the Environmentally Sensitive Lands (ESL) Regulations of the City’s Municipal Code. Also contained in the ESL are regulations on impacts to wetlands. A wetland buffer is required for all wetlands as appropriate to protect the functions and values of the existing wetland. The width of the wetland buffer is determined at the time of project proposal and the existing quality of the wetland area. It should be noted that the MHPA and the wetland buffer requirements take precedence over the San Diego River Subdistrict. The San Diego River Pathway will be required to be outside the MHPA and the wetland buffer.

- Establish regulatory zoning in the form of the Floodway (FV) and Floodplain Fringe (FPF) Zones along the entire length of the river corridor. The City Engineer should prepare the studies leading to the application of these zones.
- Establish hiking trails in the San Diego River Basin through Mission Gorge, which will minimize impacts to the riparian habitat. Trails should be located adjacent to the river within the buffer area in a manner that focuses activity away from sensitive habitat areas. Access to the habitat area should be discouraged through the design of the trails and the use of specialized plantings. Because horses can attract the brown-headed cowbird, a least Bell's vireo nest parasite, it is necessary to mitigate the effects of equestrian activities when they are near vireo habitat. During nesting season the trails should be closed.
- Restoration of the riparian habitat in the floodway should be pursued in lieu of channelization. If potential impacts to public health or safety clearly necessitate channelization, the channel should be soft-bottomed and soft-sided, and should be designed of sufficient width to support riparian vegetation across the width of the channel and to convey the 100-year flood

PARKS & RECREATION FACILITIES

OVERVIEW

The park system in the Navajo Community is made up of population-based parks, resource-based parks and open space lands. Population-based parks and recreation facilities are located within close proximity to residents and are intended to serve the daily needs of the community. The City's General Plan population-based park standard is to provide a minimum of 2.8 useable acres per 1000 residents. In communities that are built out and where there are land constraints, the City's General Plan states that Park Equivalencies should be considered to satisfy some of the community's population-based park needs during a community plan update or amendment. Park equivalencies could include Joint Use Facilities, Trails, Portions of Resource-based parks, Privately-owned Park Sites, and Non-traditional Park Sites.

Within the redevelopment of the Grantville area, public recreational opportunities should provide connections to Navajo's regional recreational and open space areas through linear parks along Alvarado Creek and the San Diego River. Locating neighborhood parks and/or pocket parks in centralized locations within Grantville, such as adjacent to the Trolley Station and along the San Diego River, would foster the re-establishment of the community's relationship with the San Diego River and Alvarado Creek. In addition, locating linear and pocket parks within the Grantville boundaries will enhance the community's character and create a sense of place by providing opportunities for social interaction and passive and active recreation for residents, employees and visitors.

The following is a discussion of the existing and proposed population-based parks and recreation facilities, including park equivalencies that are consistent with the General Plan's policies (See Table 3, Summary of Existing and Future Population-based Parks and Recreation Facilities), Resource-based parks and open space land are discussed at the end of the Parks and Recreation Element.

POPULATION-BASED PARKS, RECREATION CENTERS AND AQUATIC COMPLEXES

Per the General Plan Park standards, population-based parks consist of six facility types: 1) major park; 2) community park; 3) neighborhood park; 4) mini-park; 5) pocket park or plaza; and 6) special activity park. Typically, major parks are a minimum of 20 acres and serve single or multiple communities and provide specialized facilities that serve large populations. Community parks are a minimum of 13 useable acres, serve a population of 25,000, and provide a wide range of facilities including active and passive recreation, recreation centers, aquatic complexes and multi-purpose sports fields. Neighborhood parks are 3 – 13 useable acres; serve a population of 5,000 persons within approximately one mile radius. These parks generally provide picnic areas; children's play areas, multi-purpose courts, multi-purpose turf areas, comfort stations, walkways and landscaping. Mini parks are 1 to 3 useable acres within a half mile radius; Pocket parks and plazas are typically less than 1 useable acres within a quarter mile radius from residents to be served. Special activity parks vary depending upon the activity and population served.

The General Plan also established minimum standards for recreation centers and aquatic complexes based on population. A recreation center, typically 17,000 square feet in size, should be provided for every 25,000 residents, and an aquatic complex should be provided for every 50,000 residents. The following existing and future population-based parks, recreation centers and aquatic complexes are described below:

San Carlos Community Park and Recreation Center

The existing community park, 10.5 acres with 9.41 useable acres, is located on Lake Adlon Drive and adjacent to the Forward Elementary School. This existing park features a recreation center, multi-purpose courts, on-site parking, walkways, picnic areas, children's play area, multi-purpose fields and passive lawn areas. The existing Recreation Center (11,880 square feet) provides indoor multi-purpose courts and community meeting rooms. Future improvements to the San Carlos Community Park should include sports field lighting to expand the use of the fields and the expansion of the recreation center to a 17,000 square foot building.

Allied Gardens Community Park, Recreation Center and Aquatic Complex

The existing community park, 13.5 acre site with 13.5 useable acres, is located on Greenbrier Drive and adjacent to Lewis Middle School. This existing park features a recreation center, an aquatic complex, multi-purpose courts, on-site parking, picnic areas, walkways, children's play area, and passive lawn areas. The existing recreation center (9,186 square feet) provides indoor multi-purpose courts and community meeting rooms. Future improvements to the Allied Gardens Community Park should include the replacement of the existing recreation center and providing a new 17,000 square foot building. The existing aquatic complex should be expanded to provide indoor locker rooms and showers, a new therapeutic pool and children's pool, expansion of the spectator areas and necessary upgrades to the existing pool. In addition, upgrades to the existing children's play areas to meet accessibility standards should be provided.


Lake Murray Community Park

The existing community park, 45.83-acre site with 41.86 useable acres, is located on Murray Park Drive and contiguous to Lake Murray. This existing park features tennis courts, ball fields, parking, comfort station, children's play area, passive lawn areas, walkways and trails through natural open space areas. Future improvements to the Lake Murray Community Park should include; the expansion of the parking lot (approximately 200 cars) and roadway adjacent to the central ball fields; the expansion of the children's play area with additional play equipment, site furnishings, picnic shelters and a comfort station; and the design and construction of a ball field and parking at Cowles Point, as shown on the approved General Development Plan. Synthetic turf and sports field lighting for several fields should be considered to expand the use of the fields.



PARK & RECREATION FACILITIES

- Resource Based Park/Open Space Lands
- Existing Parks
- Proposed Parks/Joint Use
- Existing Joint Use
- Rec Center
- Swimming Pool



CITY OF SAN DIEGO • PLANNING DEPARTMENT

FIGURE 20: PARK AND RECREATION FACILITIES

Qualcomm Major Park and Recreation Center (future)

This future major park is planned to be 30 acres within the Qualcomm Stadium site, located off of Friars Road and adjacent to the San Diego River. This major park would serve both the Mission Valley and Navajo communities. Navajo community's portion would be approximately 10 acres of the 30 acres and provide active and passive recreation needs including lighted sports fields, picnic areas, children's play areas, multi-purpose courts, walkways, landscaping, and parking. In addition special activities such as skateboard, dog off leash and other unique uses could be located within the park. A Recreation Center of 25,000 square feet is proposed to serve both communities. The Navajo community's portion would be approximately 5,000 square feet. The Recreation Center could provide indoor gymnasium, multi-purpose courts, multi-purpose rooms, kitchen and other community-serving facilities.

Dailard Neighborhood Park

The existing neighborhood park, 5.1 acre site with 3.30 useable acres, is located on Cibola Road and is adjacent to the Dailard Elementary School. Park amenities include children's play area, walkways and passive turf areas.

Tuxedo Neighborhood Park

The existing neighborhood park, 9.37 acre site with 5.62 useable acres, is located on Tuxedo Road. Park amenities include passive lawn areas, walkways, volley ball courts and children's play area.

Princess Del Cerro Neighborhood Park

The existing neighborhood park, 5.48 acre site with 4.4 useable acres, is located on Wenrich Drive. Park amenities include basketball courts, walkways, passive lawn areas, picnic areas and children's play area.

Grantville Neighborhood Park

The existing neighborhood park, 2.53 acre site with 2.28 useable acres, is located on Vandever Avenue. Park amenities include passive lawn areas, children's play area, walkways, and picnic facilities.

Rancho Mission Neighborhood Park

The existing neighborhood park, 18.84 acre site with 9.42 useable acres is located on Margerum Avenue. Park amenities include passive lawn areas, walkways through natural open space, picnic areas and on-site parking.

San Carlos Pocket Park

The existing pocket park, 0.30 useable acres, is located on East Lake Drive. Park amenities include walkways, seating and landscaping.

Pasatiempo Neighborhood Park (Future)

This future neighborhood park, 10.69 acre site with 5.0 approximate useable acres, is located on Pasatiempo Avenue. Park amenities could include passive lawn areas, walkways, picnic areas, small multi-purpose courts, children's play area, comfort station and on-site parking.

Bedlow Neighborhood Park (Future)

This future neighborhood park, 3.0 acre site with 2.5 approximate useable acres, is located on Bedlow Avenue. Park amenities could include picnic areas, children's play areas, passive lawn areas, walkways and landscaping.

Pasatiempo Open Space Park (Future)

This future open space park, 5.2 acre site with 2.0 approximate useable acres, is located on Pasatiempo Avenue. Park amenities could include walkways, native landscaping, fitness course and picnic facilities that take advantage of the panoramic views.

PARK EQUIVALENCIES

The General Plan standards for Park Equivalencies state that they must be easily accessed by the public, consistent with existing Resource-based Parks Master Plans and include typical population-based park components and facilities. Categories include; joint use facilities, trails, portion of resource-based parks, privately owned park with public access easements, non-traditional park sites and facility expansion or upgrade. The following existing and future park equivalencies for the Navajo community are described below:

JOINT USE FACILITY – PARK EQUIVALENCY:

Benchley/Weinberger Elementary (Future)

This future joint use facility, 3.40 useable acres, is located on the corner of Twin Lake Drive and Gloria Lake Avenue. Joint use amenities could include multi-purpose fields, multi-purpose courts, and walkways. Synthetic turf should be considered to expand the use of the fields.

Dailard Elementary

The existing joint use facility, 2.98 useable acres, is located on Cibola Road. Joint use amenities include multi-purpose turf field.

Forward Elementary

The existing joint use facility, 4.50 useable acres is located on Boulder Lake Drive adjacent to San Carlos Community Park. Joint use amenities include multi-purpose fields with two backstops. Future amenities could include an additional multi-purpose field with School District approval.

Foster Elementary (Future)

This future joint use facility, 3.0 useable acres, is located on the corner of 51st street and Zion Avenue. Joint use amenities could include multi-purpose fields, multi-purpose courts, and walkways. Synthetic turf should be considered to expand the use of the fields.

Gage Elementary (Future)

This future joint use facility, 4.7 useable acres, is located on the corner of Bisby Lake Drive and Hudson Drive. Joint use amenities could include multi-purpose fields, multi-purpose courts, and walkways. Synthetic turf should be considered to expand the use of the fields.

Grantville Elementary (Future)

This future joint use facility, 2.2 useable acres, site is located on Decena Drive. Joint use amenities could include multi-purpose fields, multi-purpose courts, and walkways. Synthetic turf should be considered to expand the use of the fields.

Green Elementary (Future)

This future joint use facility, 3.2 useable acres, is located on the corner of Wandermere Driver and Green Gables Avenue. Joint use amenities could include multi-purpose fields, multi-purpose courts, and walkways. Synthetic turf should be considered to expand the use of the fields.

Hearst Elementary

The existing joint use facility, 4.18 useable acres, is located on Del Cerro Blvd. Joint use amenities include several sports fields with backstops and a children's play area.

Lewis Middle School

The existing joint use facility, 9.58 useable acres, is located on Irwin Avenue and adjacent to Allied Gardens Community Park. Joint use amenities include several sports fields with backstops. Future improvements should include synthetic turf and sports field lighting on the upper field and the lower field, known as Skunk Hollow area.

Marvin Elementary (Future)

This future joint use facility, 3.4 useable acres, is located on Brunswick Avenue. Future joint use amenities could include multi-purpose fields, multi-purpose courts, and walkways. Synthetic turf should be considered to expand the use of the fields.

Pershing Middle School

The existing joint use facility, 10.0 useable acres, is located on San Carlos Drive. The general development plan for the joint use facility includes multi-purpose fields, a comfort station, two shade structures, and a park entry sign. The future Phase I of the design was completed in 2006 and provided 5 acres of the multi-purpose synthetic turf fields. Phase II is to provide the

remaining synthetic turf fields (5 acres), a comfort station, two shade structures, a park sign and sports lighting on two fields to expand their hours of use.

TRAILS – PARK EQUIVALENCY:

Navajo Canyon Open Space Trails (Existing/Future)

These existing and future trails, approximately 15,300 lineal feet, are located in the center of the open space canyon and accessed from Waring Road, Lyden Road, Carthage Street and Eldridge Road. New trail amenities could include 3,200 lineal feet of new trails, trail kiosk, trail makers, interpretive signs, native landscaping and benches or picnic areas where appropriate.

Rancho Mission Canyon Open Space Trails (Existing)

These existing trails, approximately 21,900 lineal feet, are located throughout the open space canyon and accessed from Conestoga Street, Margerum Street, Hemingway Street, Cabaret Street and Navajo Street. In addition, trails within Rancho Mission Neighborhood Park provide access to the canyon trails. New trail amenities include trail kiosk, trail makers, interpretive signs, native landscaping and benches or picnic areas where appropriate.

PORTION OF RESOURCE-BASED PARK – PARK EQUIVALENCY

Deerfield Bike Skills Area at Mission Trails Regional Park (Future)

This future park, approximately 12 acres, is located in the western area of Mission Trails Regional Park. Park amenities could include typical components of bike skills parks, including overlook areas, picnic areas, walkways, parking, and native landscaping.

Deerfield Canyon Nature Park at Mission Trails Regional Park (Future)

This future park, approximately 2 acres, is located in the western area of Mission Trails Regional Park. Park amenities could include picnic areas, trails, interpretive panels, fitness course, children's play area of natural looking play structures, parking and native landscaping.

San Diego River Park Trail at Mission Trails Regional Park (Future)

The San Diego River Park Trail, approximately 4.3 miles, is located within the Mission Trails Regional Park. This trail will provide a western connection to Grantville Neighborhood and an eastern connection to Mission Trails Regional Park East Fortuna Staging area. Of the 4.3 miles of trail, 1.9 miles, approximate, exists along Father Junipero Serra trail and 2.4 miles, approximate, of new trail area are proposed. The new trail, depending on site conditions, will be approximately 4' to 14' feet wide and include a 5' to 10' feet wide buffer on each side to provide native landscaping, information kiosks, interpretive signs, identification/directional signs and benches/picnic tables where appropriate.

PRIVATELY OWNED PARK WITH A RECREATION EASEMENT – PARK EQUIVALENCY

Shawnee Neighborhood Park (Future)

This privately owned park, 5.3 acres, with a recreation easement for public use, is located on the north side of Mission Gorge Road and contiguous with the San Diego River Park. This future park will provide typical neighborhood park amenities, such as multi-purpose fields, multi-purpose courts, walkways, plazas, children’s play area, seating, picnic areas, and landscaping. In addition the park will also provide a section of the San Diego River Park pathway.

**TABLE 6: SUMMARY OF EXISTING AND FUTURE POPULATION-BASED
PARKS AND RECREATION FACILITIES**

Existing and Future Population-based Parks	Existing Useable Acres	Future Useable Acres	Total Acres
Community Parks:			
Allied Gardens	13.35		
Lake Murray	41.86		
San Carlos	9.14		
Qualcomm Major Park (future)		10.00	
Total Community Parks:	64.35	10.00	74.35
Neighborhood Parks:			
Bedlow (future)		2.50	
Dailard	3.30		
Grantville	2.28		
Pasatiempo (future)		5.00	
Pasatiempo Open Space Park (future)		2.00	
Princess Del Cerro	4.40		
Rancho Mission Canyon	9.42		
San Carlos Pocket Park	0.30		
Tuxedo	5.62		
Total Neighborhood Parks:	25.32	9.50	34.82
Park Equivalencies:			
Bench/Weinb Elementary (future)		3.40	
Dailard Elementary	2.98		
Forward Elementary	4.50		
Foster Elementary (future)		3.00	
Gage Elementary (future)		4.70	
Grantville Elementary (future)		2.20	
Green Elementary (future)		3.20	
Hearst Elementary	4.18		
Lewis Middle School	9.58		
Marvin Elementary (future)		3.40	
Pershing Middle School	5.00	5.00	
Navajo Canyon Open Space Trail (11,500 LIN. FT. X 24' WIDE = 6.33 ACRES EXISTING) (3,200 LIN. FT X 24' WIDE = 1.76 ACRES FUTURE)	6.33	1.76	
Rancho Mission Open Space Trail (21,900 LIN. FT. X 24' WIDE = 12.00 ACRES EXISTING)	12.00		
Deerfield Bike Skills area at Mission Trails Regional Park (Future)		12.00	

Existing and Future Population-based Parks	Existing Useable Acres	Future Useable Acres	Total Acres
Deerfield Canyon Nature Park at Mission Trails Regional Park (Future)		2.00	
San Diego River Trail at Mission Trails (10,032 LIN. FT. X 24' WIDE = 5.56 ACRES EXISTING) (12,672 LIN. FT X 24' WIDE = 7.00 ACRES FUTURE)	5.56	7.00	
Shawnee Neighborhood Park		5.30	
Total Park Equivalencies:	50.13	52.96	107.90
Total Existing and Future Useable	139.80	72.46	212.26
Recreation Centers:			
Allied Gardens	9,186 SF	7,814 SF	17,000 SF
San Carlos	11,880 SF	5,120 SF	17,000 SF
Qualcomm Major Park (future)		5,000 SF	5,000 SF
Total Existing and Future SF:	21,066 SF	17,934 SF	39,000 SF
Aquatic Complexes:			
Allied Gardens	1 COMPLEX	0.5	1.5 COMPLEX
Total Existing and Future:			1.5 COMPLEX

The population-based park and recreation facilities requirements for the community are calculated based on the community plan's full community development. For the Navajo community, full community development is projected to be 73,038 residents and will require 204.5 acres of population-based parks. Currently, there are 139.80 acres of existing population-based parks and 72.46 acres of future population-based parks identified, totaling 212.26 acres. This results in a 7.76 acre surplus of population-based parks

TABLE 7: SUMMARY OF POPULATION-BASED PARKS, RECREATION FACILITIES AND PARK EQUIVALENCIES FOR FULL COMMUNITY DEVELOPMENT

Existing and Future Population-based Parks and Park Equivalencies	Full Community Development	Useable Acreage Deficit/Surplus
212.26 acres	204.50 acres	7.76 acres Surplus
Existing and Future Recreation Centers SF		
39,000 SF	49,666 SF	-10,666 SF deficit
Existing and Future Aquatic Complex		
1.5 complex	1.46 complex	0.04 Surplus

PARKS AND RECREATION FACILITIES

OBJECTIVES

- Provide a sustainable park and recreation system that meets the needs of Navajo residents and visitors which serves a variety of users, including children, seniors, persons with disabilities, and the underserved teenage population.
- Provide parks and recreation facilities that keep pace with the Navajo Community population growth through timely acquisitions of available land and development of new facilities.
- Protect and enhance the integrity and quality of existing parks, open space and recreational programs in the Navajo Community.
- Provide a comprehensive pedestrian and bikeway connections between parks and open space lands within the Navajo Community, as well as to surrounding communities.

PROPOSALS

Parks, Recreation Centers and Aquatic Complexes

- Expand the hours of use of the fields at San Carlos Community Park by providing sports field lighting. Expand the existing Recreation Center from 11,880 square feet to 17,000 square feet building to meet General Plan Park standards.
- Demolish the existing Allied Gardens Recreation Center and construct a new 17,000 square foot building to meet the General Plan Park standards. Expand the Allied Gardens Aquatic Complex to provide new amenities such as; therapeutic pool, children's pool, additional locker rooms, indoor showers, changing areas and equipment. In addition, upgrades to the existing children's play areas to meet accessibility standards should be provided.
- Within the Lake Murray Community Park provide additional parking and roadway to serve the multi-purpose fields, expand the children's play area with additional play equipment, site furnishings, picnic shelters, and a comfort station. Complete the implementation of the Lake Murray Community Park General Development Plan by providing parking and a ball field at Cowles Point. Expand the hours of use of some of the existing fields by providing synthetic turf and sports field lighting.
- Provide a Major Park and Recreation Center at the city-owned site within Qualcomm Stadium. Site amenities could include active and passive recreation. The Recreation Center would be shared between the Navajo and Mission Valley community and would be 25,000 square feet. Typical amenities could include gymnasiums, multi-purpose courts, multi-purpose rooms, kitchen and other community-serving facilities.
- Develop the city-owned Pasatiempo Neighborhood Park site with amenities that may include passive lawn areas, walkways, picnic areas, multi-purpose courts, and children's play area. Provide protection and interpretation of vernal pools with fencing and interpretive signs.

- Develop the city-owned Bedlow Neighborhood Park site with park amenities that could include passive recreation such as walkways, fitness courts, picnic areas, small multi-purpose courts.
- Develop the city-owned Pasatiempo Open Space Park with park amenities that could include walkways, native landscaping, fitness course, interpretive signs, seating areas, and picnic areas to take advantage of the panoramic views.
- Develop linear and pocket parks within the Grantville area along Alvarado Creek and the San Diego River. Park amenities could include typical neighborhood park amenities, including passive lawn areas, walkways, picnic areas, small multi-purpose courts, and children's play areas.

Park Equivalencies

- The City should, in cooperation with the School District, provide joint use facilities at selected Elementary Schools, such as Benchley/Weinberger, Foster, Gage, Grantville, Green, and Marvin.
- Construct Phase II of the Pershing Middle School to provide the remaining 5 acres of synthetic turf, comfort station, two shade structures, park sign and sports field lighting to expand the hours of field use.
- Develop 2.4 miles of the San Diego River trail in Mission Trails Regional Park (the entire trail is 4.3 miles, with 1.9 miles existing) and provide amenities such as native landscaping, information kiosks, interpretive signs, identification/directional signs and benches/picnic tables where appropriate. All improvements to be consistent with the Mission Trails Regional Park Master Plan.
- Develop a 12 acre site within Mission Trails Regional Park as a Bike Skills Area by providing amenities such as Bike Skills trails, viewing areas, picnic areas, walkways, parking, seating and native landscaping. All improvements to be consistent with the Mission Trails Regional Park Master Plan.
- Develop a 2 acre mini-park, the Deerfield Canyon Nature Park, in Mission Trails Regional Park with passive recreation including walkways/trails, picnic areas, fitness course and children's play area of natural looking play structures, parking and native landscaping. All improvements to be consistent with the Mission Trails Regional Park Master Plan.

RESOURCE-BASED PARKS AND OPEN SPACE LANDS

Resource-based parks are defined in the General Plan as serving regional residents and/or visitor populations. These parks are located at sites of distinctive scenic, natural, historical or cultural features. Developed amenities should not impair the distinctive features or resources within these parks. These parks typically provide habitat and resource protection. Open Space Lands are defined as city owned land, canyons, mesas and other natural landforms, exclusive of shorelines. These areas provide habitat protection and typical components include trails, staging areas, outlooks, viewpoints, and picnic areas. The current status of Resource-based Parks and Open Space Lands are described below.

Mission Trails Regional Park

The Mission Trails Regional Park is approximately 8,000 acres and is located in the Navajo, Tierrasanta and East Elliot community plan areas. The majority of this park is contained in the Navajo Community and provides hiking, biking, and equestrian trails. A Visitor and Interpretive Center is located off of Father Junipero Serra Trail. The development of this park is guided by the Mission Trails Regional Park Master Plan.

San Diego River (Regional) Park

The San Diego River Park is located along the San Diego River on private and public land. Recommendations within the San Diego River Park Master Plan provide for increasing the health of the river, unifying the natural habitat, creating a sequence of unique places, revealing the river valley history and reorienting development toward the river. The development of this park is guided by the San Diego River Park Master Plan and the San Diego River Park Subdistrict section of the Navajo Community Plan.

Passive and active uses are planned along the river to increase the recreational potential of the Navajo community. Some of the San Diego River Park acreage will be considered as a park equivalency to help address the population-based park deficit of Navajo. Through a Community Plan Amendment process, as part of a development proposal, the amount of acreage and locations will be determined. These areas of the river park will be designed to provide population-based park amenities as defined in the General Plan.

Within the Mission Trails Regional Park, the San Diego River pathway will connect the western boundary of the park, at the Grantville area, to the eastern boundary of the park. The pathway from Grantville to the Visitor's Center will need to be designed and constructed as a new pathway/trail. From the Visitor's Center the San Diego River Pathway will be located on the existing Father Junipero Serra trail. At the Grasslands Crossing within the Mission Gorge area the San Diego River pathway and then connect to the East Fortuna Staging area. This section of the pathway will need to be enhanced with interpretive signs and amenities.

Adobe Falls Open Space

Adobe Falls Open Space, approximately 4 acres, located at the foot of Adobe Falls Road between Waring Road and College Avenue. This site is adjacent to the San Diego State University land, which together with the City-owned parcel makes up Historical Site No. 80-Adobe Falls.

Navajo Canyon Open Space

Navajo Canyon Open Space, approximately 153 acres, is located in the southwest area of the Navajo community and accessed from Waring Road and Lyden Way. This site contains several trail heads, trail kiosks and trails through natural habitat, see Exhibit A.

Rancho Mission Canyon Open Space

Rancho Mission Canyon Open Space, approximately 237 acres, is located centrally in the Navajo community, adjacent to Rancho Mission Canyon Park and is accessed from Margerum Avenue. This site contains several trail heads, trail kiosk and trails through natural habitat, see Exhibit B. All of the existing trails connect to the Ranch Mission Canyon Neighborhood Park. Approximately 5,300 lineal feet of existing trails are to be closed for habitat protection.

RESOURCE-BASED PARKS AND OPEN SPACE LANDS

OBJECTIVES

- Develop Mission Trails Regional Park in accordance with the Mission Trails Regional Park Master Plan. The portions of the Master Plan applicable to the Navajo Community Plan cover the following three major geographical areas: Lake Murray, Cowles Mountain and Mission Gorge.
- Develop the San Diego River Park in accordance with the San Diego River Park Subdistrict of this plan and the San Diego River Park Master Plan.
- Protect and enhance the natural resources of Open Space lands by locating new trails in the least sensitive areas, re-vegetate with native plants and provide protection of sensitive habitats.

PROPOSALS

Mission Trails Regional Park

- Strengthen the role of Lake Murray and its shoreline as an active, water-oriented recreational complex. This entails: (1) expanding the scope and quality of water-related facilities; (2) protecting the lake environment; and (3) transforming the surrounding area into naturally defined spaces for picnicking, playing and other day uses.
- Retain the Navajo Golf Course in perpetuity for recreational use by the public.
- Due to the importance of Cowles Mountain as an open space backdrop for urban San Diego, limit uses to low-intensity activities. Examples include hiking, bicycling and horseback riding, picnicking, photography and nature study.
- Restore the environmental quality of Cowles Mountain by re-vegetation with native plant species and protection from erosion.
- Any new communication facility on Cowles Mountain should blend with the surrounding area and not be located at the top.
- Protect views of and from Cowles Mountain by implementing development controls on urban development in its vicinity in accordance with the Mission Trails District Design Manual.

The Design District provides that no structure shall exceed four stories and in no case shall a structure exceed fifty (50) feet in height.

- Limit uses in the remainder of Mission Gorge include low-intensity activities such as hiking, biking, rock climbing and nature study.

San Diego River (Regional) Park

- Coordinate with the Mission Trails Regional Park to establish a continuous San Diego River Pathway through the park.
- Provide a kiosk at the west and east entrances to Mission Trails Regional Park along the San Diego River Pathway and provide park amenities along the trail.

Adobe Falls Open Space

- Provide a feasibility study for future uses that could include a trail heads with kiosks, interpretive signs on the significant history of the area, and public access trails to connect to the San Diego State University land.

Navajo Canyon Open Space

- Enhance the existing trail system by providing; trail heads with kiosk, trail markers, interpretive signs, overlooks, native landscaping, benches and picnic areas, etc. where appropriate for the trail type as determined by the City and provide sufficient budget for staffing and ongoing maintenance. Provide 3,200 lineal feet, approximate, of new trails and close 1,900 lineal feet, approximate, of existing trails for habitat protection and pursue an easement over private property to connect the northern trail to the southern trail.

Rancho Mission Canyon Open Space

- Enhance the existing trail system by providing; trail heads with kiosk, trail markers, interpretive signs, overlooks, native landscaping, benches and picnic areas, etc. where appropriate for the trail type as determined by the City and provide sufficient budget for staffing and ongoing maintenance. Approximately 5,300 lineal feet of existing trails are to be closed for habitat protection.




FIGURE 21: NAVAJO CANYON OPEN SPACE




FIGURE 22: RANCHO MISSION CANYON OPEN SPACE

PUBLIC SCHOOLS

EXISTING CONDITIONS

The first school opened in Navajo in 1890, at Yard and Mission Valley roads in the subdivision known as Grantville. It contained only one room for all eight grades and was built at a cost of \$1,488. The first year's enrollment was 29, but by the second year, the number of students had dropped to six, which turned out to be only a temporary setback. In 1916, the earlier one-room school was replaced by a modern two-room structure. By 1940, enrollment reached 77 students with two teachers. In 1949, the school was annexed to the San Diego City Schools System, and in 1954 the present Grantville educational facility was built.

At the present time, public educational facilities from kindergarten through the university level are located in or immediately adjacent to the Navajo area. These facilities include one senior high school, two junior high schools, ten elementary schools, the university, and a community college in El Cajon. In addition, there are three private schools. The Catholic Diocese of San Diego operates St. Therese Academy, an elementary school for grades one through six. This school was built in 1960 for an enrollment of 500 and at present time plans to continue operation. Kinder-Care Learning Center has classes and facilities for children from six months through grade three. The existing facilities, which were built in 1970, can accommodate 220 students. The majority of students attending the learning center are from the Navajo area.

Tifereth Israel Synagogue offers classes for children from kindergarten through grade seven. The existing facilities, which were built in 1979, can accommodate 225 students. In addition to the regular instruction classes, the synagogue offers a preschool program for ages 18 months to five years. The San Carlos United Methodist Church and the Del Cerro Baptist Church also provide preschool and child development programs for the community.

Grossmont Community College, located adjacent to the easterly boundary of the Navajo community, is operated by the Grossmont Community College District. Navajo is in the San Diego Community College District; however, students from Navajo may attend Grossmont Community College by agreement between the two districts.

San Diego State University, located south of the community on College Avenue, has a current total enrollment of 33,330 students. The University has been at this location since early 1931, at which time the enrollment was about 1,500 students. The name at that time was the State Teachers College.

All school structures in the community were built after the 1933 enactment of the Field Act, which provided minimum standards for structural resistance to horizontal forces, especially earthquakes and winds.

Single-family residences, which predominate in the area, originally attracted young families with many school age or younger children. In 1960, the average family size was 3.8. As these children matured, the average family size decreased to 2.8 in 1980.

Enrollment declines experienced in some schools, coupled with current and projected revenue deficiencies, may make it necessary to discontinue the use of some of these schools. In that event, the following alternative land uses are proposed:

- Other educational programs or institutions, such as special or adult education, university or community colleges, and private or parochial school purposes.
- Use by other governmental agencies.
- The community and/or the City should be given the opportunity to acquire the land for community-oriented purposes before the property is marketed and leased or sold for private development.
- In the event that the property is to be used for private development, the use should be restricted to a residential land use consistent with the density of the surrounding area.

Table 4 shows the optimum school enrollment and usable site area standards as used by the San Diego Unified School District. The three secondary schools (Henry, Lewis and Pershing) and four elementary schools (Forward, Foster, Gage and Dailard) meet the site size standards. Four elementary schools (Hearst, Green, Weinberger and Marvin) are slightly below standard size but are considered adequate for their enrollments. One elementary site (Grantville) is substantially below standard size. Present policy calls for providing permanent buildings sufficient to house the estimated long-term stable enrollment with allowance for increasing the enrollment capacity of a permanent school by 20 percent with the use of portable classrooms. The portable classrooms give the School District flexibility in meeting the fluctuating enrollments at the schools.

TABLE 8: OPTIMUM SCHOOL ENROLLMENT AND USABLE SITE AREA STANDARDS (SAN DIEGO UNIFIED SCHOOL DISTRICT)

School	Enrollment	Usable Site Area
Elementary	750-1,000	10+ acres
Junior High*	1,500-2,100	15-35 acres
Senior High*	1,800-3,000	15-60 acres
Community College	5,000-7,000	in excess of 123 acres

Exception is made for existing school sites.

* Junior and Senior High School site planning based on Planning Guide Standards of 15 usable acres plus one acre per additional 100 students of predicted ultimate enrollment.

Grantville, Foster, Marvin, Hearst, Gage, Green and Weinberger elementary sites are located on major streets or have their districts bisected by major streets which creates problems in determining safe routes for children to follow to get to school. Some of these major streets do not meet the requirements for marked school crosswalks or for school safety patrol. Walking distance exceeds one-half mile in the Marvin, Hearst, Dailard and Green elementary school districts. Many parents drive their children to these schools where the distance is excessive or where the safety of the child is endangered. Many parents have formed carpools to transport their children to school at personal expense. Students also attend elementary and secondary schools in the area through integration programs offered by the school district. Transportation for the majority of these students is provided by the school district.

All secondary schools and the community college are located on or near major streets. Henry High School and Lewis Junior High School are easily accessible to public transportation. Henry can be reached via bus route 115 and Lewis via bus route 13. Pershing is within walking distance of route 115. However, because of the inadequacy of service, most students use other transportation for school trips.

TABLE 9: EXISTING EDUCATIONAL FACILITIES

School	Location	Acres	Net Usable Facilities	
			Class Rooms*	Year Built**
PUBLIC				
Elementary and Primary				
Dailard	6425 Cibola Road	10.00	24	1977
Forward	6460 Boulder Lake	11.92	14	1961
Foster	6550 51st Street	11.11	19	1956
Gage	6811 Bisby Lake	11.68	23	1963
Grantville	6145 Decena Drive	6.04	13	1954
Green	6665 Belle Glade Ave.	8.84	24	1968
Hearst	6230 Del Cerro Blvd.	9.18	14	1959
Marvin	5720 Brunswick Ave.	8.86	19	1958
Weinberger Junior High	6269 Twin Lake Dr.	9.64	14	1963
Junior High				
Lewis	5170 Greenbrier	21.42	30	1959
Pershing	8204 San Carlos	25.89	33	1964
Senior High				
Patrick Henry	6702 Wandermere	39.72	72	1969
Community College				
Grossmont	8880 Grossmont College Dr.	134.00	--	1961
PRIVATE				
Elementary and Primary				
St. Therese	5835 Navajo Rd.	3.00	--	1960
Kinder-Care	7007 Golfcrest Dr.	1.00	--	1970
Tifereth Israel	6660 Cowles Mountain Blvd.	4.00	--	1979

- * The student enrollment capacity of all permanent public schools may be increased by moving portable classrooms onto the school site.
- ** These are the dates of completion of the oldest building on the site.

OBJECTIVES

The principal or overriding educational objective that would guide the long-range development of Navajo is to: **ASSURE THAT EDUCATIONAL FACILITIES ARE CONSTRUCTED AND MAINTAINED TO SERVE THE POPULATION OF THE COMMUNITY AND THAT THEY CONFORM TO CURRENT BOARD OF EDUCATION POLICIES.**

In addition to the principal objective, the following objectives were also adopted.



- Encourage use of school facilities for recreation, cultural and other activities.
- Assure all students direct, safe access to their school.
- Encourage community participation in identification, implementation and evaluation of the educational needs of the community.




FIGURE 23: SCHOOLS

CITY OF SAN DIEGO • PLANNING DEPARTMENT

PROPOSALS

- When a sustained need exists, schools should be constructed on available sites in order to reduce the excessive crowding at some existing facilities and provide elementary schools within a one-half mile radius of 90 percent of all dwelling units.
- All schools in the area should be built and maintained in accordance with the current board of education policy and the highest possible standards.
- Elementary school attendance boundaries should generally remain stable. However, changes should be considered when necessary to ensure safer access and balance school enrollments.
- Bus service to junior and senior high schools should be expanded to meet student needs.
- If the board of education declares any of the existing school sites surplus property, it is recommended that the community and/or the City be given the opportunity to acquire the land for community-oriented purposes before the property is put on the market and leased or sold for private development. It is further recommended that if such private development should occur, it should be restricted to a residential land use consistent with the density of the surrounding area.



OTHER COMMUNITY FACILITIES

EXISTING CONDITIONS

In addition to schools and parks, other community facilities are necessary to provide Navajo with essential services. These facilities include libraries; police and fire protection; sewer, water and drainage; and hospitals. Existing facilities do not meet the standards as outlined in the Progress Guide and General Plan. These inadequacies are the result of the public sector being unable to keep up with the rapid pace of private development.

Library Services/Facilities:

The City Library Department currently maintains two branch libraries in the Navajo community. The Edwin A. Benjamin Memorial Branch is located at 5188 Zion Street in Allied Gardens. Opened in 1964, this branch is 3,875 square feet in size and circulated 143,592 books in the fiscal year 1979-80. Although the original building was planned for a capacity of 20,000 volumes, the current collection contains over 26,000 volumes.



The San Carlos Library is located at 7265 Jackson Drive, just northwest of Golfcrest. Serving the San Carlos and Del Cerro areas, this library was opened in 1974. The building contains over 8,000 square feet and a collection of 25,000 books, with a circulation of 212,368 books during the 1970-80 fiscal years. While the opening of the San Carlos branch gave a much better circulation of books and services to the Navajo community, it did not relieve the overcrowding of the Benjamin branch. If additional facilities are required, alternative solutions to be considered include the possible expansion of the Benjamin branch as well as a third branch library in the community.

POLICE SERVICE/FACILITIES

The San Diego Police Department serves the Navajo community from the Eastern Substation in the Serra Mesa community. In addition to the Navajo community, the substation will be able to provide complete and immediate service to the community areas of Serra Mesa, Tierrasanta, State University and that portion of Mid-City lying north of University Avenue.

Patrol units are assigned and continuously operate in the community, in addition to traffic units that also operate there. The police department considers the community to be a high priority area for additional police coverage in the future.

The two major trunk sewers are capable of serving a combined population of 300,000 people and related services. The proposed Navajo community population of 65,000 to 70,000 should not adversely affect these facilities. The undeveloped property within the community will require additional collector mains and trunk sewers as a normal subdivision requirement.

Gas and Electric

There are two electric transmission lines and one gas transmission line within the limits of the Navajo study area. At present, no additional electric transmission lines or electric substations are planned for the area. It appears that the existing transmission lines will be adequate for some time to come, however, if additional transmission capacity is required, the existing lines should be reconducted within the existing easements. Additional electric distribution facilities should be added to serve additional load in the area as the need occurs.

Floodplains and Flood Control

The Navajo community includes portions of the San Diego River and Alvarado Creek floodplains and a number of unnamed canyons. The San Diego River enters the community through Mission Gorge at Padre Dam in the northwesterly section of the community, parallels Father Junipero Serra Road and Mission Gorge Road, traverses the Navy golf course, and leaves the community near the Mission de Alcala west of Grantville.

A large portion of the business community in Grantville is subject to inundation from floodwaters of the San Diego River. A flood control project for the San Diego River (The Mission Valley Project) was authorized by Congress as a result of a U.S. Army Corps of Engineers report dated January 10, 1964. This project, which had at its eastern boundary the Friars Road Bridge just downstream of the Navy golf course, provided for 5.2 miles of concrete lined channel centrally located in the existing river bed. However, as a result of public opposition to a concrete lined channel, the Corps reevaluated the project and concluded that the concrete channel was no longer justified. The project was reclassified to an inactive category in January 1978.

Alvarado Canyon, within the study area, extends from College Avenue westerly to its confluence with the San Diego River immediately to the west of Fairmount Avenue. The Mission Valley Project included plans to construct a concrete lined channel along the westerly portion of Alvarado Creek; however, there are currently no plans for construction of a concrete channel.

Stormwater

The Municipal Storm Water Permit (MS4), issued by the San Diego Regional Water Quality Control Board (SDRWQCB), requires all development and redevelopment projects to implement storm water source control and site design practices to minimize the generation of pollutants. Additionally, the Permit requires new development and significant redevelopment projects that exceed certain size threshold to implement Structural Storm Water Best Management Practices (Structural BMPs) to reduce pollutant in storm water runoff and control runoff volume.

The MS4 Permit is re-issued every five years, typically imposing more stringent requirements on a wider range of development. These requirements are adopted in the City's Land Development

Manual; Storm Water Standards Manual and apply to both private development and public improvements.

There is an increased reliance on Low Impact Development (LID) strategies to meet the MS4 Permit requirements and TMDL as well. Examples of LID techniques are bioretention cells, green streets, green roofs, porous pavement, infiltration basins and biofiltration planters. To enhance stormwater, the following strategies are encouraged.

- Encourage the use of green streets in the right-of-way to reduce pollutant runoff into San Diego River.
- Encourage building roof downspouts to drain to pervious areas such as planter boxes or adjacent landscaping.
- Encourage the use of permeable pavement surface designs in low traffic roads and parking lots where feasible.
- Design parking lots to drain to landscaped areas to provide treatment, retention, or infiltration, where feasible.

Emergency Medical Service/Facilities

Emergency medical service is provided by three hospitals located in or near to the Navajo community. These are Grossmont Hospital in the city of La Mesa, the Alvarado Hospital on Alvarado Road south of I-8, and a 200-bed Kaiser Hospital near Zion Avenue and Mission Gorge Road, both in the City of San Diego. A portion of the Navajo community (San Carlos, Del Cerro) is included in the Grossmont Hospital District.

OBJECTIVE


THE COMMUNITY'S OBJECTIVE IS TO ASSURE THAT A HIGH LEVEL OF ALL PUBLIC SERVICES IS REACHED AND MAINTAINED BY ADHERING TO STANDARDS SET FORTH IN THE PROGRESS GUIDE AND GENERAL PLAN AS A MINIMUM.

PROPOSALS

- Continue evaluation of police and fire services to obtain and ensure adequate coverage in Navajo.
- Conduct periodic studies to obtain and ensure adequate sewer, water and drainage facilities.
- Design and implement flood control facilities to ensure adequate protection for the community, while preserving the natural topography and minimizing the adverse environmental effects on the community. If channelization is necessary, the channels should be soft-bottomed and soft-sided, and should be designed of sufficient width to support riparian vegetation across the width of the channel.
- Restrict development and encroachment in the floodplain, except as provided for in the Floodplain Fringe and Floodway zones.

- Proposals relating to flood control and floodplain boundaries should be restudied periodically and updated to reflect areas subject to inundation and current planning efforts.

The Floodplain Fringe (FPF) and Floodway (FV) zones should be applied to the entire San Diego River and Alvarado Creek basins within the planning area in order to control land use and regulate future development to avoid or reduce flood damage. These zones provide controls for development in the floodplain, and will encourage the preservation of the natural waterways associated with these two floodplains. Where possible, runoff through the lesser canyons should also be carried by the natural drainage course and these drainage courses should be maintained as open space.



CITY OF SAN DIEGO • PLANNING DEPARTMENT

FIGURE 24: OTHER COMMUNITY FACILITIES

CIRCULATION

INTRODUCTION

Traffic circulation is an important concern inasmuch as the movement of people and goods within the Navajo community is directly related to its future economic, physical and social well-being. An adequate circulation system is essential to provide necessary services to households and businesses in the community.

Because the Navajo area has a greatly varying terrain, and because it is adjacent to the cities of Santee, La Mesa and El Cajon, some of the transportation problems encountered here are unique. Through the application of sound planning and engineering principles, it is possible to develop a balanced transportation system that will serve the community's internal travel needs and provide access to other communities outside the immediately surrounding area.

It is beginning to be realized that, "the effects from pollution, increasing dependency upon a single mode of transportation (motor driven vehicle) for all uses, and immobility among the poor, the aging, the young and the handicapped have caused doubt everywhere about the ultimate wisdom of our expanding roadway systems" (Report on Interim Hearings to the State Senate by the Senate Select Committee on Rapid Transit, 1971.) It is therefore necessary to make strenuous efforts to reduce our almost complete dependence on the automobile by providing efficient alternative methods for moving people. Buses and Light Rail Transit (LRT) service provide two of the most efficient, alternative and growing modes of transportation in San Diego. San Diego's Metropolitan Transit System has an integrated bus/rail system. Currently, a network of bus routes serves the Navajo area. In October 1997, the MTD Board approved the extension of LRT through the Navajo community, continuing to San Diego State University and La Mesa. The extension includes a station in Grantville. The LRT project included the extension of Alvarado Canyon Road over Waring Road to Adobe Falls Road, which provides a direct connection between the Navajo Community and the LRT station. Another recent development to reduce dependence on the automobile is the Employer Transit Assistance Program (ETAP) in which employers subsidize monthly transit passes for employees to encourage transit use. The program is administered through MTDB and Ridelink.

Future transportation requirements in the Navajo area are based upon anticipated future traffic volumes or "travel forecasts". Travel forecasts depend upon many factors, one of the most important of which is the future land use proposed for a particular area. Any substantial changes in proposed land uses and/or traffic forecasts in the Navajo area, therefore, may require a modification of the proposed transportation system, as would any change in present dependencies on the automobile for transportation. In addition to the local land use projections for Navajo, future travel demands for the entire region done by the San Diego Association of Governments (SANDAG) were used in evaluating the year 2000 transportation needs. Based on review of existing and currently anticipated future transportation needs of the Navajo area, it is proposed that the road and bikeway systems as indicated be adopted as a guideline for future street and bikeway development in the area. Additionally, it is strongly recommended that there be accelerated expansion of public transportation for the area.

OBJECTIVES

The basic objective of the circulation system is to provide each member of the community with safe, ready access around, as well as in and out of the community, by a mode of transportation of individual choice with minimal environmental damage.

To achieve this purpose will require that a fully integrated system of pedestrian, bicycle, public transit and automobile facilities be developed. The system should link all sections of the community--residential, commercial, employment, educational, recreational and cultural--by a safe mode best suited to the trip being made. With a well-balanced transportation system available, the necessity for a third or even a second car per household will be greatly reduced, thus decreasing air pollution and congested streets.


The following additional objectives concerning the circulation element are established for the Navajo community:

- Develop a balanced transportation system that adequately links the Navajo area to nearby communities as well as regional facilities.
- Encourage use of the integrated bus/LRT system to maximize the benefits of the transportation system and its ability to efficiently move people and goods.
- Develop a balanced transportation system that adequately accommodates the community's internal needs.
- Strive to separate automobile, pedestrian and bicycle conflicts and, where safe and practical, provide specially designated bikeways to accommodate the increased demand for this mode of travel.
- Encourage hillside view preservation in the design of new streets. Fit streets carefully into the topography to minimize grading to ensure that the street is compatible with the total landscape. The geology of an area may preclude or minimize grading in some specific cases.
- Create the San Diego River Pathway for bicycle and pedestrian users all along the south side of the San Diego river with connections to Mission Valley and Tierrasanta communities and Mission Trails Regional Park.

PUBLIC TRANSPORTATION

INTRODUCTION

The future improvements in public transportation should be viewed objectively with regard to requirements to meet Navajo's future transportation needs. A SANDAG report titled "Transit Development, Plan and Program," completed in June 1970, discussed future transit improvements for the entire region. Mentioned as possible problems in expanding service to areas such as Navajo is the low-density development, the varying terrain of the area, and the lack of a grid street pattern. Mentioned as positive factors for an increase in public transportation are the future anticipated increases in automobile congestion, concern over air pollution caused by automobiles, the increase in costs of parking for those who work downtown, and the progressive attitude of the San Diego Transit Corporation and other governmental agencies. With increased transit service, many residents will be given alternatives to multi-car ownership.




EXISTING CONDITIONS

Currently, there are five bus routes that operate in the Navajo community areas. Bus Route 13 provides cross-town service on College Avenue, Waring Road, Zion Avenue, and Mission Gorge Road. Its southerly terminus is the LRT station at Euclid Avenue and Market Street in Southeastern San Diego. At present, this route provides modified service on weekends and holidays.

Bus Route 115 operates from Fletcher Hills to downtown San Diego with service in the community along Lake Murray Boulevard, Jackson Drive, Navajo Road, and College Avenue.

Bus Route 115 offers modified service on weekends and holidays. Route 854, County Transit System, provides limited service to the Navajo community. This route operates between Grossmont College in El Cajon and Grossmont Shopping Center in La Mesa, via Navajo Road and Lake Murray Boulevard in the City of San Diego. Bus Route 40 provides service five days/week during AM/PM peak hours only from Fletcher Hills to downtown San Diego with service in the community along Navajo Road and Waring Road. A fifth bus route, Bus Route 81, serves the southeast portion of the Navajo community via Baltimore Drive and Lake Murray Boulevard.



A study of Fiscal Year 1997 operating characteristics of the various buses serving Navajo showed that Route 115 is the most heavily used, carrying over 1,000,000 passengers annually with ten percent of its daily trips incurring standing loads. Of the five bus routes serving the Navajo community, Bus Route 40 carries the lowest number of passengers with annual boardings totaling 41,000.

A survey of transit passengers in San Diego conducted in 1995 by SANDAG, showed that many people who use routes servicing the Navajo community are transit-dependent. While passengers on Bus Routes 13, 40 and 81 used the bus for transportation to work (35-87 percent), most passengers on Bus Routes 115 and 854 used the bus for transportation to school (36-54 percent). Because of the community's proximity to San Diego State University and Grossmont College the percentage of riders using public transit for the home to school trips exceeds the citywide average.


PROPOSALS

Implied in the transportation recommendations is the realization that circulation systems for personal vehicles can be designed only to accommodate a desired optimum traffic volume. Before traffic reaches this point, other modes of transportation must be programmed. In the past the alternative has been to continually increase rights-of-way or acquire new alignments to accommodate heavier traffic volumes. This alternative can no longer be considered the only solution.

The Metropolitan Transit Development Board has embarked on a program to improve bus service for San Diego. Planned transit improvements and others under consideration include:

- Evaluation of rerouting Bus Route 13 to serve the future Grantville LRT station.
- Increase service on Bus Route 40 to operate all day, routing midday and selected peak period trips to the Grantville station. Evaluate effect of marketing efforts, need and possible service reductions in this route.
- Possible elimination of Bus Route 81 to coincide with the opening of the Mission Valley East Light Rail Extension.
- Work with the city of La Mesa to possibly implement Westside Shuttle route operation to serve the future 70th Street trolley station.
- Extend bus route 13 further north on Mission Gorge Road to service proposed developments north of Old Cliffs Road up to Princess View Drive and link to the LRT station.

For longer term improvements (up to the year 2000) there should be additional local and express service similar to that described above, with emphasis on minimizing travel time and wait time, extending service to provide a greater number of destinations and making transit travel more pleasing (e.g., modern vehicles and terminals).



TRANSIT NETWORK

- EXISTING SERVICE
- MAJOR STREETS
- ★ TRANSFER POINT
- 13 BUS ROUTE NUMBER
- PROPOSED LRT STATION
- EXISTING LRT STATION
- EXISTING LRT ROUTE
- ++++ PROPOSED LRT ROUTE




FIGURE 25: TRANSIT NETWORK

CITY OF SAN DIEGO • PLANNING DEPARTMENT

BICYCLES

INTRODUCTION

Today across the United States the bicycle boom continues. People of all ages are riding bicycles as never before. People have turned to bicycles for exercise, recreation and transportation. Schools within a community often generate a high demand for bicycle facilities. Bikes do not pollute, are energy efficient, and they offer an opportunity to bypass congested streets.

The City has design standards for the construction of bikeways and an ongoing program of providing a comprehensive bikeway system for City residents that will connect to a regional bikeway network. Bikeways fall into three categories based on the degree or extent of their improvements: bicycle paths (Class I), lanes (Class II) and routes (Class III). Four such bikeways have been constructed in Navajo, and are noted on the bikeways map. They are described in the following section along with the proposed routes.

PROPOSALS

Regional Bikeway

A regional bike route is proposed from the ocean through Mission Valley to Mission Gorge Road and northeasterly along Mission Gorge Road. This route will also continue east parallel to the north side of I-8 from Mission Gorge Road to the vicinity of College Avenue.

Del Cerro Route

This route would be oriented to the Del Cerro area and would utilize Del Cerro Boulevard from Trinity Way on the west to Linfield Avenue on the east. The intended alignment would provide a scenic overlook of Mission Valley. Length: 2.0 miles.

Allied Gardens Route

This route would be oriented to Allied Gardens and also provide for the extension of bicycling opportunities from that community easterly to the Del Cerro area. This existing route utilizes Barclay Avenue and Brunswick Avenue between Galewood Street and Zion Avenue. Both streets run through attractive residential areas. College Avenue, the link to Del Cerro, would provide scenic overlooks of San Diego. Length: 2.0 miles.

Connector - This route provides a connection between the Allied Gardens route and the proposed San Diego River route in the vicinity of Zion Avenue. The route is aligned along Zion Avenue, Delbarton Street, Crawford Street, and Twain Avenue. Except for Twain Avenue, this route exists. Length: 2.0 miles.

Jackson Drive Extension

An extension of the Jackson Drive route would be a route that lies largely outside the San Diego City limits. This route would run from the City limits to the San Carlos Community Center by way of East Lake Avenue, Lake Ashmere, Lake Arrowhead, San Carlos Drive, Boulder Lake Avenue, and Jackson Drive. The Jackson Drive portion now exists. Length: 3.2 miles.

Lake Murray Boulevard Route

This route would be along Lake Murray Boulevard from Grossmont Community College to a connection with the Del Cerro route extension at Jackson Drive. This route presently utilizes a portion of the Lake Murray Boulevard frontage road from Jackson Drive to the Navajo shopping center. From the shopping center to the college, a portion of Lake Murray Boulevard would be set aside with appropriate striping for use as a bike route. The southerly portion of the route is a tree lined boulevard through an attractive residential area. Length: 1.75 miles.

Jackson Drive Route

This route consists of an existing Class III bikeway from the city of La Mesa to Mission Gorge Road. Total length: 3.0 miles.

Navajo Road Route

This route is along Navajo Road from the intersection of Waring Road and College Avenue, easterly to the City limits at Fanita Drive with the possibility of extensions into El Cajon. This route exists except for the most eastern half-mile. Total length: 3.7 miles.

Golfcrest Drive Route

This route would be along Golfcrest Drive from Navajo Road to Mission Gorge Road and would serve as a connector between the bike routes on those streets. Length: 1.25 miles.

Mission Gorge Road Route

This route would be along Mission Gorge Road from the Santee - San Diego City limits to the western limit of the community. Although the parallel bikeway along the San Diego River will remain as a desirable goal for future implementation, its construction is dependent upon further development along Mission Gorge Road. When private developments along Mission Gorge north of the Archstone property are initiated, street improvements will include widening and the inclusion of a bicycle lane. In the meantime, relatively minimal and inexpensive work on Mission Gorge Road can produce a usable improvement for bicyclists. Total length: 5.2 miles.

Connector - This proposed route provides a connection between the Mission Gorge Road route and the proposed San Diego River route. The route would be aligned along Father Junipero Serra Trail. Length: 1.2 miles.

San Diego River Park Pathway

This San Diego River Pathway would be along the entire length of the San Diego River within the Navajo community on the south side of the river. Bicycle and pedestrian users would be able to connect to other regional bike routes from the San Diego River Park Pathway. The design of the pathway should be in accordance with the San Diego River Park Subdistrict of this plan and consistent with the San Diego River Park Master Plan. Through the development along the river the San Diego River Pathway location will be determined and an easement to allow for public access will be required on private land.

The routes shown and described above are bikeway corridors, and not exact alignments. When this Plan is implemented, minor deviations may be necessary.

STREETS

INTRODUCTION

The five basic functional categories of streets in San Diego are present in Navajo. They are: freeways, primary arterials, major streets, collector streets, and local streets.

Street and Highway Standards adopted for the City of San Diego in 1964 and revised in 1980, are shown in the Standards and Definitions section of this Plan. Although these standards are applicable primarily to streets in new subdivisions, they also indicate desirable features to be obtained whenever improvement of an existing street system is undertaken. Also shown on the table are the maximum Average Daily Volumes (ADT) of traffic desirable for each type of street.

EXISTING CONDITIONS

The Functional Road Network and Traffic Volumes map and the Street Classification map (see pages 114 and 115) show the existing functional classifications for streets in the Navajo community, from the primary arterial to the collector street level. Interstate 8 forms the southern boundary of the area. Friars Road, Mission Gorge Road east of Friars Road, and Navajo Road all function as primary arterials. The other streets shown on the existing road network map function as major or collector streets.

The traffic volumes carried by each street in the Navajo roadway network are also shown on the Functional Road Network and Traffic Volumes map and the Street Classification map (see pages 114 and 115). The volumes listed are in vehicles per average weekday.

Volumes of over 20,000 vehicles per day exist on portions of Mission Gorge Road, Waring Road, College Avenue, Friars Road, Navajo Road, and Lake Murray Boulevard. The highest traffic volume recorded on a surface street is on Mission Gorge Road between Friars Road and Zion Avenue (52,700) where a six-lane facility exists.

There are several streets in the area that are carrying traffic volumes in excess of their design volume. Fairmount Avenue extension between Mission Gorge Road and Twain Avenue is 50 feet wide, yet carries 7,600 vehicles on an average weekday. The maximum desirable ADT for a two-lane collector street is 5,000 vehicles per day. Zion Avenue varies in width from 40 to 50 feet and has a maximum desirable ADT of 5,000 yet is currently carrying over 14,300 vehicles per day. Similarly, College Avenue between I-8 and Del Cerro Boulevard, Twain Avenue between Mission Gorge Road and 50th Street, Mission Gorge Road between Fairmount Avenue and Twain Avenue, and Madra Avenue north of Del Cerro Boulevard all carry volumes that exceed what is desirable for their classifications. (All traffic counts are as of 1987.)

PROPOSALS

Freeways and Expressways

- A recently completed study by SANDAG concluded that the easterly extension of State Route 52 (SR-52) is the most critical improvement needed to relieve traffic congestion on Mission Gorge Road, Friars Road, and I-8. Construction of SR-52 from Santo Road in Tierrasanta to the city of Santee will be scheduled as soon as environmental clearance is obtained.
- An extension of Route 125 north to SR-52 is proposed. When built, this freeway and/or expressway would parallel the eastern edge of the Navajo community.
- Improvement by Caltrans of Interstate 15 (I-15) to 6-8 lanes between I-8 and State Route 163 (SR-163), and eight or more lanes north of SR-163 is being implemented.
- An additional westbound traffic lane on I-8 between College Avenue and I-15 is being proposed by Caltrans. This improvement will relieve traffic congestion on I-8 and Navajo community streets that access I-8 (i.e., College Avenue, Waring Road, and Mission Gorge Road). Caltrans is scheduled to advertise for bids for the widening in 1991.

Streets

- The synchronization of traffic signals along Mission Gorge Road, between I-8 and Rainier Avenue is currently being designed (Fiscal Year 1988). The traffic signals north of Rainier Avenue cannot be synchronized because they are spaced in excess of one-quarter mile apart, the maximum practical distance for synchronization.
- Friars Road, between Riverdale Street and Santo Road, is planned to be widened to six lanes to alleviate congestion at the intersection of Mission Gorge Road and Friars Road that is caused by the three westbound lanes on Friars Road narrowing to two lanes west of Riverdale. This project is included in the Capital Improvements Program for design in Fiscal Year 1989.
- The easterly extension of Alvarado Canyon Road will be constructed as part of the Mission Valley East LRT project as a two-lane collector crossing over Waring Road to Adobe Falls Road. The road will provide improved access to the planned Grantville LRT Station and help to mitigate traffic impacts on Fairmount Avenue, Mission Gorge Road, and the westbound I-8 off ramp.
- A study of the realignment of Alvarado Canyon Road should be completed and the project undertaken as soon as feasible. Subject to environmental review, the intersection of Alvarado Canyon Road with Mission Gorge Road should be moved northward to align with the Mission Gorge Road/Fairmount Avenue intersection. This realignment will help alleviate traffic congestion on the westbound I-8 off ramp/Fairmount Avenue intersection. Consideration should also be given to widening the southbound Fairmount Avenue to westbound I-8 on-ramp in conjunction with this project.

The circulation plan must be oriented to provide a balanced transportation system for the Navajo community. Additional streets and alterations to existing streets should be limited to remedial

and corrective measures. Only as a last resort should the widening or addition of streets, as would be required by the City's street standards, be considered.

Special treatment should be provided as indicated on the Street Classification Map to handle capacity problems. The special treatment required may take the form of parking prohibitions, widening at intersections to obtain additional lanes, adding or changing intersection channelization to facilitate heavy directional moves, and special traffic signal phasing or interconnection.

In the event the above techniques cannot adequately facilitate traffic, the following improvements should be considered:

- Navajo Road should be widened to a six-lane major street east of Lake Murray Boulevard.
- Mission Gorge Road should be widened to a six-lane facility north of Zion Avenue with no left-turn lanes except at signaled intersections. Between Fairmount Avenue extension and I-8 (at its southerly terminus) Mission Gorge Road should also be improved to be a six-lane major street.

In preparing this next recommendation, City and state agencies and community interests were consulted and numerous alternatives were considered and analyzed. The recommendation for the extension of Navajo Road through Navajo Canyon appears to be the best solution at this time, but only under the following conditions:

Since this Plan recommends maintaining Navajo Canyon as open space, the extension of Navajo Road through the canyon should be designed to parkway standards and limited to a two-lane facility with four lanes at the intersections with College Avenue and Waring Road and no intermediate access; sufficient capacity must exist on I-8 to accommodate the Navajo Road traffic; and a reevaluation of the entire recommendation shall be undertaken if at any time before construction, any curb on automobile traffic, such as the use of gasoline rationing, etc., takes place in San Diego.




FIGURE 27: STREET CLASSIFICATION

CITY OF SAN DIEGO • PLANNING DEPARTMENT

Design Principles

One aspect of transportation planning which has been overlooked is that portion of its site planning which involves the art or form of the transportation facility. It is especially important that roadways be regarded as an integral part of the landscape in which they are sited. They must be something more than the standard provision of a surface for moving cars or guiding public transit vehicles. However, the design of the facility must not override, but be considered equally with, the safety and capacity of the facility.

Because of topography, many of the City standards for streets are not suitable for the Navajo community. The following standards are suggested for use in these areas.

Street Widening

Widening and realignment frequently destroys the visual character and identity of streets by the removal of mature trees, other landscaping, and median strips. The approach to street widening and realignment should be more sensitive to the character of the street and the quality of adjacent development. When substantial environmental damage may result to adjoining properties, the traffic carrying capacity of the street might be improved by eliminating on-street parking or using reverse lanes at peak hours rather than physical widening. When a street must be widened and necessarily encroaches on a dwelling's front or side yard, variations should be permitted in the zoning code requirements that would permit high walls to give residents privacy from the sight and noise of traffic.



Street Accessories

- Standards for street paving and lighting are not varied systematically throughout the City. Most of the streets and sidewalks in the City are paved in the same materials, and lighting fixtures often do not reflect the character and scale of the frontage development.
- Placement of telephones, police and fire call boxes, mail deposit boxes, street numbers and newsstands in consistent locations along the street would facilitate their use. These accessories should not be placed in the path of pedestrians or wheelchair users.
- A coordinated system of variation in the use and placement of street trees, lighting, and other details could give streets better visual continuity and provide differentiation between through streets and local streets to aid driver orientation and traffic flow. The variations could include size, spacing and species of street trees and other landscaping, and intensity, spacing, and design of lighting fixtures. For example, major streets might have tall, widely spaced street trees; bright, closely spaced street lights; and large street signs. Local streets might have smaller, dense and more closely spaced trees; compass headings could be indicated by


symbols on light poles or on the pavement. A more logical and systematic method of street naming should be used.

Hillside Streets


- Hillside street standards should be reviewed for compatibility with the terrain. More restrictive grading controls, street landscaping, and limitation of on-street parking to one side of all hillside roads, should all be considered. Even under existing standards however, the use of retaining walls and horizontally or vertically split street alignments would make the road blend into this special topography. These methods were common in earlier hillside street construction.

Pedestrian Walkways (Sidewalks)


- Design walkways and parking facilities to minimize danger to pedestrians. Pedestrian walkways should be sharply separated from traffic areas and set apart where possible to provide a separate circulation system. Where necessary and practical, the separation should include landscaping and other barriers. Walkways should pass through the interiors of blocks. Walkways that cross street corners should have good sight distances for motorists and pedestrians.
- Driveways across sidewalks should be kept to a practical minimum, with control maintained over the number and width of curb cuts. Barriers should be installed along parking lots to avoid encroachments on sidewalks, with adequate sight distances maintained at driveways.
- Commercial and industrial truck loading should occur on private property rather than in roadways or on sidewalks. Residential parking should be as close as possible to the dwellings served, with adequate lighting along the walking route from the parking to the dwellings.



HILL COLLECTOR STREET
STREET DIVIDED TO BETTER FIT THE TOPOGRAPHY AND TO MINIMIZE EARTHWORK. PARKING ONE SIDE OF EACH ROADWAY.








HILL RESIDENTIAL STREET
A SINGLE SIDEWALK IS PROVIDED WHICH COULD BE LOCATED AT A DIFFERENT LEVEL THAN THE MAIN ROADWAY.



HILL RESIDENTIAL STREET
ASSUMED HERE THAT ON-STREET PARKING IS PROHIBITED. EMERGENCY PARKING BAYS PROVIDED AT APPROXIMATELY 500 FOOT INTERVALS. DEVELOPMENT ONLY ON DOWNHILL SIDE.

HILLSIDE STREET TREATMENTS



PEDESTRIAN WALKWAYS

COMMUNITY ENVIRONMENT

INTRODUCTION

The term "environment" in its broadest sense refers to all the external dimensions--social and economic as well as physical--which affect the life of an individual. This element focuses on that dimension of traditional concern to urban planning, and recently of increasing concern to the public--the quality of the physical environment, natural and man-made.



The visual form of a community's physical environment should be comfortable, educational, rich in variety and highly identifiable, expressive of the community's functions and social life, and capable of being shaped by its inhabitants. The primary goal in this area of concern is the improvement, restoration, and protection of the quality of the natural and built environment. All of this is taken into account in identifying the opportunities for improvement of the visual environment.

The environment of any community is more than the sum of the homes, shops factories, schools and parks. The maintenance and improvement of the natural and built environment do much to determine the quality of particular neighborhoods and communities to preserve their distinct identities.

To many individuals, the image of the community they are most familiar with is the motorist's view as he passes through. The lack of landscaping on the perimeter of roadways, the barrenness of residential and commercial subdivisions and the seemingly endless areas of pavement are frequently expressed concerns. Residential development establishes the dominant environmental character of Navajo. Relatively uniform house size and design, parcel area and site layout--a situation typical of many postwar developments--typifies much of the community. New approaches to site and building design, however, have provided some interesting variety--an example being the San Carlos townhouse apartments at Jackson Drive and Golfcrest Avenue.



Visual clutter is a major environmental problem. The numerous signs, billboards, telephone and electrical distribution poles and lines, and television antennas are distracting and unattractive. The problem is most evident upon entering the community on Mission Gorge Road from I-8.

Signs are examples of visual nuisances that create a poor environmental image of a community and its character. Often, these signs are concentrated to appeal to the eye of the motorist.

A clutter of signs proliferates in many of the commercial areas. The signs are unsightly, disorganized, and generally degrading to the entire community. Mission Gorge Road is the most notorious example of an area blighted by excessive signs. The attempt to compete with larger, brighter, and gaudier signs not only detracts from the appearance of the area but diminishes the effectiveness of signs. The problem of sign clutter is also prevalent in the shopping centers.

Other clutter is produced by elements placed in the street areas. The undergrounding of overhead wires should continue at the most rapid pace possible, with the goal of complete elimination of such wires within a foreseeable period of time. Every other element in street areas, including public signs, should be examined with a view toward improvement of design and elimination of unnecessary elements.



Both public and private efforts in the installation and maintenance of landscaping should be increased. In residential areas, side yards and setbacks provide the best opportunities for landscaping visible in public areas. If no such space exists, then trees should be placed in the sidewalk area, preferably in the ground rather than in containers. Care should be taken to select species of trees suitable to each location. The most visible points, such as street intersections, should be given special attention. Other unused opportunities for landscaping

exist on exposed banks, usually along roadways. Where it is feasible, these should be planted and maintained by the owners of the land.

In addition to landscaping, other features along the streets add to the comfort and interest of pedestrians. Sidewalk paving and furnishings, if designed in a unified way, make walking more pleasurable. Gentle changes in level have the same effect. In commercial areas, continuous and well-appointed shop windows and arcades are invitations to movement. Little used alleys and easements can be improved as walkways, and new promenades put through blocks in new developments. Screening of the sand and gravel and industrial areas along Mission Gorge Road through the use of walls, fences and substantial landscaping can greatly enhance the appearance of these areas.

OBJECTIVE

TO PRESERVE AND ENHANCE THE NATURAL BEAUTY AND AMENITIES OF THE NAVAJO COMMUNITY.

PROPOSALS

Programs

- Grading and landscaping standards should be improved. Hillside cuts, in particular, must be better controlled to preserve the natural topography.
- Define acceptable noise rating levels for the use of motorized equipment and aircraft.
- Restrict heavy truck traffic to certain areas.
- Develop new programs and practices for the reclamation of waste water for secondary uses.
- Develop new programs and practices for the disposal or recycling of garbage, refuse and other solid wastes.
- Establish restrictions on odor-producing activities based on wind direction, atmospheric temperature, topography and proximity to built up areas.

Buildings - Structures

- Create, through design, harmony between natural features and urbanized areas and activities.
- Encourage an orderly transition of height, density, scale and arrangement of buildings to preserve the identity of each element as well as the cohesion of the whole.
- Promote the coordination of building groupings to foster neighborhood and community identity and unity.
- Encourage an overall quality of design by using materials, color and texture to give identity and focus to groups of structures within the urban landscape.
- Cable television should be encouraged throughout the study area to help eliminate the clutter of individual antennas. Future planned residential developments should include no more than one master antenna to serve all units.
- All telephone and electrical distribution lines should be underground where technically and economically feasible, in accordance with systematic long-range program establishing priorities for the Navajo area.
- Develop points of visual relief in the urban landscape through the use of open spaces and landscaping, building setbacks, building materials, location of public facilities, and street and right-of-way design and maintenance.
- Improve the appearance of public and private special use properties such as flood control channels, power line rights-of-way, mineral extraction operations, and water storage areas.

- Improve flood control and storm and sewer installations.
- Protect distinct areas and communities from intrusion and encroachment of incompatible uses.
- Minimize nuisances to adjacent uses through the control of noise, odor, pollution, vibration and glare, and the screening of unaesthetic land uses.
- Implement development controls on urban development in accordance with the Mission Trails District Design Manual, which provides that no structure shall exceed four stories and in no case shall a structure exceed fifty (50) feet in height.

Signs

- The size, placement, design and height of signs should be controlled through reasonable and uniform regulations utilized to prevent encroachment on the visual form of the community's physical environment.
- Signs should not project above the eave of the building to which the signs are attached.
- Signs should not protrude over the sidewalk or street, but be placed against the face of the building. Freestanding signs should be prohibited.
- Signs for the various businesses in any shopping center should be attractively clustered upon a marquee near the entrance to the center.
- Signs with moving parts or flashing lights should not be allowed.
- Signs should be limited in size based upon the linear feet of street frontage.
- Signs on trucks, autos, or other vehicles used to circumvent sign regulations should be restricted.
- Permitted signs should be kept in good appearance and repair. Nonconforming signs should be removed.

Landscaping

- Use trees and shrubbery along heavily traveled streets to help lessen effects of traffic noise.
- Support feasible soundproofing of residential, commercial and industrial structures.
- Mission Gorge Road industrial development should be properly screened with landscaping and other suitable means. The area should be made presentable to the community and motorists on Mission Gorge Road because of its importance as an entry to the community, the Old Mission, and Mission Trails Regional Park.
- Establish financing programs, such as assessment districts, to provide for and maintain landscaping in the public right-of-way for major streets within the community.
- The following streets should receive first priority for such right-of-way improvements: Navajo Road, Mission Gorge Road, College Avenue and Waring Road. These improvements should include the planting of street trees as well as landscaping of the center median.

Natural

- Utilize natural elements as points of visual relief in the urbanized areas.
- Establish and maintain an open space system to conserve natural resources, preserve scenic beauty, and define urban form.
- Create and preserve open space in and around built-up areas to aid in lessening the effects of high noise levels.
- Strengthen environmental pollution control measures. Support research into causes and prevention of environmental pollution.
- Prevent deterioration of natural watershed areas.

The development of an attractive community is one of the first considerations of the residents of the Navajo community, not only as a matter of personal pride and stabilization of property values, but in realization of the natural attractiveness of the area as a desirable place to live.

It is the intent of this community plan that all public facilities be provided commensurate with the need for such facilities. In some cases, the exact location for such facilities has not yet been determined. The final site selection of these facilities will be accomplished during the subdivision map filing process. City policy requires that subdivision maps be reviewed by all public agencies that may have an interest in the proposal. If through this process it is determined that a specific parcel of land within the subdivision is needed for public facility purposes, the parcel in question will be withheld from development for a reasonable period of time to allow the appropriate agency time for property acquisition. It is also intended that in the event the public agency does not arrange for the acquisition of the needed property within a reasonable period of time, private development of the property may occur as consistent with the Plan goals and objectives. Such private development shall conform to Council Policies 600-4 (standards for public rights-of-way improvements),

600-10 (adequate public services in connection with development proposals), 600-18 (residential/commercial/industrial developments phasing), or any other present or future policy of the City of San Diego that may be effective at the time of future development proposals.

Future Study Area

A City-owned parcel adjacent to Pasatiempo Avenue, consisting of ten acres of relatively level land, has been set aside for additional study. This property has been designated as FUTURE STUDY AREA to permit studies to be undertaken to determine an appropriate permanent use⁵

⁵ For land use types, refer to the General Plan Land Use and Community Planning Element - Table LU-4.

IMPLEMENTATION

Thus far, the Navajo Community Plan has set forth a wide range of goals, objectives and proposals aimed at enhancing the community. Based on these, specific actions must be undertaken to realize the Plan. These actions and the ensuing financial obligations usually are joint efforts of private citizens and enterprise and local, state and federal governments. Some implementation programs, however, may be carried out by private initiative only.

Because Navajo is a community developed to relatively high standards and not requiring extensive redevelopment, implementation will emphasize the retention of those qualities such as undeveloped canyons and hillsides which have made the community a desirable place in which to live.

The following is a descriptive list of proposals that includes means of and responsibility for implementation. Although various governmental agencies are listed as having responsibility for carrying out the Plan proposals, the City Council has ultimate responsibility. Regardless, the true burden of the Plan rests with an interested active citizenry. Without constant citizen participation and concern, the implementation of these proposals will never be a reality.

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
I ORGANIZATION				
A. Maintain community rapport.	Continuing	1. Arrange publicity, conduct public meetings, and provide information service.	NCP ⁽¹⁾	Not determined
B. Maintain and implement plan.	Continuing	1. Monitor proposed plans and other actions affecting community plan, provide input as appropriate. 2. Arrange annual public community NCP meeting (more often, if needed) to appraise changing needs and adjust planning & implementation accordingly. 3. Take other steps to promote community consciousness and identity, such as distribution to each	NCP	Not determined

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
		new resident (as well as present residents) of a pamphlet describing how citizens may participate in community planning and development.		
II RESIDENTIAL				
A. Encourage a wide range of densities (30-43, 15-29, 10-14, 5-9, & 0-4 D.U. per acre), develop and/or maintain these densities as shown on the community plan map.	Continuing	Allow no rezoning that conflicts with plan proposals.	Planning Dept.	
⁽¹⁾ Navajo Community Planners, Inc.				
B. Adopt, as City policy, inclusion of a portion of low and moderate income housing in all major residential developments based on objective determination of need for such housing.	Continuing	<ol style="list-style-type: none"> 1. Adopt policy. 2. Enforce policy in working with owners, realtors, developers. 3. Monitor implementation. 	<p>City Council</p> <p>Planning Dept.</p> <p>NCP/ Community Action</p>	
C. Vary housing types and densities to create interest and provide a mix of economic and social characteristics. Implement the Mobile-home Park Overlay Zone.	Immediate	<ol style="list-style-type: none"> 1. Adopt balanced community concept. 2. Enforce policy in working with owners, developers. 3. Monitor implementation. 	<p>City Council</p> <p>Planning Dept.</p> <p>NCP/ Community Action</p>	
D. Require all major residential development proposals to be carried out under a PRD.	Immediate	<ol style="list-style-type: none"> 1. Commission & Council approval of policy. 2. Apply policy to major proposed residential developments. 	<p>Planning Dept.</p> <p>Planning Dept.</p>	

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
E. Relate dwelling units to topography.	Immediate	Work with property owners, realtors, developers to strongly encourage the use of PRD, PCD procedures.		
F. Provide adequate, off-street parking.	Immediate	Work with property owners, realtors, developers to strongly encourage the use of PRD, PCD procedures.	Planning Dept.	
G. Implementation of the Mission Trails District controls.		<ol style="list-style-type: none"> 1. Enforce policy in working with owners and developers. 2. Monitor implementation. 	Planning Dept./NCP Community Action	
H. Implementation of the geologic hazard area controls.	Immediate	<ol style="list-style-type: none"> 1. Enforce policy in working with owners and developers. 2. Monitor implementation. 	Planning Dept.	
III COMMERCIAL				
A. Maintain and/or develop community commercial centers at Lake Murray Blvd. & Navajo Rd., Jackson Dr. & Navajo Rd. & at Waring Rd. & Orcutt St. to include professional & business offices, entertainment & cultural activities, & public & semipublic facilities.	According to need	1. Work with owners, realtors, developers using PCD and other means available.	Planning Dept.	
B. Develop neighborhood commercial centers at Golfcrest Dr. & Mission Gorge Rd to supplement 3 existing centers.	According to need	<ol style="list-style-type: none"> 1. Work with owners, realtors using PCD and other means available. 2. Maintain zoning at existing centers. 3. Rezone land where needed to implement plan. 	Planning Commission/ Planning Dept.	

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
E. Retain visitor-oriented facilities at I-8 at Waring Rd. & Mission Gorge Rd. at Alvarado Canyon Rd. No additional visitor-oriented facilities are proposed.	Immediate & continuing	Monitor situation.	Planning Dept.	
F. Regulate number & location of service stations.	Immediate	1. Obtain approval for criteria. 2. Enforce criteria.	Planning Dept./NCP Planning Dept.	
G. Remove off-premise signs and consolidate multiple on-premise signs.	Continuing	1. Enforce City sign code. 2. Monitor development projects.	Planning Dept./NCP	
H. Process new commercial center developments as PCDs.	Continuing	Require PCD with map or rezone processing.	Planning Dept.	
I. Ensure compliance with design standards in Grantville.	Continuing	1. Apply CPIOZ. 2. Monitor development projects.	Planning Dept./NCP	
J. Implement the Mission Trails Design District controls.		1. Enforce policy in working with owners and developers. 2. Monitor implementation.	Planning Dept./NCP Community Action	
IV INDUSTRIAL				
A. Ensure that property rezoned to permit industrial use is developed in a manner compatible with the river and surrounding residential areas.	Upon application for rezone	Require processing of PID concurrent with rezone processing.	Planning Dept.	
B. Ensure that future development of the remaining sand and gravel facility (VR Dennis) is reviewed for compatibility with the river and Mission Trails Park, and for traffic impacts.	Upon application for rezone	Require processing of master PID concurrent with rezone application.	Planning Dept.	

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
C. Ensure that future development complies with the design standards for Grantville.	Immediate & continuing	1. Apply CPIOZ SDRs. 2. Monitor development projects.	Planning Dept.	
D. Implement the Mission Trails Design District controls.	Continuing	1. Monitor implementation. 2. Work with owners, realtors, developers, & tenants to solicit interest and participation.		

V OPEN SPACE RETENTION AND UTILIZATION

A. Acquire open space system: Mission Gorge 300 ac. (San Diego River system).	As soon as possible	Initiate proceedings for hearing and Council action on establishment.	NCP/City Council/Community Action	Not determined, Assessment District (see cooperative arrangement w/ Water Dist. on land it owns)
B. Redesignate those lands within the open space areas to the guidelines established in the open space element of this report.	Contingent on Open Space Implementation	1. Initiate rezoning. 2. Monitor development of plans for preservation of natural amenities.	Planning Dept.	Not determined
C. Establish hiking trails in S.D. River Basin through Mission Gorge linked to City-County system.	Immediate	Schedule into CIP.	Park and Rec. Dept.	To be determined/ CIP or other funds
D. Public access to open space areas.	Immediate	Establish and maintain.	Park and Rec. Dept.	
E. Establish FW and FPF zoning along the river.	Immediate	Rezone in accordance with FEMA maps.	Engineering & Dev't.	
F. Regulate dev't. adjacent to the river to minimize disturbance to the wetland habitat.	Immediate & ongoing	1. Apply CPIOZ. 2. Adopt Habitat Conservation Plan.	Planning Dept./ SANDAG	

VI PARKS & RECREATION

Park & Recreation Centers

A. Lake Murray Community Park & Rec. Center #370)	As soon as possible	Expanded parking lot, children's play area, site furnishings, and new ball field.	Park and Rec. Dept.	CIP, Park Fees, 1973 Bond Issue
---	---------------------	---	---------------------	---------------------------------

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
B. Allied Gardens Community Park & Recreation Center (#380)	As soon as possible	Expand lockers, new pools & ADA upgrades.	Park and Rec. Dept.	CIP, Park Fees
C. San Carlos Community Park & Recreation Center (#360)	As soon as possible	Ball field lighting.	Park and Rec. Dept.	CIP, Park Fees, 1966 Bond Issue
D. Qualcomm Major Park and Recreation Center	As soon as possible	Sports fields, picnic areas, children's play area, passive recreation areas.	Park and Rec. Dept.	CIP, Park Fees
Neighborhood Parks				
A. Margerum (#383)	1st	Develop City-owned site.	Park and Rec. Dept.	CIP, Park Fees, 1966 Bond Issue
B. Tuxedo (#373)	2nd	Develop City-owned site.	Park and Rec. Dept.	CIP, Park Fees
C. Cowles Mountain (#361)	3rd	Open Space Park-- Lease & develop acreage on Gage Elementary School for active play fields.	Park and Rec. Dept.	CIP, Park Fees, 1977 Bond Issue
D. Dailard (#372)	4th	Develop City-owned site.	Park and Rec. Dept.	CIP, Park Fees, 1973 Bond Issue
E. Pasatiempo Open Space Park (#371)	5th	Develop City-owned site.	Park and Rec. Dept.	CIP, Park Fees
F. Princess Del Cerro (#381)	6th	Develop City-owned site.	Park and Rec. Dept.	CIP, Park Fees
G. Del Cerro (#371)	7th	Investigate purchase of private park.	NCP	Private
H. Grantville Neighborhood Park	?	Develop City-owned site.		
Rancho Mission	?			
. Small parks & plazas in community & neighborhood	Continuing	Encourage developers to include beautification when maps are submitted.	Planning Dept.	Private
Resource-Based Parks				
A. Mission Trails Regional Park				
B. Adobe Falls Open Space Park				
C. Padre Dam				

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
D. San Diego River Park (SDRP)	Immediate & ongoing	Apply San Diego River Subdistrict CPIOZ	Development Services Dept.	CIP Private Grants
VII SCHOOLS				
Adjust boundaries to maintain proper balance.	As needed		San Diego Unified School District	
VIII OTHER COMMUNITY FACILITIES				
Library				
Appraisal of need for additional service.	Continuing	1. Evaluate effect of new branch.	City Librarian	CIP
		2. Consider expansion of Benjamin Branch.		CIP
		3. Consider adding third branch in Community.		
Police, Fire, Water, Sewer, Private Facilities				
Monitor adequacy of service.	Continuing	Notify appropriate City staff of unmet service needs and follow up as needed with staff and/or Council.	NCP/Community Action	
Flood Control				
A. Monitor San Diego River Control Plan.	Continuing	1. Ensure adequate control plan is implemented.	NCP/Community Action	
B. Monitor Alvarado Creek Control Plan.	Continuing	2. Apply appropriate zoning.	NCP/Community Action	
IX CIRCULATION				
Public Transportation				
A. Increase frequency & hours for routes.	Immediately	Implement plans.	MTDB	Not determined
B. Extend routes indicated on Network Map.	As soon as possible	Implement plans.	MTDB	Not determined

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
C. Provide I-8 express service--El Cajon to Downtown with a stop in Navajo Community.	As soon as possible	Implement plans.	MTDB	Not determined
D. Institute area minibus system.	Long-range	Develop and implement local service plan, possibly linked to citywide.	NCP/ through MTDB or Private	Not determined
E. Construct LRT system along the east Mission Valley corridor.	Short-range	Implement plans.	MTDB	Local, State and Federal Transit Funding
Bikeways				
F. Develop community bikeway system coordinated with regional system.	As soon as possible	Follow through for implementation of approved plans.	Engineering & Dev't.	CIP, Bikeway Fund, General Fund
Streets				
G. Increase I-8 & I-15 traffic handling capacity.	As soon as possible	Continuing study and improvement.	Engineering & Dev't./ State Div. of Highways	Hwy. Trust Fund, Gas Tax
H. Extend Navajo Rd.	When needed & conditions met	Monitor need and I-8 access; schedule into CIP.	Engineering & Dev't.	CIP, Gas Tax
I. Expansion of existing roads to 6 lanes: Friars Rd., Mission Gorge Rd.	According to need	Schedule into CIP according to need.	Engineering & Dev't.	CIP
J. Extend Jackson Dr. to Mission Gorge Road.	As soon as possible	Construct according to CIP.	Engineering & Dev't.	CIP, Gas Tax
K. Provide misc. special treatments.	As needed	Monitor & determine needs and opportunities to increase capacity of road system through special treatment.	Engineering & Dev't.	CIP and/or General Fund
L. Construct easterly extension of Alvarado Canyon Rd.	Concurrent with LRT system	Implements plans.	Engineering & Capital Projects Dept.	Local, State and Federal Funding
M. Realign Alvarado Canyon Rd. to Fairmount/Mission Gorge Rd.	As soon as possible	Proceed with design and environmental review when funding has been identified.	Engineering & Capital Projects Dept.	Local, State and Federal Funding

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
N. San Diego River Bike Pathway		Implement the bike route through private development	Development Services Dept.	CIP Private Funds
X COMMUNITY ENVIRONMENT				
A. Improve grading, landscaping standards and control of hillside cuts.	Immediate	1. Proposed amendment to PRD, PCD, & HR requirements to provide better protection and enhancement of environment.	Planning Dept.	
		2. Enforce adopted standards.	Planning Dept.	
B. Underground utilities.	As soon as possible	Seek scheduling of undergrounding of utilities on major streets not already undergrounded.	Community Action/NCP	Utility Co. assume program or Assessment District
C. Extend Cable TV.	As soon as possible	Approach franchise operators re: expediting service follow-up.	Community Action/NCP	
D. Require use of master antenna in PRDs.	Continuing	Establish criterion through City Council that master antennas only are allowed in PRDs.	Planning Dept.	
E. Extend sign control.	Immediate	Adopt proposed changes in Sign Control Ordinance.	City Council	
F. Screen Mission Gorge Road industrial development.	Immediate	Persuade property owners to create special assessment.	NCP/Community Action	Assessment District
G. Plant street trees & landscaping: Navajo Road, Mission Gorge Road, College Ave., & Waring Road.	Immediate	Initiate special assessment districts as determined with City staff.	NCP/Community Action	Assessment District
H. Control environmental pollution.	Immediate & continuing	Develop new programs & practices.	Community Action/City Council	
I. Prepare Urban Design Plan.	Immediate		Planning Dept.	

Proposal or Activity	Priority or Timing	Action	Responsibility	Financing Method
J. Implement the Mission Trails Design District controls.	As soon as possible	Monitor implementation.	Planning Dept./NCP/ Community Action	

CONCLUSION

Comprehensive review of the community plan by the Navajo Community Planners and City staff should be undertaken at periodic intervals to accomplish the following:

- Review and analyze the relationship of development trends to the goals and proposals of the Plan.
- Investigate new implementation tools and aids for their application in making sustained progress towards achievement of the goals of the Plan.
- Recommend appropriate Plan amendments to the City Planning Commission and City Council to ensure the Plan is kept up to date.

Navajo is one of the fastest growing residential areas in the City of San Diego. As such, its future will be a significant factor in the quality of the City as a whole. As a young community, Navajo exhibits the promise of youthfulness and the problems of rapid growth. It is paramount that guidelines be established for the community as a desirable place in which to live.

It is the purpose of the Navajo Community Plan to provide such a framework for the City Council, Planning Commission, private developers and other people concerned with the area's future. In essence, the Plan gives rational direction to the recognition that planning must be an ongoing process supported by the citizens. The continuing vitality of the Navajo Community Planners will be a key element in the success of planning for this community.

The Navajo Community Plan can only be meaningful if it leads to action-oriented implementation. The programs outlined previously, both public and private, are necessary tools for the effectuation of the Plan. They chart a course that embodies the various proposals presented, and together with the entire Plan, assure the significance which it deserves now and in the year 2000.

STANDARDS AND DEFINITIONS

Balanced Transportation System - A transportation network in which the several circulation subsystems (auto, bus, LRT, bike, etc.) complement and reinforce one another and provide mobility, accessibility and safety for residents of the community.

Bikeways fall into three general categories based on the degree or extent of their improvements:

Bicycle paths (Class I) are completely separate from vehicle traffic.

Bicycle lanes (Class II) along streets are reserved for bikes only. They may be marked with a painted stripe on the road (more a psychological than a physical protection) or with curb barriers.

Bicycle routes (Class III) are simply lightly traveled streets marked with signs encouraging bicycle use and cautioning motorists.

Commercial

Regional Centers emphasize such shopping goods as apparel, major household appliances, and furnishings. The dominant establishments are usually one or more department stores. Variety and specialized stores are typical tenants, as are business and professional services. Recently, automobile agencies and major recreational facilities have made their appearance. In all, more than forty different kinds of establishments are generally required to provide the range of goods and services associated with regional centers.

Community Centers provide a wide range of convenience goods as well as some shopping goods. A variety or junior department store may be the primary facility among the more than twenty different kinds of establishments normally found in this type of center.

Neighborhood Centers characteristically provide goods and services of a convenience nature, designed to meet daily needs. The dominant store is usually a supermarket. Other establishments may include a drug store, liquor store, self-service laundry, beauty and barber shop, shoe repair and service station. At least fifteen different kinds of establishments are necessary to provide a complete range of convenience goods and services.

A smaller center is sometimes economically feasible and will provide public convenience where the distance to the nearest shopping center is at least one mile, or where the local topography isolates an area of residences. These smaller centers, which can be supported by resident populations of one to two thousand, consist of a small grocery store, service station, and one or more service establishments. However, the limited size and composition of such small centers place them at a competitive disadvantage except under the unusual circumstances noted.

Specialized commercial uses include automobile sales agencies, furniture stores, bowling alleys, drive-in theaters, hotels, motels and a wide variety of business, personal and repair services. Their trade areas are normally not easily definable since these establishments may attract patronage from a metropolitan or regional area. Specialized commercial uses are generally found

in strip developments along major streets; however, they occasionally seek to cluster for mutual support, and sometimes locate within or adjacent to community and regional centers.

Visitor-oriented commercial uses are intended primarily to serve tourists, business travelers, or those persons attending conventions. Such uses largely include hotels, motels, trailer parks and convention facilities. Locations are determined by regional access routes and terminals, specialized recreational facilities, and centers of financial and administrative facilities.

Business and professional office development is often efficiently clustered near such institutional facilities as hospitals, clinics, and research complexes. In addition, it may be appropriately located at the periphery, or even within major concentrations of commercial activities.

Planned Commercial Development (PCD) - a Planned Commercial Development is a predominantly commercial project designed and improved in accordance with a comprehensive project plan located within any commercial zoning district except CP (Commercial Parking). It may include residential, office, institutional, cultural, selected light manufacturing and recreational uses and facilities. A Planned Commercial Development may be subject to a development phasing program reflecting anticipated needs of project population growth in the service area of the project.

The PCD regulations provide for a greater variety of goods and services than is normally found within a center built under typical commercial zone regulations. Included are residential and certain light industrial or handicraft uses as well as a full range of both light and heavy retail uses, commercial recreation activities and public services.

An underlying purpose of the Planned Commercial Development is to encourage full-time use of the center's facilities while minimizing space allocated to parking. Consequently, it is conceived that reductions in the total off-street parking requirement might be granted by the Planning Commission where it can be shown that different uses utilize the same parking facilities at different times of the day. This provision could, in some instances, significantly reduce the vast parking areas typically required in larger regional and community centers.

The PCD regulations also provide for a program of phased development where it is deemed desirable. Such a program would be based upon population growth within the potential service area of a Planned Commercial Development. This provision requires that the developer present and follow a construction program that will ensure that residents of the service area are provided with adequate commercial services during development of the center and to ensure that community and regional shopping centers are not developed in a piecemeal manner with a resultant loss in design cohesiveness and sensitivity.

Conditional Use Permits are issued for special uses of land which are not included in the normal range of permitted uses in any zone. Examples include churches, schools, service stations, etc.

Demography is the science of vital and social statistics, such as the births, deaths, diseases, marriages, etc.

Density is the ratio between numbers of persons or dwellings and land area.

Density Ranges

Very low density	0-4 dwelling units per acre
Low density	5-9 dwelling units per acre
Low-medium density	10-14 dwelling units per acre
Medium density	15-29 dwellings units per acre
Medium-high density	30-43 dwelling units per acre
High density	44-73 dwelling units per acre
Very high density	44-109 dwelling units per acre

Developed Land is land upon which improvements have been made (grading, structures, agricultural use).

Dial-A-Bus is a system of small buses on fixed routes or in designated areas. On-call vehicles will pick up passengers at home and take them to their destination.

Dwelling Unit - a room or suite of rooms in a building or portion thereof, used, intended, or designed to be used or occupied for living purposes by one family, and containing only one kitchen.

Express Bus - buses operating nonstop or with limited stops between two points over existing streets and/or freeways.

Field Act - Long Beach, in 1933, experienced an earthquake that destroyed a large number of school buildings. As a consequence of this earthquake, the State Legislature enacted legislation known as the "Field Act" which provided for the establishment of structural standards both in design and construction of school buildings. This Act was amended in 1968 to provide that any building classified as unsafe shall not be used for classroom purposes after July 1, 1975.

Fire Stations - require a site size of approximately three-quarters of an acre. This is regarded by many authorities as appropriate for a fire station. This provides an adequate amount of layout area for fire hoses.

According to present General Plan standards, fire station service areas should be determined on the basis of present and proposed land use patterns and freeway and major street systems. Currently, in newly developing areas, fire stations are being provided on the basis of a four-mile service area and five-minute response time. Fire stations should be situated so as to permit easy access to major streets.

Floodplain - the relatively flat area of low lands adjoining, and including, the channel of a river, stream, water course, bay or other body of water which is subject to inundation by flood waters of the Standard Project Flood established by the U. S. Army Corps of Engineers.

Floodplain Fringe - all that land in a floodplain not lying within a delineated floodway. Land within a floodplain fringe is subject to inundation by relatively low velocity flows and shallow water depths.

Floodway - that land in a floodplain, which is delineated on a map approved by the City

Council, required for passage of a 100-year frequency flood in an unlined channel with a resultant rise in the natural flood water profile of one foot. The natural flood water profile is the water surface elevation of a non-confined 100-year frequency flood in the natural undeveloped floodplain.

Health Care Facilities - Hospitals should be located as near as possible to the center of the population served. Community hospitals should be located not more than 20 minutes automobile travel time from any point in the service area.

General hospitals should have frontage on a prime arterial or major street. Specialized hospitals and long-term care facilities should have frontage on a collector or local street. Community general hospitals should have public transportation available within one-quarter mile of the facility. Regional general hospitals, because of the very large area served, should have convenient access to all forms of transportation.

Hospitals normally should not be located adjacent to lands that create an exceptionally high degree of activity or generate undue noise such as that emanating from railroads, freight yards, schools, stadia, or playgrounds. Specialized hospitals and long-term care facilities should be a part of or in proximity to a community or metropolitan general hospital in order to provide a full range of medical care for the inpatients.

Site area should be sufficiently large to accommodate the facility, the required off-street parking, planned future additions, and open space. When fully developed, about 50 percent of the site should remain uncovered by buildings.

Libraries

Community Branches - Currently, the General Plan standards state that a branch library should have a minimum of 5,000 square feet of floor area and contain a minimum book collection of 20,000 volumes. The branch library should have a site size of approximately one acre and should serve a resident population of at least 15,000 persons. Recently, the City Librarian advocated a system of larger branches or community libraries. Under this proposal, these facilities would be spaced farther apart and serve larger geographical areas. Large branch libraries would be from 10,000-15,000 square feet in floor area and house 44,000 to 66,000 volumes. The service area would have a radius of about two miles and include from 33,000 to 45,000 residents. Site size would be approximately one and one-half acres. In some cases, medium size branch of 8,000-10,000 square feet of floor space with 35,000-44,000 volumes would be provided to serve a resident population within a radius of slightly less than two miles. Small branches under 8,000 square feet would be provided for areas between large branches as funding became available and after there had been an opportunity to observe the effectiveness of the larger unit's operation.

Bookmobiles - Bookmobiles should contain 2,000 to 3,000 books per unit and serve sparsely populated or inadequately served areas on a once or twice a week basis, as demand indicates. Bookmobiles should also be used to test future locations for new branch libraries.

Modal Split - the separation of person trips by type of travel used, such as driving automobiles, riding on transit facilities, or walking.

Multiple Dwelling - a building used or designed to be used for housing three or more families.

Open Space – Is defined in the City’s General Plan as land that provides for the preservation of land that has distinctive scenic, natural or cultural features that contribute to community character and form, of that contains environmentally sensitive resources. Applies to land or water areas that are undeveloped, generally free from development, or developed with very low-intensity uses that respect natural environmental characteristics and are compatible with the open space use. Open Space may have utility for; primarily passive park and recreation uses; conservation of land, water, or other natural resources; historic or scenic purposes; visual relief; or landform preservation.

Parks

Population-Based Parks¹ - those intended to serve the recreational needs of the immediately surrounding residential population. The two categories of such parks are discussed below.

Neighborhood Parks and Playgrounds - Neighborhood parks should contain a minimum usable area of three to thirteen acres. They should serve a resident population of 5,000 persons within approximately one mile. The arrangement of space and the type of facilities located within each park must be related to the population and use characteristics of the neighborhood served. However, each park should have at least a play area, multipurpose courts, picnic facilities, lawn area and landscaping.

Community Park and Recreation Centers - Community parks Recreation Centers should serve a population of 25,000. Community Parks to be 13 acres minimum. Community parks should provide a wide range of facilities including athletic fields and multipurpose courts, picnic facilities, a variety of play areas, a recreation center building, lawn areas, and landscaping.

Resource-Based Parks² - Resource-based parks and recreation areas should be located in areas notable for scenic, natural, or cultural attractions. The two subcategories of resource-based parks are Regional Park and Shoreline Parks and Beaches. Resource-Based parks serve regional residents and/or visitor populations. Developed amenities should not impair the distinctive features or resources.

River Corridor Area - The area comprised of the current 100-year floodway as mapped by the Federal Emergency Management Agency (FEMA) and the 35-foot wide Path Corridor on each side of the floodway.

River Influence Area - The 200-foot wide area extending outward from the River Corridor Area on each side of the river.

Mini-Parks - Small areas used for open space or recreation. They may be used as play areas for small children, in which case they supplement individual backyards. They may serve senior citizens only, older children, or all age groups, depending on the needs in the neighborhood. They may include play apparatus, paved areas, sand pits, wading pools or simply be planted in grass. Their size usually ranges from one acre to 3 acres, although in the past the size and location generally depended more on availability of vacant parcels of land than on other factors. Mini-parks serve population within ½ mile and are accessible primarily by bicycling and walking.

Park-and-Ride - Terminals where passengers may leave their cars and transfer to public transportation.

Planned Residential Development - A predominately residential development improved in accordance with an overall project plan and characterized by the following:

1. The density regulations of the zone in which the Planned Residential Development is located are applied to the total area of the Planned Residential Development rather than separately to individual lots or building sites.
2. The right to use and enjoy any privately-owned common open space areas and recreational facilities provided on the site of the Planned Residential Development shall be coupled with the severalty interests of the owners of the dwelling units. Ownership may be of lots or condominiums or both.
3. A Planned Residential Development may include accessory commercial, office and recreational facilities limited in size and capacity to the needs of the occupants of the development and their guests.

Public Transportation, Mass Transit, Mass Transportation - General terms, often used interchangeably to describe a system of common carrier facilities offering transportation service on a fare payment basis and operating on established schedules along designated routes with specific stops.

1. LRT-Light Rail Transit is a mode of urban transportation utilizing predominantly reserved but not necessarily grade-separated rights-of-way. Electrically propelled rail vehicles operate singly or in trains. The LRT provides a wide range of passenger capabilities and performance characteristics.
2. Bus Transit is a mode of urban transportation operating primarily in 40-foot transit vehicles on public rights-of-way. Buses operate on clean diesel or Compressed Natural Gas (CNG). Bus transit is characterized by route and planning flexibility to allow service modifications as community dynamics change.

Rapid Transit - Mass transportation either by rail or bus, distinguished from other transit by its operating at high average speeds over exclusive, grade separated rights-of-way.

Street Classifications - The five basic functional categories of streets in San Diego are present in Navajo. They are freeways, prime arterial, major streets, collector streets and local streets.

Freeways (usually under the jurisdiction of the California Division of Highways) - are designed to carry large volumes of through traffic and are always divided highways. They have no at-grade intersections and traffic may cross, enter, or leave it only via the ramps of an interchange.

Prime arterials also are intended to facilitate the movement of large volumes of traffic and are usually, but not always, divided highways. Most street crossings will be at-grade, but there may be a few interchanges. There will be no driveways from abutting property, and traffic may cross, enter, or leave the road only at an interchange or intersection.

Major streets are designed primarily to carry traffic through an area but will generally also provide access to abutting property. They may be divided but normally all street crossings will be at-grade and there will be little or no restriction of driveway access.

Collector streets function both to distribute traffic from arterial thoroughfares and to provide access to abutting property. They are rarely divided, all street crossings will be at-grade, and there will be no restriction of driveway access.

Local streets are designed primarily to provide access to abutting property. They normally are not divided, but have all street crossings at-grade and have no restriction on driveway access.

Parkways are limited access roads that traverse a corridor within which all natural scenic resources and aesthetic values are protected and enhanced.



THE CITY OF SAN DIEGO

DATE OF NOTICE: (April 28, 2015)

NOTICE OF PUBLIC HEARING

PLANNING COMMISSION RECOMMENDATION

DATE OF HEARING: May 14, 2015
TIME OF HEARING: 9:00 A.M.
LOCATION OF HEARING: Council Chambers, 12th Floor, City Administration Building,
202 C Street, San Diego, California 92101

PROJECT TYPE: Process Five: Amendment to the Navajo Community
Plan/General Plan; Rezones; Environmental Impact Report
(SCH No. 2013111017), including a water supply assessment.

PROJECT NUMBER: 346289

PROJECT NAME: GRANTVILLE FOCUSED PLAN AMENDMENT

APPLICANT: City of San Diego

COMMUNITY PLAN AREA: Navajo
COUNCIL DISTRICT: 7

CITY PROJECT MANAGER: Seth Litchney, Senior Planner
PHONE NUMBER/E-MAIL: (619) 236-6892 slitchney@sandiego.gov

As a property owner, tenant or person who has requested notice, you should know that the Planning Commission will hold a public hearing to **recommend** approval, conditional approval, or denial to the City Council of the Grantville Focused Plan Amendment (FPA). The amendments are subject to Process 5 review. The Grantville FPA consists of the following components: an amendment to the Navajo Community Plan; an amendment to the Community Plan Implementation Overlay Zone (CPIOZ) language within the Navajo Community Plan; the processing of rezones to implement the Plan; and an update to the Navajo Public Facilities Financing Plan; certification of the Program Environmental Impact Report (PEIR) SCH No. 2013111017 including adoption of the Findings, a Statement of Overriding Considerations, and a Mitigation, Monitoring and Reporting Program. The

public notice of preparation was filed on November 5, 2013 for the PEIR. The draft PEIR was released on December 16, 2014 and the public comment period closed on February 17, 2015, after receiving a 14-day extension. The final PEIR and associated technical appendices have been placed on the City of San Diego web-site at:

<http://www.sandiego.gov/planning/community/cpu/grantvillemasterplan/index.shtml>

The list of Assessor's Parcel Numbers proposed for zoning change is as follows:

43-402-013, 45-852-111, 45-870-012, 46-115-013, 46-121-004, 46-123-508, 46-132-005, 46-161-015, 43-402-029, 45-852-112, 45-870-013, 46-115-021, 46-121-005, 46-123-601, 46-132-006, 46-161-016, 43-402-029, 45-852-115, 45-872-002, 46-115-022, 46-121-006, 46-123-602, 46-132-007, 46-161-017, 43-402-030, 45-852-117, 45-872-003, 46-115-023, 46-121-007, 46-123-603, 46-132-008, 46-161-018, 43-404-044, 45-852-121, 45-872-007, 46-115-024, 46-121-009, 46-123-604, 46-132-009, 46-161-019, 43-404-045, 45-852-122, 45-872-011, 46-116-001, 46-121-010, 46-123-605, 46-132-011, 46-161-020, 43-404-105, 45-852-123, 45-872-014, 46-116-002, 46-121-011, 46-123-606, 46-132-012, 46-161-021, 43-404-108, 45-852-125, 45-872-015, 46-116-003, 46-121-012, 46-123-607, 46-132-020, 46-161-022, 45-830-003, 45-852-126, 45-872-016, 46-116-004, 46-122-010, 46-123-608, 46-132-021, 46-161-023, 45-830-004, 45-852-127, 46-102-103, 46-116-005, 46-122-011, 46-123-609, 46-132-023, 46-161-024, 45-830-014, 45-852-128, 46-102-104, 46-116-006, 46-122-012, 46-123-610, 46-132-024, 46-161-025, 45-830-015, 45-852-129, 46-102-105, 46-116-007, 46-122-015, 46-124-103, 46-132-025, 46-161-026, 45-830-016, 45-852-130, 46-102-106, 46-116-008, 46-122-016, 46-124-104, 46-132-026, 46-161-027, 45-830-017, 45-852-202, 46-102-107, 46-116-009, 46-122-017, 46-124-105, 46-132-027, 46-162-004, 45-834-209, 45-852-203, 46-102-108, 46-116-010, 46-122-018, 46-124-203, 46-132-028, 46-162-006, 45-834-210, 45-852-204, 46-102-109, 46-116-015, 46-122-026, 46-124-204, 46-132-029, 46-162-007, 45-834-211, 45-852-205, 46-102-110, 46-116-020, 46-122-028, 46-124-301, 46-132-030, 46-162-008, 45-834-212, 45-852-206, 46-102-111, 46-117-003, 46-122-030, 46-124-302, 46-133-021, 46-162-009, 45-834-215, 45-852-207, 46-102-112, 46-117-005, 46-122-032, 46-124-303, 46-133-022, 76-022-667, 45-834-220, 45-852-209, 46-102-113, 46-117-006, 46-122-035, 46-124-304, 46-133-023, 76-022-678, 45-834-221, 45-852-211, 46-102-118, 46-117-007, 46-122-036, 46-124-305, 46-133-024, 76-022-679, 45-834-223, 45-852-214, 46-102-119, 46-117-008, 46-122-042, 46-124-306, 46-133-025, 76-022-689, 45-834-224, 45-852-217, 46-102-120, 46-117-011, 46-122-043, 46-124-310, 46-133-026, 76-022-696, 45-834-301, 45-852-218, 46-102-123, 46-117-012, 46-122-044, 46-124-311, 46-133-030, 76-022-697, 45-834-302, 45-852-219, 46-102-124, 46-117-013, 46-122-045, 46-125-201, 46-133-031, 45-834-327, 45-852-220, 46-102-202, 46-117-014, 46-122-046, 46-125-202, 46-133-032, 45-834-328, 45-852-223, 46-102-203, 46-117-015, 46-122-047, 46-125-208, 46-133-033, 45-851-001, 45-852-224, 46-102-204, 46-118-004, 46-122-048, 46-125-209, 46-133-034, 45-851-003, 45-853-102, 46-102-205, 46-118-005, 46-122-049, 46-125-210, 46-133-035, 45-851-004, 45-853-121, 46-103-003, 46-118-006, 46-123-303, 46-127-220, 46-161-001, 45-851-005, 45-853-122, 46-103-004, 46-118-007, 46-123-304, 46-130-003, 46-161-002, 45-851-011, 45-853-123, 46-103-019, 46-118-010, 46-123-305, 46-130-004, 46-161-003, 45-851-012, 45-853-126, 46-103-020, 46-118-011, 46-123-403, 46-130-013, 46-161-004,

45-851-014, 45-853-127, 46-103-026, 46-118-012, 46-123-404, 46-130-017, 46-161-005, 45-851-018, 45-853-204, 46-103-040, 46-119-004, 46-123-405, 46-130-018, 46-161-006, 45-851-026, 45-853-212, 46-103-043, 46-119-005, 46-123-406, 46-130-019, 46-161-007, 45-851-027, 45-853-216, 46-103-045, 46-119-006, 46-123-407, 46-130-020, 46-161-008, 45-851-028, 45-853-220, 46-103-046, 46-119-008, 46-123-408, 46-130-021, 46-161-009, 45-851-029, 45-853-222, 46-103-047, 46-120-009, 46-123-503, 46-130-022, 46-161-010, 45-851-030, 45-870-004, 46-103-048, 46-120-011, 46-123-504, 46-130-023, 46-161-011, 45-851-032, 45-870-007, 46-115-010, 46-120-012, 46-123-505, 46-132-002, 46-161-012, 45-851-033, 45-870-010, 46-115-011, 46-120-013, 46-123-506, 46-132-003, 46-161-013, 45-852-103, 45-870-011, 46-115-012, 46-121-003, 46-123-507, 46-132-004, 46-161-014.

Objectives of the Grantville FPA include the following: promote Transit Oriented Development (TOD) within walking distance to the Grantville Trolley Station, promote revitalization of properties which are underutilized; promote a multi-modal transportation strategy including walkable and bicycle-friendly streets; provide additional market-rate and affordable housing opportunities consistent with a land use pattern that promotes infill development; and facilitate implementation of the San Diego River Park Master Plan. The Grantville FPA provides direction for future development and has been guided by the citywide policy direction contained in the City of San Diego General Plan.

The decision to approve, conditionally approve, modify, or deny the amendments to the General Plan, Navajo Community Plan, and the Rezone will be made by the City Council at a future public hearing. A separate notice of public hearing will be provided 10 business days prior to the City Council hearing for this item.

If you wish to challenge the City's action on the above proceedings in court, you may be limited to addressing only those issues you or someone else have raised at the public hearing described in this notice, or written in correspondence to the City at or before the public hearing. If you have any questions after reviewing this information, you can contact Seth Litchney, listed above.

This information will be made available in alternative formats upon request. To request an agenda in alternative format or to request a sign language or oral interpreter for the meeting, call the Disability Services Program Coordinator at (619) 236-5979 at least five working days prior to the meeting to ensure availability. Assistive Listening Devices (ALD's) are available for the meeting upon request.

This notice was published in the SAN DIEGO DAILY TRANSCRIPT and distributed on April 28, 2015.

Internal Order Number: 21003370



THE CITY OF SAN DIEGO

Seth Litchney / Project No. 346289

Long Range Planning

1222 First Ave., MS 413 • San Diego, California 92101-3864

Return Service Requested



THE CITY OF SAN DIEGO

DATE OF NOTICE: (April 28, 2015)

NOTICE OF PUBLIC HEARING

PLANNING COMMISSION RECOMMENDATION

DATE OF HEARING: May 14, 2015
TIME OF HEARING: 9:00 A.M.
LOCATION OF HEARING: Council Chambers, 12th Floor, City Administration Building,
202 C Street, San Diego, California 92101

PROJECT TYPE: Process Five: Amendment to the Navajo Community
Plan/General Plan; Rezones; Environmental Impact Report
(SCH No. 2013111017), including a water supply assessment.

PROJECT NUMBER: 346289

PROJECT NAME: GRANTVILLE FOCUSED PLAN AMENDMENT

APPLICANT: City of San Diego

COMMUNITY PLAN AREA: Navajo
COUNCIL DISTRICT: 7

CITY PROJECT MANAGER: Seth Litchney, Senior Planner
PHONE NUMBER/E-MAIL: (619) 236-6892 slitchney@sandiego.gov

As a property owner, tenant or person who has requested notice, you should know that the Planning Commission will hold a public hearing to **recommend** approval, conditional approval, or denial to the City Council of the Grantville Focused Plan Amendment (FPA). The amendments are subject to Process 5 review. The Grantville FPA consists of the following components: an amendment to the Navajo Community Plan; an amendment to the Community Plan Implementation Overlay Zone (CPIOZ) language within the Navajo Community Plan; the processing of rezones to implement the Plan; and an update to the Navajo Public Facilities Financing Plan; certification of the Program Environmental Impact Report (PEIR) SCH No. 2013111017 including adoption of the Findings, a Statement of Overriding Considerations, and a Mitigation, Monitoring and Reporting Program. The

public notice of preparation was filed on November 5, 2013 for the PEIR. The draft PEIR was released on December 16, 2014 and the public comment period closed on February 17, 2015, after receiving a 14-day extension. The final PEIR and associated technical appendices have been placed on the City of San Diego web-site at:

<http://www.sandiego.gov/planning/community/cpu/grantvillemasterplan/index.shtml>

The list of parcels proposed for zoning change is identified by Assessor's Parcel Numbers on Attachment A. Attachment A includes all the assessor's parcel numbers that will be rezoned. Attachment B highlights the location of the rezone area. The rezone area includes approximately 227 acres.

Objectives of the Grantville FPA include the following: promote Transit Oriented Development (TOD) within walking distance to the Grantville Trolley Station, promote revitalization of properties which are underutilized; promote a multi-modal transportation strategy including walkable and bicycle-friendly streets; provide additional market-rate and affordable housing opportunities consistent with a land use pattern that promotes infill development; and facilitate implementation of the San Diego River Park Master Plan. The Grantville FPA provides direction for future development and has been guided by the citywide policy direction contained in the City of San Diego General Plan.

The decision to approve, conditionally approve, modify, or deny the amendments to the General Plan, Navajo Community Plan, and the Rezone will be made by the City Council at a future public hearing. A separate notice of public hearing will be provided 10 business days prior to the City Council hearing for this item.

If you wish to challenge the City's action on the above proceedings in court, you may be limited to addressing only those issues you or someone else have raised at the public hearing described in this notice, or written in correspondence to the City at or before the public hearing. If you have any questions after reviewing this information, you can contact Seth Litchney, listed above.

This information will be made available in alternative formats upon request. To request an agenda in alternative format or to request a sign language or oral interpreter for the meeting, call the Disability Services Program Coordinator at (619) 236-5979 at least five working days prior to the meeting to ensure availability. Assistive Listening Devices (ALD's) are available for the meeting upon request.

This notice was published in the SAN DIEGO DAILY TRANSCRIPT and distributed on April 28, 2015.

Internal Order Number: 21003370

Revised 04-16-15


GRANTVILLE FOCUSED PLAN AMENDMENT

Assessor's Parcel Numbers Proposed for Zoning Change

43-402-013	45-852-111	45-870-012	46-115-013	46-121-004	46-123-508	46-132-005	46-161-015
43-402-029	45-852-112	45-870-013	46-115-021	46-121-005	46-123-601	46-132-006	46-161-016
43-402-029	45-852-115	45-872-002	46-115-022	46-121-006	46-123-602	46-132-007	46-161-017
43-402-030	45-852-117	45-872-003	46-115-023	46-121-007	46-123-603	46-132-008	46-161-018
43-404-044	45-852-121	45-872-007	46-115-024	46-121-009	46-123-604	46-132-009	46-161-019
43-404-045	45-852-122	45-872-011	46-116-001	46-121-010	46-123-605	46-132-011	46-161-020
43-404-105	45-852-123	45-872-014	46-116-002	46-121-011	46-123-606	46-132-012	46-161-021
43-404-108	45-852-125	45-872-015	46-116-003	46-121-012	46-123-607	46-132-020	46-161-022
45-830-003	45-852-126	45-872-016	46-116-004	46-122-010	46-123-608	46-132-021	46-161-023
45-830-004	45-852-127	46-102-103	46-116-005	46-122-011	46-123-609	46-132-023	46-161-024
45-830-014	45-852-128	46-102-104	46-116-006	46-122-012	46-123-610	46-132-024	46-161-025
45-830-015	45-852-129	46-102-105	46-116-007	46-122-015	46-124-103	46-132-025	46-161-026
45-830-016	45-852-130	46-102-106	46-116-008	46-122-016	46-124-104	46-132-026	46-161-027
45-830-017	45-852-202	46-102-107	46-116-009	46-122-017	46-124-105	46-132-027	46-162-004
45-834-209	45-852-203	46-102-108	46-116-010	46-122-018	46-124-203	46-132-028	46-162-006
45-834-210	45-852-204	46-102-109	46-116-015	46-122-026	46-124-204	46-132-029	46-162-007
45-834-211	45-852-205	46-102-110	46-116-020	46-122-028	46-124-301	46-132-030	46-162-008
45-834-212	45-852-206	46-102-111	46-117-003	46-122-030	46-124-302	46-133-021	46-162-009
45-834-215	45-852-207	46-102-112	46-117-005	46-122-032	46-124-303	46-133-022	76-022-667
45-834-220	45-852-209	46-102-113	46-117-006	46-122-035	46-124-304	46-133-023	76-022-678
45-834-221	45-852-211	46-102-118	46-117-007	46-122-036	46-124-305	46-133-024	76-022-679
45-834-223	45-852-214	46-102-119	46-117-008	46-122-042	46-124-306	46-133-025	76-022-689
45-834-224	45-852-217	46-102-120	46-117-011	46-122-043	46-124-310	46-133-026	76-022-696
45-834-301	45-852-218	46-102-123	46-117-012	46-122-044	46-124-311	46-133-030	76-022-697
45-834-302	45-852-219	46-102-124	46-117-013	46-122-045	46-125-201	46-133-031	
45-834-327	45-852-220	46-102-202	46-117-014	46-122-046	46-125-202	46-133-032	
45-834-328	45-852-223	46-102-203	46-117-015	46-122-047	46-125-208	46-133-033	
45-851-001	45-852-224	46-102-204	46-118-004	46-122-048	46-125-209	46-133-034	
45-851-003	45-853-102	46-102-205	46-118-005	46-122-049	46-125-210	46-133-035	
45-851-004	45-853-121	46-103-003	46-118-006	46-123-303	46-127-220	46-161-001	
45-851-005	45-853-122	46-103-004	46-118-007	46-123-304	46-130-003	46-161-002	
45-851-011	45-853-123	46-103-019	46-118-010	46-123-305	46-130-004	46-161-003	
45-851-012	45-853-126	46-103-020	46-118-011	46-123-403	46-130-013	46-161-004	
45-851-014	45-853-127	46-103-026	46-118-012	46-123-404	46-130-017	46-161-005	
45-851-018	45-853-204	46-103-040	46-119-004	46-123-405	46-130-018	46-161-006	
45-851-026	45-853-212	46-103-043	46-119-005	46-123-406	46-130-019	46-161-007	
45-851-027	45-853-216	46-103-045	46-119-006	46-123-407	46-130-020	46-161-008	
45-851-028	45-853-220	46-103-046	46-119-008	46-123-408	46-130-021	46-161-009	
45-851-029	45-853-222	46-103-047	46-120-009	46-123-503	46-130-022	46-161-010	
45-851-030	45-870-004	46-103-048	46-120-011	46-123-504	46-130-023	46-161-011	
45-851-032	45-870-007	46-115-010	46-120-012	46-123-505	46-132-002	46-161-012	
45-851-033	45-870-010	46-115-011	46-120-013	46-123-506	46-132-003	46-161-013	
45-852-103	45-870-011	46-115-012	46-121-003	46-123-507	46-132-004	46-161-014	



CITY OF SAN DIEGO • DEVELOPMENT SERVICES
PROPOSED REZONING



Grantville Rezone

ORDINANCE NO. _____
 EFF. DATE ORD. _____
 ZONING SUBJ. TO _____
 BEFORE DATE _____
 EFF. DATE ZONING _____
 MAP NAME AND NO. _____

REQUEST VARIOUS
PLANNING COMM. RECOMMENDATION
CITY COUNCIL ACTION

CASE NO.

DEVELOPMENT SERVICES MANAGER

B- 4308

APN: VARIOUS

(227-1737) 4-9-15 Ldj



THE CITY OF SAN DIEGO

Seth Litchney / Project No. 346289

Long Range Planning

1222 First Ave., MS 413 • San Diego, California 92101-3864

Return Service Requested

Parcel Numb	First Owner Name	Mailing Address	City
43-402-013	DENTON EDMON TESTAMENTARY TRUST	2223 AVENIDA LA JOLLA	
43-402-029	ASENCIO NICOLE	6373 RANCHO SAN DIEGO	
43-402-029	BAEZ KARLA M FAMILY TRUST 01-12-96	6385 RANCHO SAN DIEGO	
43-402-029	BARKHODAE PAUL P LIVING TRUST 11-13-08	6385 RANCHO SAN DIEGO	
43-402-029	BERTRAND BRADLEY	6367 RANCHO SAN DIEGO	
43-402-029	BRACKEN DANIEL J	6371 RANCHO SAN DIEGO	
43-402-029	BURGESS STEVEN P & JOSEFA NETA	6385 RANCHO SAN DIEGO	
43-402-029	CAMPBELL THOMAS F	6365 RANCHO SAN DIEGO	
43-402-029	CHANDLER GERI	42640 25TH ST LANCASTER	
43-402-029	COLLINS RICHARD M II FAMILY TRUST 06-14-07	6371 RANCHO SAN DIEGO	
43-402-029	CONCEPCION GRACE	6385 RANCHO SAN DIEGO	
43-402-029	FARRELL JEAN C	6377 RANCHO SAN DIEGO	
43-402-029	FERNANDEZ JENNIFER L	5555 LAKE MU LA MESA	
43-402-029	FOSTER HOLLY J	550 W 54TH ST NEW YORK	
43-402-029	FRANK CHRISTOPHER S	6381 RANCHO SAN DIEGO	
43-402-029	FUNK JEFFREY R 2011 TRUST 04-28-11	7420 TEASDAL SAN DIEGO	
43-402-029	GARON ROBIN M	6371 RANCHO SAN DIEGO	
43-402-029	GARRIDO FAMILY TRUST	10623 PORTOE SAN DIEGO	
43-402-029	GORDON FAMILY TRUST	11477 BOOTES SAN DIEGO	
43-402-029	GOVARI MEHDI & ZOHORYAN RAMESH	6371 RANCHO SAN DIEGO	
43-402-029	GREER THOMAS D & CUBILLOS-GREER ADRIANA	6369 RANCHO SAN DIEGO	
43-402-029	GUINTO JENNIFER	6379 RANCHO SAN DIEGO	
43-402-029	HAGGAR FAMILY TRUST	10553 WHISPE SAN DIEGO	
43-402-029	HAILEY CHRISTOPHER	6385 RANCHO SAN DIEGO	
43-402-029	HAUG SHAIN G & MICHELLE R	6381 RANCHO SAN DIEGO	
43-402-029	HELMAN KRISTIN R	6369 RANCHO SAN DIEGO	
	HILL LLOYD & CAROL FAMILY TRUST A 10-07-91 C/O		
43-402-029	HILL HILL REALTY	7290 NAVAJO I SAN DIEGO	
43-402-029	HULL THOMAS K III & BUTLER GINGER G	6377 RANCHO SAN DIEGO	
43-402-029	J Z PARADISE LLC	2801 W CANYC SAN DIEGO	
43-402-029	JEFFERSON WILLIAM	6371 RANCHO SAN DIEGO	
43-402-029	KARAGOZIAN KAREN L 2010 TRUST	3891 CRESTSTC SAN DIEGO	
43-402-029	KELVINGTON BRADY L	6365 RANCHO SAN DIEGO	
43-402-029	LANKAMP MARY M	40228 BENWO TEMECULA	
43-402-029	LAWRENCE KIRK M	13681 CONNEF FISHERS	
43-402-029	LEHNHARDT FAMILY 2007 TRUST 08-06-07	2014 FAIRWAY HOLTVILLE	
43-402-029	LIN MARK C	6373 RANCHO SAN DIEGO	
43-402-029	M & L PROPERTIES 1 TRUST	2658 DEL MAR DEL MAR	
43-402-029	MARTIN RONALD L	6381 RANCHO SAN DIEGO	
43-402-029	MONROE BRADFORD R & BOTZ ANNA T	6371 RANCHO SAN DIEGO	
43-402-029	MOUNTS KENNETH S & CIUFFREDA MARCELLINE A	7936 LAKE CAY SAN DIEGO	
43-402-029	MUELLER ARNO & MARIE TRUST 03-27-06	18412 DEERHC JAMUL	
43-402-029	OCCUPANT	6365 RANCHO SAN DIEGO	
43-402-029	OCCUPANT	6365 RANCHO SAN DIEGO	
43-402-029	OCCUPANT	6365 RANCHO SAN DIEGO	

43-402-029 WHITE STEPHEN P	101 W BROAD SAN DIEGO
43-402-029 WOODS FAMILY TRUST 04-26-91	6369 RANCHO SAN DIEGO
43-402-029 YOUNG PETER C & GRACIE L	2840 FLETCHER EL CAJON
43-402-030 AKAMINE JOEL	6389 RANCHO SAN DIEGO
43-402-030 ANDERSON WILLIAM P	6395 RANCHO SAN DIEGO
43-402-030 ARELLANO SALVADOR	6391 RANCHO SAN DIEGO
43-402-030 BOURQUIN GARY	6395 RANCHO SAN DIEGO
43-402-030 BRAHAM BRITT R	6389 RANCHO SAN DIEGO
43-402-030 BROWNWELL GARY	2452 DEERPAR SAN DIEGO
43-402-030 CHUNG NAKKU & POOLE EMILY C	6397 RANCHO SAN DIEGO
43-402-030 COOKSEY NANCY M TRUST 06-12-14	6395 RANCHO SAN DIEGO
43-402-030 DOWN UNDER USD LLC	P O BOX 2869 JACKSON
43-402-030 EYMAN NATALIE R Y	2862 W CANYON SAN DIEGO
43-402-030 FRIEDEL FAMILY TRUST	6389 RANCHO SAN DIEGO
43-402-030 GARCIA JAIME G II & BACKSTROM FRANKLIN F	6391 RANCHO SAN DIEGO
43-402-030 GATHWRIGHT IVA D	6395 RANCHO SAN DIEGO
43-402-030 GERACE JAMES S	1220 ROSECRA SAN DIEGO
43-402-030 GUICO HENRY T F & VIVIEN	6389 RANCHO SAN DIEGO
43-402-030 GUNST C TRUST 10-20-03	6397 RANCHO SAN DIEGO
43-402-030 HARPER FAMILY TRUST 10-20-11	5905 WAYMARK AUSTIN
43-402-030 HOLMEN ERIC C	6397 RANCHO SAN DIEGO
43-402-030 JIMENEZ JOSE	6391 RANCHO SAN DIEGO
43-402-030 KEYVANI ANOOSHEH	6395 RANCHO SAN DIEGO
43-402-030 KIMBLE BRENDA N	6399 RANCHO SAN DIEGO
43-402-030 LEMAICH RAMSEY	6395 RANCHO SAN DIEGO
43-402-030 MAFNAS JANICE R	6389 RANCHO SAN DIEGO
43-402-030 MAMER PATRICK J	6393 RANCHO SAN DIEGO
43-402-030 MASIKAT JEROME	6397 RANCHO SAN DIEGO
43-402-030 NEASE ELSIE J REVOCABLE TRUST 05-18-09	6395 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6387 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6389 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6391 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6391 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6391 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6391 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6393 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6395 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6395 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6395 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6395 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6395 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6397 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6397 RANCHO SAN DIEGO
43-402-030 OCCUPANT	6399 RANCHO SAN DIEGO
43-402-030 OMAR BASSAM & ETEFAGH MARYAM TRS	1562 COPA DE LA JOLLA
43-402-030 PALOS MARTIN & RUTH H	6389 RANCHO SAN DIEGO
43-402-030 ROGERS LARRY E & SCHMIDT LEOTA E	6395 RANCHO SAN DIEGO
43-402-030 SCHUMACHER PETER J	5642 MEREDIT SAN DIEGO

43-402-030 SHATILA HANI & MARILYN TRS	11580 CORTE F SAN DIEGO
43-402-030 SHIPMAN ARON	6395 RANCHO SAN DIEGO
43-402-030 SIMONS GREGORY D	6391 RANCHO SAN DIEGO
43-402-030 SPRADLIN MARY K	6395 RANCHO SAN DIEGO
43-402-030 TAN NELSON	6395 RANCHO SAN DIEGO
43-402-030 THOMPSON ALEXIS E	6395 RANCHO SAN DIEGO
43-402-030 THRONEBERRY GRAHAM & BRIDGET	6395 RANCHO SAN DIEGO
43-402-030 TRETTEL IAN A & ONSTOTT APRIL	6395 RANCHO SAN DIEGO
43-402-030 TROXIL CHRISTOPHER S & VARGAS EMILY D	6387 RANCHO SAN DIEGO
WEBER RAYMOND C REVOCABLE INTER VIVOS TRUST	
43-402-030 07-02-97	6387 RANCHO SAN DIEGO
43-402-030 YIN SIDNEY S	6397 RANCHO SAN DIEGO
43-404-044 OCCUPANT	10818 SAN DIE SAN DIEGO
43-404-044 ROMAN CATHOLIC BISHOP OF SAN DIEGO	P O BOX 85728 SAN DIEGO
43-404-045 NAZARETH HOUSE OF SAN DIEGO INC	10728 SAN DIE SAN DIEGO
43-404-045 OCCUPANT	6331 RANCHO SAN DIEGO
43-404-108 AGID LAWRENCE/OCCUPANT	5930 CAMINITI SAN DIEGO
43-404-108 AMMI SHAHRIAR FAMILY 2006 TRUST 05-17-06	5974 CAMINITI SAN DIEGO
43-404-108 ANDREWS MICHAEL B & KARINE LIVING TRUST	10780 CAMINI SAN DIEGO
43-404-108 ARJONA LOURDES R	5978 CAMINITI SAN DIEGO
43-404-108 BIRD FAMILY TRUST	10793 CAMINI SAN DIEGO
43-404-108 BOYLE GARY D	9932 PROSPEC SANTEE
43-404-108 BUGGS JOSEPH/OCCUPANT	5966 CAMINITI SAN DIEGO
CALIFORNIA CONDO IRREVOCABLE 2007 TRUST 03-02-	
43-404-108 07	8019 WARWIC UNIVERSITY PK
43-404-108 CAMERON LIVING TRUST	10708 CAMINI SAN DIEGO
43-404-108 CORRAL FLORINDA S REVOCABLE TRUST	10765 CAMINI SAN DIEGO
43-404-108 DIAZ TRINIDAD	10791 CAMINI SAN DIEGO
43-404-108 DODGE FAMILY TRUST 01-15-01	6027 POPPY ST LA MESA
43-404-108 DUBIEL MICHAEL F	10785 CAMINI SAN DIEGO
43-404-108 ELASSAL FAMILY TRUST 03-31-87	5923 CAMINITI SAN DIEGO
43-404-108 ELSASSER MICHAEL C & DILLON TONI	5929 CAMINITI SAN DIEGO
43-404-108 ELWART CLIFFORD REVOCABLE TRUST	10784 CAMINI SAN DIEGO
43-404-108 FANNING BRIDGET R	4925 JUNEBER SAN DIEGO
43-404-108 FINKOWSKI ARLA A	6741 BIRCHWC SAN DIEGO
43-404-108 FULLER SANDRA L	10716 CAMINI SAN DIEGO
43-404-108 GILE BRIAN	6553 HILLGRO SAN DIEGO
43-404-108 GILES MARLENE J TRUST 06-30-11	5956 CAMINITI SAN DIEGO
43-404-108 GREEN SUN WAVE CORP	301 E FOOTHIL ARCADIA
43-404-108 GUILLORY MATTHEW A FAMILY TRUST	10775 CAMINI SAN DIEGO
43-404-108 HALIM JOKOSETIO & RINCON DANIELLE M	10796 CAMINI SAN DIEGO
43-404-108 HAMPSON NANCY B	10776 CAMINI SAN DIEGO
43-404-108 JIMENEZ MARICEL	5217 TOPSIDE SAN DIEGO
43-404-108 JONES KATHLEEN MURPHY FAMILY TRUST 06-09-04	2855 LA CASIT LAS VEGAS
43-404-108 KAHARA CHAN & MAYUKO	12942 CARMEI SAN DIEGO
43-404-108 KATANANI KAMAL A	10771 CAMINI SAN DIEGO

43-404-108 KELLEY BETTY L TRUST 02-01-13	5952 CAMINITI SAN DIEGO
43-404-108 KUZIELA THADDEUS J	4234 TOCH ST SAN DIEGO
43-404-108 LASUGA (PTNRSP)	BORSARI/LASU CARLSBAD
43-404-108 LASUGA (PTNRSP) C/O GAY BORSARI LASUGA	2017 MESQUIT CARLSBAD
43-404-108 LUNA GRANT B	10795 CAMINI SAN DIEGO
43-404-108 MAGNESS JACOB B	10783 CAMINI SAN DIEGO
43-404-108 MARDESICH LYN TRUST 06-08-07	9637 RANCHO ESCONDIDO
43-404-108 MATTUS WILLIAM J	38091 STONE I MURRIETA
43-404-108 MCCARTHY JEFFREY S & NINA V	10724 CAMINI SAN DIEGO
MCNAUGHTON MICHAEL & SHERRIE FAMILY TRUST 05-	
43-404-108 29-02	650 COLUMBI SAN DIEGO
43-404-108 MURPHY ANDREW & NICOLE	5937 CAMINITI SAN DIEGO
43-404-108 MURRAY FAMILY TRUST 03-02-98	6129 WOLFST SAN DIEGO
43-404-108 NARES/MCPHERSON FAMILY TRUST 04-10-06	5010 HASTING SAN DIEGO
43-404-108 OBERLANDER KIRK G	10736 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10732 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10740 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10744 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10748 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10752 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10760 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10761 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10767 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10768 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10773 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10777 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10781 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10788 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10792 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10796 CAMINI SAN DIEGO
43-404-108 OCCUPANT	10797 CAMINI SAN DIEGO
43-404-108 OCCUPANT	5915 CAMINITI SAN DIEGO
43-404-108 OCCUPANT	5938 CAMINITI SAN DIEGO
43-404-108 OCCUPANT	5941 CAMINITI SAN DIEGO
43-404-108 OCCUPANT	5942 CAMINITI SAN DIEGO
43-404-108 OCCUPANT	5960 CAMINITI SAN DIEGO
43-404-108 PEDERSEN MARK & ASHLEY E M	10720 CAMINI SAN DIEGO
43-404-108 PULSIFER JAMES L	10728 CAMINI SAN DIEGO
43-404-108 SCRIBNER MILES B & ANNE	6939 CORDWC BOULDER
43-404-108 SEVICK CARTER & MYRNA	6956 S EATON AURORA
43-404-108 SOUZA MICHAEL D & MICHELLE H	10787 CAMINI SAN DIEGO
43-404-108 STIEHL FAMILY TRUST	10756 CAMINI SAN DIEGO
43-404-108 TORRES CRYSTAL L TRUST 05-19-11	1253 ALTA VIS VISTA
UGARTE FRANCISCO & CAMACHO SILVIA REVOCABLE	
43-404-108 TRUST 08-05-14	5919 CAMINITI SAN DIEGO
43-404-108 VALDEZ ROGELIO H & BERNARDINA E	1216 PASEO C/ CALEXICO
43-404-108 VIRISSIMO JOHN J	5851 TULANE S SAN DIEGO

43-404-108 WALLACE BETSY A	5934 CAMINITO SAN DIEGO
43-404-108 WALLS SUSAN	211 COUNTRY SAN MARCOS
43-404-108 WONG FAMILY TRUST	10610 LOIRE A SAN DIEGO
43-404-108 WOOLSEY BRIAN R & KAREN K	10772 CAMINI' SAN DIEGO
43-404-108 YUCATAN SMOOGINN LLC C/O JAMES L SMOOGEN	12312 KINGSPI SAN DIEGO
43-404-108 ZEICHICK DAVID R & KELLY Q	311 LEGION AV CHICO
43-404-108 ZICHITTELLA RICHARD G	10 WAILEA EKKIHEI
45-830-003 DENTON EDMON TESTAMENTARY TRUST	2223 AVENIDA LA JOLLA
45-830-004 DENTON EDMON TESTAMENTARY TRUST	2223 AVENIDA LA JOLLA
45-830-004 OCCUPANT	6216 FAIRMOL SAN DIEGO
45-830-014 DENTON EDMON TESTAMENTARY TRUST	2223 AVENIDA LA JOLLA
45-830-015 DENTON EDMON TESTAMENTARY TRUST	2223 AVENIDA LA JOLLA
DENTON EDMON TESTAMENTARY TRUST C/O W NEAL	
45-830-016 SCHRAM	2223 AVENIDA LA JOLLA
45-834-209 G I S ESTATE TRUST 02-12-09	2821 SANTA FE ENCINITAS
45-834-209 OCCUPANT	6410 RIVERDAI SAN DIEGO
45-834-210 17560 WILD HORSE CREEK LLC	P O BOX 2198 MEMPHIS
45-834-210 OCCUPANT	6424 MISSION SAN DIEGO
45-834-211 LARIAT LAND LLC	700 COLORADO DENVER
45-834-211 OCCUPANT	10445 FRIARS I SAN DIEGO
45-834-212 LARIAT LAND LLC	700 COLORADO DENVER
MORGAN KENNETH E REVOCABLE FAMILY TRUST 07-	
45-834-215 17-96 C/O NATIONAL ELECTRIC WORKS INC	4440 RAINIER / SAN DIEGO
45-834-220 OCCUPANT	6404 MISSION SAN DIEGO
45-834-220 ORKIN INC	THRIFTY OIL CC SANTA FE SPRINGS
MORGAN KENNETH E REVOCABLE FAMILY TRUST 07-	
45-834-221 17-96 C/O NATIONAL ELECTRIC WORKS INC	4440 RAINIER / SAN DIEGO
45-834-223 O E C PROPERTY LLC C/O GATEWAY PROP MGMT LLC	9988 HIBERT S' SAN DIEGO
45-834-223 OCCUPANT	10433 FRIARS I SAN DIEGO
45-834-224 PETRARCA FAMILY TRUST / OCCUPANT	4420 RAINIER / SAN DIEGO
45-834-301 MISSION GORGE PROPERTIES LLC	7830 LA MESA LA MESA
45-834-301 OCCUPANT	6435 MISSION SAN DIEGO
45-834-302 MISSION GORGE PROPERTIES LLC C/O GEORGE T FELIX	7830 LA MESA LA MESA
45-834-327 KAISER FOUNDATION HOSPITALS	393 E WALNUT PASADENA
45-834-327 OCCUPANT	4647 ZION AVE SAN DIEGO
45-834-328 M G INVESTORS LLC	P O BOX 50082 SAN DIEGO
45-834-328 OCCUPANT	6401 MISSION SAN DIEGO
DENTON EDMON TESTAMENTARY TRUST C/O W NEAL	
45-851-001 SCHRAM	2223 AVENIDA LA JOLLA
45-851-001 OCCUPANT	6225 FAIRMOL SAN DIEGO
DENTON EDMON TESTAMENTARY TRUST C/O W NEAL	
45-851-003 SCHRAM	2223 AVENIDA LA JOLLA
45-851-003 OCCUPANT	6225 FAIRMOL SAN DIEGO

DENTON TESTAMENTARY TRUST C/O W NEAL	
45-851-004	SCHRAM 2223 AVENIDA LA JOLLA
45-851-004	OCCUPANT 4336 SHERIDAI SAN DIEGO
DENTON EDMON TESTAMENTARY TRUST C/O W NEAL	
45-851-005	SCHRAM 2223 AVENIDA LA JOLLA
45-851-005	OCCUPANT 4340 SHERIDAI SAN DIEGO
45-851-011	OCCUPANT 4337 SHERIDAI SAN DIEGO
45-851-011	PIETRAVALLE NICOLA 4337 SHERIDAI SAN DIEGO
45-851-012	MARK I LP 4626 30TH ST SAN DIEGO
45-851-012	OCCUPANT 4317 SHERIDAI SAN DIEGO
45-851-014	OCCUPANT 6215 FAIRMOL SAN DIEGO
45-851-014	PUTNAM FAMILY SURVIVORS TRUST 37361 MARX R RANCHO MIRAGE
C K RIVERDALE INVESTMENT LLC C/O CHRISTOPHER L	
45-851-018	EDDY 550 FRONT ST SAN DIEGO
45-851-018	OCCUPANT 6302 RIVERDAI SAN DIEGO
45-851-026	I D Y L L VENTURES LLC 4340 VANDEVE SAN DIEGO
45-851-027	IVY EDWARD J DESCENDANTS TRUST C/O JERRY IVY SR 450 FERGUSON MOUNTAIN VIEW
45-851-027	OCCUPANT 4388 VANDEVE SAN DIEGO
45-851-028	I D Y L L VENTURES LLC OR OCCUPANT 4340 VANDEVE SAN DIEGO
45-851-029	KROOSKOS TULA C TR 5815 OVERLAK SAN DIEGO
45-851-029	OCCUPANT 4320 VANDEVE SAN DIEGO
45-851-030	OCCUPANT 6205 FAIRMOL SAN DIEGO
45-851-030	PUTNAM FAMILY SURVIVORS TRUST 37361 MARX R RANCHO MIRAGE
45-851-032	H K B G LLC 5598 CAMINITI LA JOLLA
45-851-032	OCCUPANT 6280 RIVERDAI SAN DIEGO
45-851-033	H K B G LLC 5598 CAMINITI LA JOLLA
45-851-033	OCCUPANT 6260 RIVERDAI SAN DIEGO
45-852-103	OCCUPANT 6322 MISSION SAN DIEGO
45-852-103	SAATHOFF RONALD L 4450 GLACIER SAN DIEGO
45-852-111	LIBBY FAMILY PARTNERS 6789 BONNIE SAN DIEGO
45-852-111	OCCUPANT 4452 GLACIER SAN DIEGO
45-852-112	OCCUPANT 4440 GLACIER SAN DIEGO
45-852-112	ZARRABI ARDESHIR & GANJI SHOHREH 11527 TRAILBF SAN DIEGO
45-852-115	OCCUPANT 6314 MISSION SAN DIEGO
WILSON MARK & ELIZABETH FAMILY TRUST 11-01-07	
45-852-115	C/O MARK WILSON 2772 ANJULI C EL CAJON
45-852-117	MCKINLEY RICHARD V & PATRICIA J TRS 1176 BROWN /LAFAYETTE
45-852-117	OCCUPANT 6333 RIVERDAI SAN DIEGO
45-852-121	FRANKEL MARILYN M TRUST B 11-14-86 1749 LA VALH/ EL CAJON
45-852-121	OCCUPANT 4410 GLACIER SAN DIEGO
45-852-122	OCCUPANT 4422 GLACIER SAN DIEGO
45-852-122	WOOD-WALL TRUST 01-30-90 P O BOX 160 SANTA YSABEL
45-852-123	BOGZARAN HATEF LIVING TRUST 11-05-07 6970 MOHAWI SAN DIEGO
45-852-123	OCCUPANT 4428 GLACIER SAN DIEGO
45-852-125	MCKINLEY RICHARD V & PATRICIA J TRS 1176 BROWN /LAFAYETTE
45-852-126	BROWN BRADLEY 5015 SANTA CF SAN DIEGO

45-852-126 OCCUPANT	4417 RAINIER / SAN DIEGO
45-852-127 CORINTHIAN MEDIA INC	P O BOX 8743 RANCHO SANTA FE
45-852-127 OCCUPANT	4427 RAINIER / SAN DIEGO
MCDONALDS CORP <DBA DELAWARE MCDONALDS	
45-852-128 CORP> C/O PAUL SCHMID	485 E CARMEL SAN MARCOS
CASSU INVESTMENT GROUP LTD THE C/O PAUL	
45-852-129 SCHMID	485 E CARMEL SAN MARCOS
45-852-129 OCCUPANT	6326 MISSION SAN DIEGO
45-852-130 JACKSON CLAUDIA M REVOCABLE TRUST 12-27-05	570 ABERDEEN INVERNESS
45-852-130 OCCUPANT	6305 RIVERDAI SAN DIEGO
45-852-202 JAROSIN TRUST B 11-09-82	8857 GLENHAV SAN DIEGO
45-852-202 OCCUPANT	4417 GLACIER . SAN DIEGO
CENTRAL INVESTMENTS OF SAN DIEGO LLC /	
45-852-203 OCCUPANT	4421 GLACIER . SAN DIEGO
45-852-204 CENTRAL INVESTMENTS OF SAN DIEGO LLC	4421 GLACIER . SAN DIEGO
45-852-204 OCCUPANT	4435 GLACIER . SAN DIEGO
45-852-205 MISSION GORGE ENTERPRISES	6240 MISSION SAN DIEGO
45-852-205 OCCUPANT	4445 GLACIER . SAN DIEGO
45-852-206 MISSION GORGE ENTERPRISES	6240 MISSION SAN DIEGO
45-852-206 OCCUPANT	4447 GLACIER . SAN DIEGO
45-852-207 MISSION GORGE ENTERPRISES LLC	6240 MISSION SAN DIEGO
45-852-207 OCCUPANT	4461 GLACIER . SAN DIEGO
45-852-209 JOHNSON FAMILY TRUST	130 VIA DE LA ` SOLANA BEACH
45-852-209 OCCUPANT	6218 MISSION SAN DIEGO
45-852-211 JOHNSON FAMILY TRUST	130 VIA DE LA ` SOLANA BEACH
45-852-214 MISSION GORGE ENTERPRISES LLC	6240 MISSION SAN DIEGO
45-852-214 OCCUPANT	6230 MISSION SAN DIEGO
45-852-217 OCCUPANT	4411 GLACIER . SAN DIEGO
ROUNTREE ANNETTE M TR C/O MRS ANNETTE M	
45-852-217 ROUNTREE	6004 CAMINITI SAN DIEGO
45-852-218 OCCUPANT	4430 VANDEVE SAN DIEGO
45-852-218 SCHWERMA JAMES R LIVING TRUST 01-05-94	5150 MARLBOI SAN DIEGO
KAISER FOUNDATION HOSPITALS C/O KAISER	
45-852-219 FOUNDATION HEALTH PLAN	393 W WALNU PASADENA
45-852-219 OCCUPANT	4402 VANDEVE SAN DIEGO
45-852-220 OCCUPANT	4438 VANDEVE SAN DIEGO
45-852-220 PACIFIC ENTERPRISES LLC	17215 GOLDEN SAN DIEGO
45-852-223 DAISON LLC	4120 30TH ST # SAN DIEGO
45-852-223 OCCUPANT	4456 VANDEVE SAN DIEGO
45-852-224 NAISMITH FAMILY REVOCABLE TRUST 04-06-93	14679 CARMEL SAN DIEGO
45-852-224 OCCUPANT	6202 MISSION SAN DIEGO
45-853-102 DINAN CHRISTINA	26033 MANZA MURRIETA
45-853-102 OCCUPANT	6333 MISSION SAN DIEGO
45-853-121 DINAN CHRISTINA	26033 MANZA MURRIETA
45-853-121 OCCUPANT	6323 MISSION SAN DIEGO
45-853-122 DEBERRY JERRY & NANCY LIVING TRUST 12-03-02	1403 BURRIS D EL CAJON

45-853-220	GEEDING KRIS L / OCCUPANT	4530 VANDEV	SAN DIEGO
45-853-220	GUPTA ANUJ	2401 E DIVISIO	NATIONAL CITY
45-853-220	JACKEL DONALD & SANDRA TRS	6009 MADRA F	SAN DIEGO
45-853-220	JACKEL DONALD & SANDRA TRS	6009 MADRA F	SAN DIEGO
45-853-220	JAVELOSA ELISEO R & SUSANA R	1909 BASSETT	SANTEE
45-853-220	JIMENEZ JESUS E	4540 VANDEV	SAN DIEGO
45-853-220	MOVIUS EDWARD G	29 BEANVOIR	(ROCKVILLE
45-853-220	OCCUPANT	4540 VANDEV	SAN DIEGO
45-853-220	OCCUPANT	4540 VANDEV	SAN DIEGO
45-853-220	OCCUPANT	4540 VANDEV	SAN DIEGO
45-853-220	OCCUPANT	4540 VANDEV	SAN DIEGO
45-853-220	OCCUPANT	4540 VANDEV	SAN DIEGO
45-853-220	OCCUPANT	4540 VANDEV	SAN DIEGO
45-853-220	OCCUPANT	4540 VANDEV	SAN DIEGO
45-853-220	OCCUPANT	4540 VANDEV	SAN DIEGO
45-853-220	OCCUPANT	4540 VANDEV	SAN DIEGO
45-853-220	SHRESTHA RAJEEV	5841 N ROCKI	MC CORDSVILLE
45-853-220	VENABLE CAROL F TRUST 07-17-00	2400 6TH AVE	SAN DIEGO
45-853-220	WALLS LORRAINE L & RANDAL B FAMILY TRUST	1455 HARBISO	EL CAJON
45-853-220	WALLS LORRAINE L & RANDAL B FAMILY TRUST	1455 HARBISO	EL CAJON
45-870-004	OCCUPANT	6501 MISSION	SAN DIEGO
	R & H INVESTMENT ASSOCIATES / ZION CORNER LLC		
45-870-004	C/O REFF REAL ESTATE SERVICES	517 4TH AVE #	SAN DIEGO
45-870-007	OCCUPANT	6511 MISSION	SAN DIEGO
	R & H INVESTMENT ASSOCIATES / ZION CORNER LLC		
45-870-007	C/O REFF REAL ESTATE SERVICES	517 4TH AVE #	SAN DIEGO
45-870-010	FRIARS LLC C/O STEPSTONE REAL ESTATE SVCS	2750 WOMBLE	SAN DIEGO
45-870-010	OCCUPANT	10450 FRIARS I	SAN DIEGO
45-870-011	FRIARS LLC C/O STEPSTONE REAL ESTATE SVCS	2750 WOMBLE	SAN DIEGO
45-870-011	OCCUPANT	10460 FRIARS I	SAN DIEGO
45-870-012	FRIARS LLC	1500 STATE ST	SAN DIEGO
45-870-012	OCCUPANT	10410 FRIARS I	SAN DIEGO
45-870-013	FERRARI FAMILY LAND TRUST	10067 VALLE C	EL CAJON
45-870-013	OCCUPANT	10430 FRIARS I	SAN DIEGO
	PECKHAM PROPERTIES INC / PECKHAM PROPERTIES		
45-872-002	INC ET AL	401 W A ST #2:	SAN DIEGO
45-872-003	PECKHAM PROPERTIES INC C/O MICHAEL PECKHAM	401 W A ST #2:	SAN DIEGO
	C K RIVERDALE INVESTMENT LLC C/O CHRISTOPHER L		
45-872-007	EDDY	550 FRONT ST	SAN DIEGO
45-872-007	OCCUPANT	6320 RIVERDAI	SAN DIEGO
	FRIARS-RIVERDALE LTD / HODGE EDWARD M		
	SEPARATE PROPERTY TRUST C/O PACIFIC COAST		
45-872-011	COMMERCIAL	P O BOX 42095	SAN DIEGO
45-872-011	OCCUPANT	10383 FRIARS I	SAN DIEGO
45-872-014	OCCUPANT	10320 FRIARS I	SAN DIEGO
45-872-014	PECKHAM PROPERTIES INC /	401 W A ST #2:	SAN DIEGO
45-872-015	OCCUPANT	10320 FRIARS I	SAN DIEGO

PECKHAM PROPERTIES INC(SUBLEASE:SAGA

45-872-015 ENTERPRISES INC / ET AL	10067 VALLE C EL CAJON
45-872-016 PECKHAM PROPERTIES INC /	401 W A ST #2: SAN DIEGO
46-102-103 ARNOLD LEE R 2013 TRUST	9319 VISTA DR SPRING VALLEY
46-102-103 OCCUPANT	6082 WANDA (SAN DIEGO
46-102-104 FINKOWSKI ARLA A	6076 WANDA (SAN DIEGO
46-102-104 OCCUPANT	6076 WANDA (SAN DIEGO
46-102-105 SCHINDLER FAMILY TRUST 02-12-03	6070 WANDA (SAN DIEGO
46-102-106 TSEGAI HILINA	6062 WANDA (SAN DIEGO
46-102-107 GUARIAN KIRK A & SHLYN	6056 WANDA (SAN DIEGO
46-102-108 GROUT FAMILY TRUST 07-27-87	5167 HILDA RD SAN DIEGO
46-102-108 OCCUPANT	6050 WANDA (SAN DIEGO
46-102-109 BUTLER FRANK A & TINA M	6057 DELOR C1 SAN DIEGO
46-102-110 SUCHAR SURVIVORS 2002 TRUST 09-10-02	6063 DELOR C1 SAN DIEGO
46-102-111 CRULL MICHAEL R & ALCINA A	1836 MARLINE EL CAJON
46-102-111 OCCUPANT	6069 DELOR C1 SAN DIEGO
46-102-112 TOURTELLOTT MICHAEL	6077 DELOR C1 SAN DIEGO
46-102-113 ERICKSON MARGA M FAMILY TRUST	6083 DELOR C1 SAN DIEGO
46-102-118 GUICE SHARON J	6076 CRAWFO SAN DIEGO
46-102-118 OCCUPANT	6076 CRAWFO SAN DIEGO
46-102-119 CONNIRY WILLIAM J JR & MILDRED A	6066 CRAWFO SAN DIEGO
46-102-120 RUDAT KARL	6058 CRAWFO SAN DIEGO
46-102-123 ABRAHAM GEORGE & BEHER AZEB TRUST	11175 BRECKE SAN DIEGO
46-102-124 ABRAHAM GEORGE & BEHER AZEB TRUST	11175 BRECKE SAN DIEGO
46-102-124 OCCUPANT	6050 CRAWFO SAN DIEGO
46-102-202 BEHLMAN INTERVIVOS TRUST 06-01-92	6085 WANDA (SAN DIEGO
46-102-203 NINO RANDALL & JENNIFER	13287 TREECRI POWAY
46-102-203 OCCUPANT	6053 WANDA (SAN DIEGO
46-102-204 OCCUPANT	6054 DELOR C1 SAN DIEGO
STADIUM PARK EAST ASSOCIATION INC C/O	
46-102-204 TERRENCE R CASTER	6805 MORRIS ^ CLOQUET
46-102-205 KLOEPFER TERRY L	6086 DELOR C1 SAN DIEGO
46-102-205 OCCUPANT	6086 DELOR C1 SAN DIEGO
46-103-003 ATOMIC INVESTMENTS INC	3200 HIGHLAN NATIONAL CITY
46-103-003 OCCUPANT	6155 MISSION SAN DIEGO
46-103-004 HENDRICKSON JOHN & DOLPHINE TRUST 06-17-93	6154 DECENA SAN DIEGO
46-103-019 AMBROSIA JON E JR & SANDRA A	8676 GARDEN/ LAKESIDE
46-103-019 BLIN ALFRED B & MARY H B	4560 TWAIN A' SAN DIEGO
46-103-019 BROOKS JOHN C	11360 PORTOE SAN DIEGO
46-103-019 CONSTON BRYAN	4560 TWAIN A' SAN DIEGO
46-103-019 GIOFFRE PAUL	4562 TWAIN A' SAN DIEGO
46-103-019 LOU H S FAMILY TRUST 07-19-02	8544 CLIFFORC SANTEE
46-103-019 LOU YUK CHIU & ZHOU WEI	7656 MONA L SAN DIEGO
46-103-019 LOU YUK CHIU & ZHOU WEI	7656 MONA L SAN DIEGO
46-103-019 LOU YUK CHIU & ZHOU WEI	7656 MONA L SAN DIEGO
46-103-019 MCLAURIN MELINA	1322 SAN BERI SPRING VALLEY

46-103-019 MOSIN JAYME	2125 WESTING SAN DIEGO
46-103-019 OCCUPANT	4560 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4560 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4560 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4560 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4560 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4560 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4562 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4562 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4562 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4562 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4562 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4562 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4562 TWAIN A' SAN DIEGO
46-103-019 OCCUPANT	4562 TWAIN A' SAN DIEGO
46-103-019 RUNYEN JANELLE	10154 PRINCE'S SANTEE
46-103-019 WORM REVOCABLE TRUST 05-31-06	7595 JENNITE I SAN DIEGO
46-103-019 XIE WEILIN & LI PING	P O BOX 67635 RANCHO SANTA FE
46-103-020 OCCUPANT	6115 DECENA I SAN DIEGO
46-103-020 WORM REVOCABLE TRUST 05-31-06	6115 DECENA I SAN DIEGO
46-103-026 OCCUPANT	6115 MISSION SAN DIEGO
46-103-026 SADATRAFIEI RAHIM	2323 CALLE CC LA JOLLA
46-103-040 OCCUPANT	6101 MISSION SAN DIEGO
46-103-040 SADATRAFIEI RAHIM	2323 CALLE CC LA JOLLA
46-103-043 OCCUPANT	6171 MISSION SAN DIEGO
SIDNEY FAMILY LTD PARTNERSHIP C/O SHERRY S	
46-103-043 SIDNEY	915 W CRESCE PALM SPRINGS
46-103-045 ALAMILLO JULIE C	6120 DECENA I SAN DIEGO
46-103-045 BERCHMANZ ANTONY	5970-B MISSIO SAN DIEGO
46-103-045 BLACKWOOD ERIL V	6120 DECENA I SAN DIEGO
46-103-045 BOYLE TROY J	6120 DECENA I SAN DIEGO
46-103-045 BRONNENBURG DUANE A & MARSHA L	2341 TANAGEF PLEASANTON
46-103-045 CHENG HAOWEN	6120 DECENA I SAN DIEGO
46-103-045 COCKERILL TOSHIKO	6848 CAMINO SAN DIEGO
46-103-045 CORREIA TONY & MARIA	6120 DECENA I SAN DIEGO
DOVE COLIN & FLORENCE REVOCABLE 2001 TRUST 02-	
46-103-045 06-01	73342 BROKEN PALM DESERT
DOVE COLIN & FLORENCE REVOCABLE 2001 TRUST 02-	
46-103-045 06-01	73342 BROKEN PALM DESERT
46-103-045 ETTEFAGH MARJAN	8520 WESTMO SAN DIEGO
46-103-045 FANSLER FAMILY TRUST 02-07-90	1510 MARIA PI CORONADO
46-103-045 IWAHARA ERINA	6120 DECENA I SAN DIEGO
46-103-045 KOHLER SANDRA J	6120 DECENA I SAN DIEGO
46-103-045 LOGAN RONALD F	6120 DECENA I SAN DIEGO
46-103-045 MARQUEZ KENNETH & JUDITH	1765 SANTA AI COSTA MESA
46-103-045 MCCONNELL TERESA	6120 DECENA I SAN DIEGO
46-103-045 MOLLOY SCOTT C	3050 UDALL ST SAN DIEGO
46-103-045 MOLLOY SCOTT C	3050 UDALL ST SAN DIEGO

46-103-045 NUHAILY JALAL	P O BOX 2891 CHULA VISTA
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 OCCUPANT	6120 DECENA I SAN DIEGO
46-103-045 PETERSON STEVEN	6120 DECENA I SAN DIEGO
46-103-045 RICAUD SHANNON M	6120 DECENA I SAN DIEGO
46-103-045 SAFI YEHYA	2946 W CANYC SAN DIEGO
46-103-045 SANDERSON PAMELA REVOCABLE TRUST 10-30-13	6120 DECENA I SAN DIEGO
46-103-045 SCHWARTZ ADELE 2001 TRUST 11-07-01	7856 CAMINO SAN DIEGO
46-103-045 TAN CATHARINA	6120 DECENA I SAN DIEGO
46-103-045 VAISBERG DMITRI	11356 FAIRWII SAN DIEGO
46-103-045 VILLEGAS WENDY	6120 DECENA I SAN DIEGO
46-103-046 MALL JOHANN & MARTHA R	3110 SUMMIT ESCONDIDO
46-103-046 OCCUPANT	6104 DECENA I SAN DIEGO
46-103-047 MASHAYEKAN AHMAD & NEPTON	9850 GENESEE LA JOLLA
46-103-047 OCCUPANT	6131 MISSION SAN DIEGO
46-103-048 MASHAYEKAN AHMAD & NEPTON	9850 GENESEE LA JOLLA
46-103-048 OCCUPANT	6121 MISSION SAN DIEGO
46-115-010 H G F L P C/O H G FENTON CO	7577 MISSION SAN DIEGO
46-115-010 OCCUPANT	6190 FAIRMOL SAN DIEGO
46-115-011 H G F L P C/O H G FENTON CO	7577 MISSION SAN DIEGO
46-115-011 OCCUPANT	6180 FAIRMON SAN DIEGO
46-115-012 KAISER FOUNDATION HEALTH PLAN INC	393 E WALNUT PASADENA
46-115-012 OCCUPANT	10992 SAN DIE SAN DIEGO
46-115-013 KAISER FOUNDATION HEALTH PLAN INC	393 E WALNUT PASADENA
46-115-013 OCCUPANT	10990 SAN DIE SAN DIEGO
HOME DEPOT U S A INC / COLE HD SAN DIEGO CA L P	
46-115-021 C/O PROPERTY TAX DEPT 6634	P O BOX 10584 ATLANTA
46-115-021 OCCUPANT	5920 FAIRMOL SAN DIEGO
46-115-022 FENTON H G DEVELOPMENT CO LLC	7577 MISSION SAN DIEGO
46-115-022 OCCUPANT	5980 FAIRMOL SAN DIEGO
46-115-023 FENTON H G DEVELOPMENT CO LLC	7577 MISSION SAN DIEGO
46-115-023 OCCUPANT	10957 SAN DIE SAN DIEGO
46-115-024 FENTON H G DEVELOPMENT CO LLC	7577 MISSION SAN DIEGO
46-115-024 OCCUPANT	10981 SAN DIE SAN DIEGO
46-116-001 ELKHORN RANCH INC	P O BOX 633 RANCHO SANTA FE

46-116-001 OCCUPANT	6055 FAIRMOL SAN DIEGO
46-116-002 KELLER MICHAEL & ANNE	6041 FAIRMOL SAN DIEGO
46-116-002 OCCUPANT	6041 FAIRMOL SAN DIEGO
46-116-003 OCCUPANT	5841 FAIRMOL SAN DIEGO
46-116-003 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-116-004 OCCUPANT	6035 FAIRMOL SAN DIEGO
SCHOSSOW FRANK W JR & COLLEEN S TRUST B 09-19-	
46-116-004 77	2933 CHICAGO SAN DIEGO
46-116-005 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-116-006 OCCUPANT	4325 TWAIN A' SAN DIEGO
46-116-006 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-116-007 GREENVET PROPERTIES LLC	3440 TONY DR SAN DIEGO
46-116-007 OCCUPANT	4329 TWAIN A' SAN DIEGO
46-116-008 OCCUPANT	4341 TWAIN A' SAN DIEGO
46-116-008 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-116-009 OCCUPANT	4345 TWAIN A' SAN DIEGO
46-116-009 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-116-010 OCCUPANT	4385 TWAIN A' SAN DIEGO
46-116-010 SUDA DAVID H & DARLENE FAMILY 2009 TRUST	4385 TWAIN A' SAN DIEGO
46-116-015 KIRSCH ANDREA L FAMILY TRUST 06-16-98	1482 CHERRY C SAN JOSE
46-116-015 OCCUPANT	4375 TWAIN A' SAN DIEGO
46-116-020 OCCUPANT	4401 TWAIN A' SAN DIEGO
TWAIN CENTER C/O ARVCO REALTY C/O PHILIP A	
46-116-020 TERZICH	4655 CASS ST SAN DIEGO
46-117-003 CONANT PROPERTIES III L P	20322 SW ACA NEWPORT BEACH
46-117-005 OCCUPANT	5981 FAIRMOL SAN DIEGO
46-117-005 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-117-006 OCCUPANT	4345 TWAIN A' SAN DIEGO
46-117-006 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-117-007 OCCUPANT	4349 TWAIN A' SAN DIEGO
46-117-007 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-117-008 CONANT PROPERTIES III L P	20322 SW ACA NEWPORT BEACH
46-117-008 OCCUPANT	5910 MISSION SAN DIEGO
46-117-011 CONANT PROPERTIES III L P	20322 SW ACA NEWPORT BEACH
46-117-012 OCCUPANT	5975 FAIRMOL SAN DIEGO
46-117-012 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-117-013 OCCUPANT	5975 FAIRMOL SAN DIEGO
46-117-013 SECURED CAPITAL LTD PARTNERSHIP	5839 MISSION SAN DIEGO
46-117-014 CONANT PROPERTIES III L P	20322 SW ACA NEWPORT BEACH
46-117-015 CONANT PROPERTIES III L P	20322 SW ACA NEWPORT BEACH
46-118-004 FOZWYATT L P	185 SUSSEX PL CARSON CITY
46-118-004 OCCUPANT	4455 TWAIN A' SAN DIEGO
46-118-005 FOZWYATT L P	185 SUSSEX PL CARSON CITY
46-118-005 OCCUPANT	4455 TWAIN A' SAN DIEGO
46-118-006 FOZWYATT L P	185 SUSSEX PL CARSON CITY
46-118-006 OCCUPANT	6040 MISSION SAN DIEGO

BAREKATAIN FAMILY TRUST 05-05-97 C/O PACIFIC

46-118-007 COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-118-007 OCCUPANT	6050 MISSION SAN DIEGO
46-118-010 JACK IN THE BOX INC / HEROD PARTNERS LLC	LEGAL ESTATE SAN DIEGO
46-118-010 OCCUPANT	6080 MISSION SAN DIEGO
46-118-011 6070 MGR LLC C/O ROBERT GREENSTONE	6070 MISSION SAN DIEGO
46-118-011 OCCUPANT	6070 MISSION SAN DIEGO
46-118-012 A S P MISSION VALLEY LP / OCCUPANT	4437 TWAIN A' SAN DIEGO
46-119-004 EFS-MG LLC	3200 4TH AVE SAN DIEGO
46-119-004 OCCUPANT	5945 MISSION SAN DIEGO
46-119-005 CONANT PROPERTIES III L P	20322 SW ACA NEWPORT BEACH
46-119-006 CONANT PROPERTIES III L P	20322 SW ACA NEWPORT BEACH
46-119-008 GUPTA ASHOK K LIVING TRUST 04-21-99	5188 RENAISS/ SAN DIEGO
46-119-008 OCCUPANT	6008 MISSION SAN DIEGO
46-120-009 GREEN BARRY D TR	1560 SCOTT ST SAN DIEGO
46-120-009 OCCUPANT	4571 TWAIN A' SAN DIEGO
46-120-011 OCCUPANT	4573 TWAIN A' SAN DIEGO
46-120-011 STADIUM ARMS	4525 TWAIN A' SAN DIEGO
46-120-012 STADIUM ARMS	4525 TWAIN A' SAN DIEGO
46-120-013 BAHADOR AMIR SEPERATE PROPERTY TRUST 01-27-07	864 LORING ST SAN DIEGO
46-120-013 OCCUPANT	6035 MISSION SAN DIEGO
46-121-003 CALIFORNIA NEON PRODUCTS	4530 MISSION SAN DIEGO
46-121-003 OCCUPANT	4520 MISSION SAN DIEGO
46-121-004 CALIFORNIA NEON PRODUCTS	4530 MISSION SAN DIEGO
46-121-004 OCCUPANT	4550 MISSION SAN DIEGO
46-121-005 HALDEMAN A THOMAS	2937 TANAGEF LOS ANGELES
46-121-005 OCCUPANT	4551 MISSION SAN DIEGO
46-121-006 OCCUPANT	4533 MISSION SAN DIEGO
TEEMSMA DONALD & BARBARA FAMILY TRUST 04-14-	
46-121-006 95	5534 TRINITY V SAN DIEGO
MUIRLANDS INVESTMENTS LLC C/O ATOMIC	
46-121-007 INVESTMENTS	3200 HIGHLAN NATIONAL CITY
46-121-007 OCCUPANT	4525 MISSION SAN DIEGO
46-121-009 BAILEY LAWRENCE J TR C/O BRAD BAILEY	10035 PROSPE SANTEE
46-121-009 OCCUPANT	5995 MISSION SAN DIEGO
46-121-010 AHRENS CORP	5959 MISSION SAN DIEGO
46-121-010 AHRENS CORP	5959 MISSION SAN DIEGO
46-121-010 BRAY ROBERT L & TAKORVIAN DIANE TRUST 12-23-08	4743 NATALIE SAN DIEGO
46-121-010 BUTROS BASHAR E & DINA	997 CAMINITO CHULA VISTA
46-121-010 BUTROS BASHAR E & DINA	997 CAMINITO CHULA VISTA
46-121-010 ENGINEER FREDDY N	400 CYPRESS A SAN JOSE
46-121-010 HEDJIRAN NADER	5959 MISSION SAN DIEGO
46-121-010 MOORE JONATHAN B	6940 CAMINO SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO

46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 OCCUPANT	5959 MISSION SAN DIEGO
46-121-010 SAINE MARTHA C	4341 MT DAVIS SAN DIEGO
46-121-010 THORNBURGH DEFOREST C LIVING TRUST	4141 AMOROS SAN DIEGO
46-121-010 THORNBURGH DEFOREST C LIVING TRUST	4141 AMOROS SAN DIEGO
46-121-010 THORNBURGH DEFOREST C LIVING TRUST	4141 AMOROS SAN DIEGO
46-121-010 THORNBURGH DEFOREST C LIVING TRUST	4141 AMOROS SAN DIEGO
46-121-010 WILSON IRA III & CHRISTY C FAMILY TRUST 11-15-95	5959 MISSION SAN DIEGO
46-121-011 CALIFORNIA NEON PRODUCTS INC	4530 MISSION SAN DIEGO
46-121-011 OCCUPANT	6025 MISSION SAN DIEGO
46-121-012 GINOS CLARENCE W & MYRNA R	9912 OXFORD HIGHLAND
46-121-012 OCCUPANT	6011 MISSION SAN DIEGO
46-122-010 E & H INVESTMENTS OF CA LLC TWAIN SERIES	1001 AVENIDA SAN DIMAS
46-122-010 OCCUPANT	4408 TWAIN A' SAN DIEGO
MISSION VALLEY POST 3787 VETERANS OF FOREIGN	
46-122-011 WARS OF THE UNITED STATE	4370 TWAIN A' SAN DIEGO
46-122-012 ALESSIO LEASING CORP INC	P O BOX 3538 LA MESA
46-122-012 OCCUPANT	4354 TWAIN A' SAN DIEGO
46-122-015 G & GB TRUST 07-17-81	P O BOX 904 WHITEHALL
46-122-015 OCCUPANT	6127 FAIRMOL SAN DIEGO
46-122-016 EM INVESTMENTS LP	11976 TRAIL C SAN DIEGO
46-122-016 OCCUPANT	6121 FAIRMOL SAN DIEGO
46-122-017 G & GB TRUST 07-17-81	P O BOX 904 WHITEHALL
46-122-017 OCCUPANT	4322 TWAIN A' SAN DIEGO
46-122-018 G & GB TRUST 07-17-81	P O BOX 904 WHITEHALL
46-122-018 OCCUPANT	4304 TWAIN A' SAN DIEGO
46-122-026 KAISER FOUNDATION HOSPITALS	393 E WALNUT PASADENA
46-122-026 OCCUPANT	4405 VANDEVE SAN DIEGO
46-122-028 LE JOSEPH HAI & VU THUY THI BICH	3870 SACRAMI LA MESA
46-122-028 OCCUPANT	6140 MISSION SAN DIEGO
46-122-030 LA BREA APARTMENTS LLC	16130 VENTUR ENCINO
46-122-030 OCCUPANT	6110 MISSION SAN DIEGO
HOME SAVINGS OF AMERICA / LA BREA APARTMENTS	
46-122-032 LLC	16130 VENTUR ENCINO
46-122-032 OCCUPANT	4450 TWAIN A' SAN DIEGO
46-122-035 OCCUPANT	6136 MISSION SAN DIEGO

THE OFFICE & PROFESSIONAL EMPLOYEES	
46-122-035 INTERNATIONAL UNION LOCAL NO30 GUSTAFSON WAREHOUSE LLC C/O DONNA J	ATTN: BOOKKE SAN DIEGO
46-122-036 HOUSTON	4562 GARFIELD LA MESA
46-122-036 OCCUPANT	4307 VANDEVESAN SAN DIEGO
HOME SAVINGS OF AMERICA / LA BREA APARTMENTS	
46-122-042 LLC C/O INDUSTRY CONSULTING GROUP INC	P O BOX 1919 WICHITA FALLS
46-122-042 OCCUPANT	6116 MISSION SAN DIEGO
THE OFFICE & PROFESSIONAL EMPLOYEES	
46-122-043 INTERNATIONAL UNION LOCAL NO30	ATTN: BOOKKE SAN DIEGO
46-122-044 CORREA TRUST	1196 BROCKTC EL CAJON
46-122-044 OCCUPANT	6178 MISSION SAN DIEGO
MISSION CORPORATE CENTER LLC C/O PARMA MGMT	
46-122-045 CO INC	6390 GREENW SAN DIEGO
MISSION CORPORATE CENTER LLC C/O PARMA MGMT	
46-122-046 CO INC	6390 GREENW SAN DIEGO
46-122-046 OCCUPANT	6160 MISSION SAN DIEGO
MISSION CORPORATE INDUSTRIAL CENTER L P C/O	
46-122-047 PARMA MGMT CO INC	6390 GREENW SAN DIEGO
46-122-047 OCCUPANT	6152 MISSION SAN DIEGO
46-122-048 PARMA PROPERTY CO INC C/O PARMA MGMT CO INC	
MISSION CORPORATE INDUSTRIAL CENTER L P C/O	
46-122-049 PARMA PROPERTY COMPANY INC	6165 GREENW SAN DIEGO
46-122-049 OCCUPANT	6151 FAIRMOL SAN DIEGO
46-123-303 CUMMINGS GARY G & SARA FAMILY TRUST 04-01-93	
46-123-303 OCCUPANT	1954 OAK VIEV ALPINE
46-123-304 FREITAS SALVADOR & LUCILLE M 1996 TRUST	6071 HODSON SAN DIEGO
46-123-305 TERZICH FAMILY TRUST 05-31-13	6061 HODSON SAN DIEGO
46-123-403 OLVERA IRMA E TRUST 07-10-03	4770 ELSA RD SAN DIEGO
46-123-404 HARING TRUST	6073 MOHLER SAN DIEGO
46-123-405 PROFFER NORMA L TRUST OF 1996	6063 MOHLER SAN DIEGO
46-123-406 OCCUPANT	6053 MOHLER SAN DIEGO
TERZICH ANTHONY P & PHYLLIS P TRUST C/O PHILIP A	
46-123-406 TERZICH	6052 HODSON SAN DIEGO
46-123-407 MCCOLM JOHN S & JOAN E	4770 ELSA RD SAN DIEGO
46-123-408 POWELL PAUL W & KATHLEEN A	6062 HODSON SAN DIEGO
46-123-503 STEIN FILOMENA N	6072 HODSON SAN DIEGO
46-123-504 CURRY FAMILY TRUST 02-28-96	6075 CRAWFO SAN DIEGO
46-123-505 HOBBS FAMILY TRUST 07-18-08	6065 CRAWFO SAN DIEGO
46-123-506 KLEIN JOSEPH F & DIANNE L	6055 CRAWFO SAN DIEGO
46-123-507 MILLETT WILLIAM & BETSY	6054 MOHLER SAN DIEGO
DUNKIN HAROLD & LUCILLE SURVIVORS TRUST 11-23-	
46-123-508 07	PSC 561 # 1305 FPO AP
46-123-601 SCHROM CHRISTOPHER R & MYUNGEUN L	6074 MOHLER SAN DIEGO
	4701 ELSA RD SAN DIEGO

46-123-602 FALKNER JR FAMILY TRUST 10-20-06	4709 ELSA RD SAN DIEGO
46-123-603 KELLER EDWARD E FAMILY TRUST 09-28-06	4717 ELSA RD SAN DIEGO
46-123-604 GALICIA CHRISTINA	4725 ELSA RD SAN DIEGO
46-123-605 LUCIANO MARK J & SHELLEY	6602 NORMAN SAN DIEGO
46-123-605 OCCUPANT	4733 ELSA RD SAN DIEGO
46-123-606 ISKANDER ISSAC & KATHY L	7699 CAMERO FORT MYERS
46-123-606 OCCUPANT	4741 ELSA RD SAN DIEGO
46-123-607 RILEY NANCY J	4749 ELSA RD SAN DIEGO
46-123-608 FURTAK ROBERT A	237 VIA DEL CE OLIVENHAIN
46-123-608 OCCUPANT	4755 ELSA RD SAN DIEGO
46-123-609 FRANK MARY M	4761 ELSA RD SAN DIEGO
46-123-610 JOHNSON MARK R	4769 ELSA RD SAN DIEGO
46-124-103 SEIBER LESLIE & LYDIA	6076 48TH ST SAN DIEGO
46-124-104 GEERDES LARRY & JANE LIVING TRUST 07-16-01	6066 48TH ST SAN DIEGO
46-124-104 OCCUPANT	6066 48TH ST SAN DIEGO
46-124-105 OCCUPANT	6056 48TH ST SAN DIEGO
RUDAT EWALD & BERTA REVOCABLE FAMILY TRUST	
46-124-105 07-08-94	6642 ARCHWO SAN DIEGO
46-124-203 PEREZ ANGELA	6065 48TH ST SAN DIEGO
46-124-204 TYE FAMILY TRUST 11-11-87 C/O CYNTHIA D WISHERT	15387 MATURI SAN DIEGO
46-124-301 LERUD FAMILY TRUST 06-24-98	225 BLANCHAF EL CAJON
46-124-301 OCCUPANT	4775 ELSA RD SAN DIEGO
46-124-302 WEISS HOWARD J & AMY S	4785 ELSA RD SAN DIEGO
46-124-303 JAWORSKI ROSEMARY M/OCCUPANT	4795 ELSA RD SAN DIEGO
HAAS ANTHONY C & MARY A REVOCABLE TRUST 10-	
46-124-304 24-11	4803 ELSA RD SAN DIEGO
46-124-305 INOUYE TODD H & BLANCA B	4811 ELSA RD SAN DIEGO
46-124-306 BROWNELL GREGORY J & KELLY K	4819 ELSA RD SAN DIEGO
46-124-310 KNECHT BRIAN & EMILY	4835 ELSA RD SAN DIEGO
46-124-311 CELLERE NICHOLAS JR & DONNA K	4827 ELSA RD SAN DIEGO
46-125-201 ULIBARRI DEVIN A & LYNSEY R/OCCUPANT	4841 ELSA RD SAN DIEGO
46-125-202 COPHER JANICE K FAMILY TRUST 09-22-88	4847 ELSA RD SAN DIEGO
46-125-208 ABRAHAMSON KORT	5038 MT HARR SAN DIEGO
46-125-208 OCCUPANT	6032 FENIMOF SAN DIEGO
46-125-209 CAPSTONE PROGRAMS LLC/OCCUPANT	4756 MISSION SAN DIEGO
46-125-210 CORR PATRICK W	6042 FENIMOF SAN DIEGO
46-127-220 GARCIA KIERAN-JOSEPH L & JOCELYN G	6022 FENIMOF SAN DIEGO
46-130-003 CUSH INDUSTRIAL HOLDINGS LLC	10620 TREENA SAN DIEGO
46-130-003 OCCUPANT	5812 MISSION SAN DIEGO
HOME DEPOT U S A INC / COLE HD SAN DIEGO CA L P	
46-130-004 C/O PROPERTY TAX DEPT 6634	P O BOX 10584 ATLANTA
46-130-004 OCCUPANT	5920 FAIRMOL SAN DIEGO
46-130-013 WILLIS ENTERPRISES INC C/O URC MGNT	3525 DEL MAR SAN DIEGO
46-130-017 OCCUPANT	4262 CAMINO SAN DIEGO
46-130-017 WILLIS ENTERPRISES INC C/O URC MGNT	3525 DEL MAR SAN DIEGO
46-130-018 OCCUPANT	4252 CAMINO SAN DIEGO

46-130-018 WILLIS ENTERPRISES INC C/O MARVIN F POER CO 46-130-019 OCCUPANT	P O BOX 8022C DALLAS 4232 CAMINO SAN DIEGO
46-130-019 WILLIS ENTERPRISES INC C/O URC MANAGEMENT BODY BEAUTIFUL CAR WASH INC C/O YOGESH G	3525 DEL MAR SAN DIEGO
46-130-020 MODY C/O YOGESH G MODY 46-130-020 OCCUPANT	4282 CAMINO SAN DIEGO 4282 CAMINO SAN DIEGO
46-130-021 WILLIS ENTERPRISES INC C/O URC MGNT 46-130-022 OCCUPANT	3525 DEL MAR SAN DIEGO 4242 CAMINO SAN DIEGO
46-130-022 WILLIS ENTERPRISES INC C/O URC MGNT 46-132-002 FOUR D PROPERTIES INC	3525 DEL MAR SAN DIEGO 5839 MISSION SAN DIEGO
46-132-002 OCCUPANT 46-132-003 FOUR D PROPERTIES INC C/O DANIEL SMITH	5803 MISSION SAN DIEGO 5839 MISSION SAN DIEGO
46-132-003 OCCUPANT 46-132-004 FOUR D PROPERTIES INC	5821 MISSION SAN DIEGO 5839 MISSION SAN DIEGO
46-132-004 OCCUPANT 46-132-005 OCCUPANT	5835 MISSION SAN DIEGO 5855 MISSION SAN DIEGO
46-132-005 SUN MAU YUN FAMILY TRUST 07-16-87 BLOOD NATHAN A 1992 TRUST 10-27-92 C/O	5236 SEAGROV SAN DIEGO
46-132-006 VONDELL FORRESTER C/O VONDELL FORRESTER 46-132-006 OCCUPANT	16787 BEACH E HUNTINGTON BEACH 5901 MISSION SAN DIEGO
46-132-007 OCCUPANT 46-132-008 AHRENS PARTNERS C/O GREG AHRENS	4470 ALVARAD SAN DIEGO 5959 MISSION SAN DIEGO
46-132-008 OCCUPANT 46-132-009 AHRENS FAMILY TRUST B 10-16-01	5927 MISSION SAN DIEGO 5945 WENRICH SAN DIEGO
46-132-009 OCCUPANT 46-132-011 OCCUPANT	5915 MISSION SAN DIEGO 5935 MISSION SAN DIEGO
46-132-011 SAN DIEGO WINE & SPIRITS INC 46-132-012 OCCUPANT	6549 MISSION SAN DIEGO 4574 ALVARAD SAN DIEGO
46-132-020 OCCUPANT 46-132-021 OCCUPANT	5801 FAIRMOL SAN DIEGO 5805 FAIRMOL SAN DIEGO
46-132-023 BAILLARGEON RANDAL J LIVING TRUST 11-24-97 46-132-023 OCCUPANT	3883 RUFFIN R SAN DIEGO 4460 ALVARAD SAN DIEGO
46-132-024 CONANT PROPERTIES III L P 46-132-025 CONANT PROPERTIES III L P	20322 SW ACA NEWPORT BEACH 20322 SW ACA NEWPORT BEACH
46-132-026 CONANT PROPERTIES III L P COOVER MAXINE M TRUST ET AL C/O RONALD C	20322 SW ACA NEWPORT BEACH
46-132-027 COOVER 46-132-027 OCCUPANT	10495 LIVEWO SAN DIEGO 4450 ALVARAD SAN DIEGO
46-132-028 OCCUPANT 46-132-028 OCEANIC SAN DIEGO LP	4370 ALVARAD SAN DIEGO 7942 ENTRADA SAN DIEGO
46-132-029 OCCUPANT 4772 ALVARADO CANYON BUILDING LLC C/O JACK	4464 ALVARAD SAN DIEGO
46-133-021 LITKE 46-133-021 OCCUPANT	10 DEL MAR CTORINDA 4772 ALVARAD SAN DIEGO
46-133-022 CALIFORNIA NEON PRODUCTS	4530 MISSION SAN DIEGO

46-133-023 CALIFORNIA NEON PRODUCTS	4530 MISSION SAN DIEGO
46-133-024 CALIFORNIA NEON PRODUCTS	4530 MISSION SAN DIEGO
46-133-025 CALIFORNIA NEON PRODUCTS CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	4530 MISSION SAN DIEGO
46-133-026 PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-133-026 OCCUPANT	4561 MISSION SAN DIEGO
46-133-030 ALVARADO CANYON LLC C/O HAROLD HOFFMAN	240 GRAND AV ENGLEWOOD
46-133-030 OCCUPANT	4610 ALVARAD SAN DIEGO
46-133-031 OCCUPANT	4660 ALVARAD SAN DIEGO
46-133-031 STINSON FAMILY PARTNERSHIP	607 WINGSPRE PEACHTREE CITY
46-133-032 AVARADO PROPERTIES LLC	4943 PACIFICA SAN DIEGO
46-133-032 OCCUPANT CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	4670 ALVARAD SAN DIEGO
46-133-033 PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	
46-133-033 PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
CASTER TERRENCE R FAMILY TRUST C/O BRIAN	
46-133-033 CASTER	4607 MISSION SAN DIEGO
46-133-033 OCCUPANT	4579 MISSION SAN DIEGO
46-133-033 OCCUPANT	4680 ALVARAD SAN DIEGO
46-133-033 OCCUPANT	4688 ALVARAD SAN DIEGO
46-133-033 OCCUPANT	4694 ALVARAD SAN DIEGO
46-133-034 FOUR AMIGOS THE C/O PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-133-034 OCCUPANT CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	4560 ALVARAD SAN DIEGO
46-161-001 PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-001 OCCUPANT	4636 MISSION SAN DIEGO
46-161-002 GENERAL TEAMSTERS ASSN/OCCUPANT	4666 MISSION SAN DIEGO
46-161-003 M C H M PROPERTIES LLC/OCCUPANT	4686 MISSION SAN DIEGO
46-161-004 MUSCAT PAUL & VERONICA TRUST 04-29-97	5746 ANTIGUA SAN DIEGO
46-161-004 OCCUPANT CASTER FAMILY ENTERPRISES INC C/O PACIFIC COAST	4656 MISSION SAN DIEGO
46-161-005 COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-005 OCCUPANT	4646 MISSION SAN DIEGO
46-161-006 GRAUER GEORGE M	2516 BRANT ST SAN DIEGO
46-161-006 OCCUPANT	4616 MISSION SAN DIEGO
46-161-007 F N B LAND ENTERPRISES LLC C/O FRED N BROWN	P O BOX 1492 NATIONAL CITY
46-161-007 OCCUPANT SHEET METAL WORKERS INTERNATIONAL ASSN LOCAL	4606 MISSION SAN DIEGO
46-161-008 UNION 206 SHEET METAL WORKERS INTERNATIONAL ASSN LOCAL	4596 MISSION SAN DIEGO
46-161-009 UNION 206/OCCUPANT	4594 MISSION SAN DIEGO
46-161-010 OCCUPANT	4592 MISSION SAN DIEGO
46-161-010 SANDERS NORBERT TR	4343 AVENIDA SPRING VALLEY

46-161-011	CATHOLIC CHARITIES DIOCESE OF SAN DIEGO	349 CEDAR ST SAN DIEGO
46-161-011	OCCUPANT	4581 MISSION SAN DIEGO
46-161-012	CATHOLIC CHARITIES DIOCESE OF SAN DIEGO	349 CEDAR ST SAN DIEGO
46-161-012	OCCUPANT	4587 MISSION SAN DIEGO
46-161-013	CATHOLIC CHARITIES DIOCESE OF SAN DIEGO	349 CEDAR ST SAN DIEGO
46-161-013	OCCUPANT	4575 MISSION SAN DIEGO
46-161-014	GOOVILLE LLC C/O ROYCE NICHOLAS	3903 MEADE A SAN DIEGO
46-161-014	OCCUPANT	4593 MISSION SAN DIEGO
	CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	
46-161-015	PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-015	OCCUPANT	4599 MISSION SAN DIEGO
	CASTER FAMILY ENTERPRISES INC C/O PACIFIC COAST	
46-161-016	COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-016	OCCUPANT	4607 MISSION SAN DIEGO
	CASTER FAMILY ENTERPRISES INC C/O PACIFIC COAST	
46-161-017	COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-017	OCCUPANT	4619 MISSION SAN DIEGO
	CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	
46-161-018	PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-018	OCCUPANT	4627 MISSION SAN DIEGO
	CASTER FAMILY ENTERPRISES INC C/O PACIFIC COAST	
46-161-019	COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-019	OCCUPANT	4635 MISSION SAN DIEGO
	CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	
46-161-020	PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-020	OCCUPANT	4643 MISSION SAN DIEGO
	CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	
46-161-021	PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-021	OCCUPANT	4651 MISSION SAN DIEGO
	CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	
46-161-022	PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-022	OCCUPANT	4659 MISSION SAN DIEGO
	CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	
46-161-023	PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-023	OCCUPANT	4667 MISSION SAN DIEGO
	CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	
46-161-024	PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-024	OCCUPANT	4675 MISSION SAN DIEGO
	CASTER TERRENCE R FAMILY TRUST 10-01-71 C/O	
46-161-025	PACIFIC COAST COMMERCIAL	P O BOX 42095 SAN DIEGO
46-161-025	OCCUPANT	4683 MISSION SAN DIEGO
	STADIUM PARK EAST ASSOCIATION INC C/O	
46-161-026	TERRENCE R CASTER	4607 MISSION SAN DIEGO
	STADIUM PARK EAST ASSOCIATION INC C/O	
46-161-027	TERRENCE R CASTER C/O TERRENCE R CASTER	4607 MISSION SAN DIEGO
	MISSION VALLEY CHURCH OF THE	
46-162-004	NAZARENE/OCCUPANT	4750 MISSION SAN DIEGO

46-162-007 D R G DANSKE REAL ESTATE GROUP LLC/OCCUPANT CASTER TERRENCE R TR C/O PACIFIC COAST	4720 MISSION SAN DIEGO
46-162-008 COMMERCIAL	P O BOX 42095 SAN DIEGO
46-162-008 OCCUPANT	4760 MISSION SAN DIEGO
76-022-678 OCCUPANT	5801 FAIRMOL SAN DIEGO
76-022-689 LERUS CORPORATION C/O TIO LEO'S MEXICAN REST	6333 MISSION SAN DIEGO
76-022-696 MORAN FRANK <DBA ALL-PRO ASPHALT>	3401 ADAMS A SAN DIEGO
76-022-696 OCCUPANT	4574 ALVARAD SAN DIEGO
76-022-697 AKHAVEN MAHMOUD	834 W GRAPE ! SAN DIEGO
76-022-697 OCCUPANT	4574 ALVARAD SAN DIEGO
Allied Gardens Community Council	PO BOX 60042 SAN DIEGO
Ann Meador	5466 Chaparaj, SAN DIEGO
Brian and Monet Desrosiers	5469 Chaparaj, SAN DIEGO
California Department of Transportation	4050 TAYLOR S SAN DIEGO
County of San Diego	5570 OVERLAN SAN DIEGO
Genoveva S. and Eugene Martinez Jr.	5452 Chaparaj, SAN DIEGO
Lawrence F. and Judith A. Blick	5458 Chaparaj, SAN DIEGO
Marilyn Reed	6266 SEAMAN SAN DIEGO
Metropolitan Transit System C/O TIM ALLISON MANAGER OF REAL ESTATE ASSETS	1255 IMPERIAL SAN DIEGO
PAUMA TRIBAL COUNCIL - Pauma Band of Luiseno Indians	1010 PAUMA F PAUMA VALLEY
Potter and Associates	4975 MILTON ! SAN DIEGO
San Diego Association of Governments / SUSAN BALDWIN	401 B STREET S SAN DIEGO
San Diego Unified School District C/O OFFICE OF SPECIAL PROJECTS - SARAH HUDSON	4100 NORMAL SAN DIEGO

State	Zip
CA	92037
CA	92108
CA	93536
CA	92108
CA	92108
CA	92108
CA	91942
NY	10019
CA	92108
CA	92122
CA	92108
CA	92124
CA	92126
CA	92108
CA	92108
CA	92108
CA	92130
CA	92108
CA	92108
CA	92108
CA	92119
CA	92108
CA	92123
CA	92108
CA	92130
CA	92108
CA	92591
IN	46038
CA	92250
CA	92108
CA	92014
CA	92108
CA	92108
CA	92119
CA	91935
CA	92108
CA	92108
CA	92108

CA	92124
CA	92108

CA	92108
CA	92108
CA	92108
CA	92186
CA	92108
CA	92071
CA	92108

FL	34201
CA	92108
CA	92108
CA	92108
CA	91942
CA	92108
CA	92123
CA	92120
CA	92108
CA	92120
CA	92108
CA	91006
CA	92108
CA	92108
CA	92108
CA	92154

NV	89120
CA	92130
CA	92108

CA	92108
CA	92069
CA	92131
CA	92108

CA	92131
CA	95926
HI	96753
CA	92037
CA	92037
CA	92108
CA	92037
CA	92037

CA	92037
CA	92024
CA	92120
TN	38101
CA	92120
CO	80206
CA	92120
CO	80206

CA	92120
CA	92120
CA	90670

CA	92120
----	-------

CA	92131
CA	92120
CA	92120
CA	91942
CA	92120

CA	91942
CA	91188
CA	92120
CA	92150
CA	92120

CA	92037
CA	92120

CA	92037
CA	92120

CA 92037
CA 92120

CA 92037
CA 92120
CA 92120
CA 92120
CA 92116
CA 92120
CA 92120
CA 92270

CA 92101
CA 92120
CA 92120

CA 94043
CA 92120
CA 92120
CA 92120
CA 92120
CA 92120
CA 92270
CA 92037
CA 92120
CA 92037
CA 92120
CA 92120
CA 92120
CA 92119
CA 92120
CA 92120
CA 92128
CA 92120

CA 92020
CA 94549
CA 92120
CA 92019
CA 92120
CA 92120
CA 92070
CA 92115
CA 92120
CA 94549
CA 92107

CA	92120
CA	92067
CA	92120
CA	92078
CA	92078
CA	92120
IL	60067
CA	92120
CA	92123
CA	92120
CA	92075
CA	92120
CA	92075
CA	92120
CA	92116
CA	91103
CA	92120
CA	92120
CA	92127
CA	92104
CA	92120
CA	92128
CA	92120
CA	92563
CA	92120
CA	92563
CA	92120
CA	92019

CA	92120
CA	91950
CA	92120
CA	92120
CA	92071
CA	92120
MD	20855
CA	92120
IN	46055
CA	92101
CA	92019
CA	92019
CA	92120
CA	92101
CA	92120
CA	92101
CA	92106
CA	92120
CA	92106
CA	92120
CA	92101
CA	92120
CA	92021
CA	92120
CA	92101
CA	92101
CA	92101
CA	92120
CA	92142
CA	92120
CA	92120
CA	92101
CA	92120

CA	92021
CA	92101
CA	91977
CA	92120
CA	92110
CA	92120
CA	92120
CA	92120
CA	92021
CA	92120
CA	92131
CA	92131
CA	92120
CA	92120
CA	92064
CA	92120
CA	92120
MN	55720
CA	92120
CA	92120
CA	91950
CA	92120
CA	92120
CA	92040
CA	92120
CA	92124
CA	92120
CA	92120
CA	92071
CA	92130
CA	91977

CA	92111
CA	92120
CA	92071
CA	92119
CA	92067
CA	92120
CA	92120
CA	92120
CA	92037
CA	92120
CA	92037
CA	92120
CA	92262
CA	92120
CA	92123
CA	92120
CA	92120
CA	94566
CA	92120
CA	92120
CA	92120
CA	92260
CA	92260
CA	92126
CA	92118
CA	92120
CA	92120
CA	92120
CA	92627
CA	92120
CA	92106
CA	92106

CA	92120

CA	92117
CA	92120
CA	92120
CA	92120
CA	92122
CA	92120
CA	95125
CA	92120
CA	92120

CA	92109
CA	92660
CA	92120
CA	92660
CA	92120
CA	92660
CA	92120
CA	92660
CA	92660
NV	89703
CA	92120
NV	89703
CA	92120
NV	89703
CA	92120

CA	92142
CA	92120
CA	92123
CA	92120
CA	92103
CA	92120
CA	92660
CA	92660
CA	92122
CA	92120
CA	92106
CA	92120
CA	92109
CA	92120
CA	90040
CA	92120
CA	92120
CA	92120
CA	91950
CA	92120
CA	92071
CA	92120
CA	92120
CA	92120
CA	92115
CA	91910
CA	91910
CA	95117
CA	92120
CA	92111
CA	92120
CA	92120

CA	92120
CA	92117
CA	92111
CA	92120
CA	92120
CA	92120
UT	84003
CA	92120
CA	91773
CA	92120
CA	92120
CA	91944
CA	92120
MT	59759
CA	92120
CA	92131
CA	92120
MT	59759
CA	92120
MT	59759
CA	92120
CA	91188
CA	92120
CA	91941
CA	92120
CA	91436
CA	92120
CA	91436
CA	92120
CA	92120

CA 92120

CA 91941

CA 92120

TX 76307

CA 92120

CA 92120

CA 92020

CA 92120

CA 92122

CA 92122

CA 92120

CA 92122

CA 92120

CA 92122

CA 92122

CA 92120

CA 91901

CA 92120

96310

CA 92120

CA 92120

TX	75380
CA	92108
CA	92130
CA	92108
CA	92108
CA	92130
CA	92108
CA	92130
CA	92120
CA	92130
CA	92647
CA	92120
CA	92123
CA	92120
CA	92660
CA	92660
CA	92660
CA	92131
CA	92120
CA	92120
CA	92127
CA	92120
CA	94563
CA	92120
CA	92120

CA	92120
CA	92120
CA	92120
CA	92142
CA	92120
NJ	07631
CA	92120
CA	92120
GA	30269
CA	92109
CA	92120
CA	92142
CA	92142
CA	92120
CA	92142
CA	92120
CA	92142
CA	92120
CA	92120
CA	92120
CA	92124
CA	92120
CA	92142
CA	92120
CA	92101
CA	92120
CA	91951
CA	92120
CA	91977

CA	92101
CA	92120
CA	92101
CA	92120
CA	92101
CA	92120
CA	92116
CA	92120
CA	92142
CA	92120
CA	92142
CA	92120
CA	92142
CA	92120
CA	92142
CA	92120
CA	92142
CA	92120
CA	92142
CA	92120
CA	92142
CA	92120
CA	92142
CA	92120
CA	92142
CA	92120

CA 92120

CA 92142

CA 92120

CA 92120

CA 92120

CA 92116

CA 92120

CA 92101

CA 92120

CA 92160

CA 92120

CA 92120

CA 92110

CA 92123

CA 92120

CA 92120

CA 92120

CA 92101

CA 92061

CA 92110

CA 92101

CA 92103



THE CITY OF SAN DIEGO

April 24, 2015

RE: Notice of proposed Grantville Focused Plan Amendment subject to SB 18; Project No. **346289**

To Whom It May Concern:

Enclosed for your review and comment is a draft of the proposed changes to the Navajo Community Plan for Project No. **346289**.

The Grantville Focused Plan Amendment (FPA) area consists of approximately 280 acres within the Navajo Community Planning Area. The Grantville FPA was initiated by the City Council in June 2007, following which, the Grantville Stakeholders Committee was formed and an extensive community outreach process began. The Grantville FPA was developed through a series of design charrettes and nearly eight years of stakeholder meetings in the Navajo community. The Grantville FPA includes a Community Plan Amendment (CPA) to the Navajo Community Plan, processing of rezones to implement the plan amendment, certification of the Program Environmental Impact Report (PEIR) SCH No. 2013111017 including adoption of the Findings, a Statement of Overriding Considerations, and a Mitigation, Monitoring and Reporting Program. The Proposed Grantville FPA will provide direction for future development and has been guided by the citywide policy direction contained in the City of San Diego General Plan.

Objectives of the Grantville FPA include: to promote Transit Oriented Development (TOD) within walking distance to the Grantville Trolley Station, promote revitalization of properties which are underutilized; promote a multi-modal transportation strategy including walkable and bicycle-friendly streets; provide additional market-rate and affordable housing opportunities consistent with a land use pattern that promotes infill development; and facilitate implementation of the San Diego River Park Master Plan.

The proposed amendment to the Navajo Community Plan (including the Grantville Focused Plan Amendment) is available online at:

http://www.sandiego.gov/planning/community/cpu/grantvillemasterplan/pdf/draft_navajo_cp_ame ndment.pdf

The current Navajo Community Plan is available online at:

<http://www.sandiego.gov/planning/community/profiles/navajo/plan.shtml>

You have 45 days from the date you receive this notification to request consultation by calling Seth Litchney, Senior Planner in the Planning Department at 619-236-6892. You may also request consultation via email to slitchney@saniego.gov or regular mail sent to Seth Litchney, Planning Department, 1222 First Ave., MS 413, San Diego, CA, 92101.

Written comments on the proposed Grantville Focused Plan Amendment must be sent to the following address no later than **June 9, 2015**: Seth Litchney, Planning Department, 1222 First Ave., MS 413, San Diego, CA, 92101 or email your comments to **slitchney@saniego.gov** **Navajo Community Plan Amendment** in the subject line.

The proposed project has been scheduled for public hearing at Planning Commission on May 14, 2015. The proposed project has not yet been scheduled for public hearing at City Council. Once the public hearing for City Council has been scheduled, notice of the hearing date will be issued at least 10 days prior to the hearing. Should you have any questions, please contact **Seth Litchney** at **(619) 236-6892** or slitchney@saniego.gov.

Sincerely,

Jenny An
Associate Planner
Planning Department
1222 First Avenue, MS 413
San Diego, CA 92101